



IM AQ6360-01EN 1st Edition Thank you for purchasing the AQ6360 Optical Spectrum Analyzer. This instrument enables high speed measurement of the optical properties of LD and LED light sources, optical amps, and other devices.

This user's manual describes the instrument's functions, operating procedures, and handling precautions, and provides other important information for use of the instrument. For correct operation, please read this manual thoroughly before use. After reading this manual, keep it in a convenient location for quick reference in the event a question arises during operation.

List of Manuals

The following manuals, including this one, are provided as manuals for the AQ6360. Please read all manuals.

Manual Title	Manual No.	Description
AQ6360 Optical Spectrum Analyzer User's Manual	IM AQ6360-01EN	This manual. The manual is located on the CD included in your package (pdf format). Explains all functions and operating procedures of the AQ6360 except remote control and program functions.
AQ6360 Optical Spectrum Analyzer Getting Started Guide	IM AQ6360-02EN	This guide explains the handling precautions, installation procedure, basic operations, and specifications of this instrument.
AQ6360 Optical Spectrum Analyzer Remote Control User's Manual	IM AQ6360-17EN	The manual is located on the CD included in your package (pdf format).Explains functions for controlling the instrument with communication commands and program functions.
Model AQ6360-01 AQ6360 Optical Spectrum Analyzer Limited model User's Manual	IM AQ6360-51EN	Explains the specifications of the limited model of the AQ6360.
AQ6360 Optical Spectrum Analyzer	IM AQ6360-92Z1	Document for China.

The "EN" in the manual number is the language code.

Contact information of Yokogawa offices worldwide is provided on the following sheet.

Document Description	Description
PIM 113-01Z2	List of worldwide contacts

Notes

- The contents of this manual are subject to change without prior notice as a result of improvements in the instrument's performance and functions. Display contents illustrated in this manual may differ slightly from what actually appears on your screen.
- Every effort has been made in the preparation of this manual to ensure the accuracy of its contents. However, should you have any questions or find any errors, please contact your nearest YOKOGAWA dealer.
- Copying or reproducing all or any part of the contents of this manual without the permission of YOKOGAWA is strictly prohibited.

Trademarks

- Microsoft and Windows are registered trademarks or trademarks of Microsoft Corporation in the United States and/or other countries.
- Adobe and Acrobat are registered trademarks or trademarks of Adobe Systems incorporated.
- In this manual, the
 ß and TM symbols do not accompany their respective registered trademark or trademark names.
- Other company and product names are registered trademarks or trademarks of their respective companies.


Revisions

1st Edition: April 2018

Conventions Used in This Manual

Safety Markings

The following markings are used in this manual.



Note Calls attention to inform that is important for proper operation of the instrument.

Notations Used on Pages Describing Operating Procedures

On pages that describe the operating procedures in Chapter 2 through 7, the following notations are used to distinguish the procedures from their explanations.

Procedure

This subsection contains the operating procedure used to carry out the function described in the current chapter. All procedures are written with inexperienced users in mind; experienced users may not need to carry out all the steps.

Explanation

This subsection describes the setup parameters and the limitations on the procedures.

Characters and Terminology Used in Procedural Explanations


Bold alphanumeric characters in procedural explanations indicate characters appearing near panel controls and characters of the control menu items shown on the screen.

Unit

k: Denotes "1000."	Example: 100kS/s
K: Denotes "1024."	Example: 459KB (file data size)

Workflow

The figure below is provided to familiarize the first-time user with the basic workflow for operating the product. For the details of each item, see the relevant section in IM AQ6360-01EN or IM AQ6360-02EN.



* IM AQ6360-02EN

Contents

List of Manuals	i
Conventions Used in This Manual	
Workflow	v

Chapter 1 Features

1.1	System Configuration	1-1
1.2	Feature Summary	1-2

Chapter 2 Measurement Preparation

<u>^</u> 2.1	Wavelength Calibration	2-1
2.2	Resolution calibration	2-6
2.3	Measurement Precautions	2-11

Chapter 3 Measurement


3.1	Auto Measurement	
3.2	Setting the Horizontal and Vertical Scales	
3.3	Sub Scale	
3.4	Setting the Reference Level	
3.5	Setting the Center Wavelength (Center Frequency)	
3.6	Setting the Sweep Span	3-21
3.7	Setting the Wavelength (Frequency) Resolution	
3.8	Setting the Sampling Points and Interval	
3.9	Setting the Sensitivity	
3.10	Setting the Sweep Speed	3-30
3.11	Setting the Average Times	
3.12	Selecting Traces	
3.13	Starting a Measurement (Sweep)	
3.14	Specifying a Sweep Range	
3.15	Pulse Light Measurement	
3.16	Smoothing	

Chapter 4 Waveform Display

4.1	Zooming a Waveform	4-1
4.2	Updating or Fixing Waveforms	
4.3	MAX/MIN HOLD Display	4-10
4.4	Sweep Average	4-12
4.5	Displaying Calculated Waveforms	4-14
4.6	Normalized Display	4-20
4.7	Curve Fitting	
4.8	Power Spectral Density Trace	4-27
4.9	Marker Display	4-29
4.10	Displaying a Split Screen	
4.11	Noise Mask	4-51
4.12	Copying and Clearing Traces	4-53
4.13	Single Search	
4.14	Multi Search	4-59

Contents

Chapter 5	Analys	sis	
	5.1 S	pectral Width Measurement	5-1
	5.2 N	lotch Width Measurement	5-4
	5.3 S	MSR Measurement	5-6
	5.4 P	Power Measurement	5-9
	5.5 D	FB-LD, FP-LD, and LED Measurement	5-11
	5.6 P	MD Measurement	5-13
	5.7 V	VDM Transmission Signal Analysis	5-15
	5.8 C	Optical Amp Gain and NF Measurement	5-22
	5.9 C	Optical Filter Characteristics Measurement	5-30
	5.10 E	diting the Grid Table	5-41
	5.11 N	leasurement of Level Fluctuations in Single- Wavelength Light (0 nm Sweeping)	5-45
	5.12 S	pecifying an Analysis Range	5-48
	5.13 C	Correcting the Displayed Values	5-51
Chapter 6	Savino	g and Loading Data	
	-	ISB Storage Device	6-1
Â		aving and Loading Waveform Data	
		aving and Loading Waveform Data (All Trace)	
		aving and Loading Setting Data	
		aving and Loading Analysis Results Data	
		aving and Loading Program Data	
		aving Screen Capture Data	
		ile Operations	
Shapter /	7.1 S	Operations Increen Display	
		Registering User Keys	
		pata Initialization	
		lelp	
		Registering and Recalling Character Strings	
		ocking the Keys	
		Other Settings	
	7.8 C	Displaying the System Information	1-21
Appendix	A		
	Appendix		
	Appendix		
	Appendix	-	
	Appendix	-	
	Appendix		
	Appendix		
	Appendix	7 Function Menu Tree Diagram	App-51
Index			



1.2 Feature Summary

Measurement (Details in chapter 3)

Sweep Settings

Optical power at different wavelengths can be measured while changing the wavelength automatically.

The available sweep modes are (1) single sweep, which makes a single measurement, (2) repeat sweep, which repeats measurements using the same measurement conditions, and auto measurement, which makes measurements by automatically setting the measurement conditions to the optimal conditions. If the optimal measurement conditions are unknown, auto measurement is convenient.

In addition, sweeping between markers, which makes measurements within the specified sweep wavelength range, and 0 nm sweeping, which measures the variation in the level over time with a fixed wavelength measurement point are available.

The 0 nm sweeping function is useful for aligning the optical axis when a light source is input into an optical fiber.

Measurement Condition Settings

Measurements can be performed by setting various conditions.

In addition to center wavelength, span, wavelength resolution, and measurement sensitivity, a smoothing function that reduces measurement waveform noise and a function for switching between air wavelength and vacuum wavelength are available. By using the one-action key functions, you can set measurement conditions using the data of the active trace waveform (currently displayed waveform). To use them, a waveform must be displayed in the active trace.

One-Action Keys

•	
One-action key name	Description
Peak Level \rightarrow Ref Level	The reference level is set to the peak level of the active trace measurement waveform.
$Marker \to RefLevel$	The reference level is set to the moving marker level.
Peak WL → Center	The center wavelength or center frequency is set to the peak wavelength or peak frequency of the active trace measurement waveform.
$\text{Mean WL} \rightarrow \text{Center}$	The center wavelength or center frequency is set to the RMS 20 dB center wavelength or center frequency of the active trace measurement waveform.
View Scale \rightarrow Measure	The measurement scale (CENTER, START, STOP, SPAN) of the next sweep to the zoom scale currently displayed.
Marker \rightarrow Center	The center wavelength or center frequency is set to the moving marker wavelength or frequency.
$\Delta\lambda \rightarrow \text{Span}$	The sweep span is set to RMS 20 dB span × 6 of the active trace measurement waveform.
Marker L1-L2 \rightarrow Span	The sweep span is set to the span between line markers 1 and 2.
$Peak \to Zoom\ Ctr$	The center wavelength of the zoom display is set to the peak wavelength of the active trace measurement waveform.
Marker \rightarrow Zoom Ctr	The center wavelength of the zoom display is set to the moving marker wavelength.
Marker L1-L2 → Zoom Span	The sweep span of the zoom display is set to the span between line markers 1 and 2.

Display (Details in chapter 4)

Display Mode

Measured waveforms and calculated waveforms are shown in the waveform display area of the screen.

A function that splits the waveform display area into two screens and a function that displays analysis results in data tables are also available.

Vertical Scale

The vertical axis of the waveform display area has a level scale and a sub level scale, and each scale can be set to a log scale or linear scale to display optical power levels. In addition, a power spectral density display function, which shows power per nm (dB/ nm) and a noise mask function, which masks levels at or less than the specified value are available.

Horizontal Scale

The horizontal scale of the waveform display area can be set to wavelength (nm) or frequency (THz).

You can specify a wavelength to zoom in on a waveform or pinch out or pinch in on the touch panel to adjust the zoom display.

While the zoom display is shown, an overview window (entire waveform) is shown at the bottom of the waveform display area where you can view the zoom range.

Trace (Details in chapters 3 and 4)

Display Function

This instrument has seven independent traces in which measured waveforms and calculated waveforms are drawn.

For each trace, you can turn the waveform display on and off as well as set the trace to write mode or calculation mode.

Write mode is further divided into (1) MAX/MIN HOLD mode, which detects and writes the maximum and minimum values of each sweep, (2) roll average (sweep average) mode, which takes a cumulative average for each sweep and writes the result, and (3) FIX mode in which no writing takes place.

In calculation mode, calculated results such as calculation between traces, normalization of waveforms, and approximation (curve fitting) of waveforms can be displayed in another trace.

Marker and Search (Details in chapter 4)

Marker

The marker function is used to place the moving marker ($\mathbf{\nabla}$) on a displayed waveform and show the wavelength and level at the marker position.

The function can be used to easily search for peak wavelengths and peak levels. Further, by setting up to 1024 fixed markers, you can measure the wavelength difference or level difference between adjacent fixed markers and between the moving marker and a fixed marker.

In addition to the normal marker, there are two vertical and horizontal line markers (wavelength line marker and level line marker) and advanced markers.

Wavelength line markers show wavelengths and wavelength difference while level line markers show levels and level difference. Line markers can be used to specify a sweep range or analysis range.

Advanced markers can be used to display the power value per normalization bandwidth (power spectral density) and integrated power of a specified range.

Search

The peak/bottom search function can be used to detect waveform peak levels and bottom levels.

The function has two search modes: single, in which a single peak or a single bottom of the measured waveform's level are detected, and multi, in which multiple peaks and bottoms are detected in a single search.

Markers are displayed at the peak and bottom points.

There is also an auto search function that automatically performs peak/bottom searches during each sweep. This is useful when you want to observe the changes to the peak and bottom levels during repeat sweeping.

Data Analysis (Details in chapter 5)

Analysis Function

The following analysis functions are available.

Spectral Width Measurement

The spectral width and center wavelength can be displayed using the following four calculation methods.

- THRESH
- ENVELOPE (envelope curve)
- RMS
- PEAK RMS

Notch Width Measurement

Passband/notch width can be analyzed by measuring filters with V-shaped or U-shaped wavelength characteristics.

Device Analysis

Light source parameter analysis can be performed by measuring the DFB-LD, FP-LD, and LED light sources.

- SMSR measurement of DFB-LD Side mode suppression ratio (SMSR) can be analyzed by measuring a DFB-LD.
- Total power measurement of FP-LD and LED Optical power can be analyzed by integrating the measured waveform levels.

PMD Measurement

A wideband light source such as an ASE or high-output LED light source can be combined with a polarizer, polarization controller, and analyzer to analyze the polarization mode dispersion (PMD) of the DUT such as an optical fiber.

WDM Analysis

WDM transmission signals can be analyzed. The OSNR of a DWDM transmission system with 50 GHz spacing can also be analyzed. The wavelength, level, wavelength spacing, and OSNR of up to 1024 channels of WDM signals are measured collectively, and the analysis results are shown in a data table.

Optical Amplifier Measurement

The signal light to an optical amplifier and the output light from the amplifier can be measured to analyze the gain and noise figure (NF) of the amplifier.

Optical Filter Characteristics Measurement

The input light to an optical filter and the output light from the filter can be measured to analyze the characteristics of the filter.

Analysis is possible not only for single-mode optical filters but also multi-mode WDM filters.

Auto Measurement (Details in IM AQ6360-17EN)

Programming

You can select program commands freely and register up to 64 programs (200 steps/ program).

The program function can be used to control external devices connected to the Ethernet interface of this instrument.

Others

Wavelength Calibration (Details in chapter 2)

The built-in reference light source (/LFC, /LSC option) or an external light source can be used to perform wavelength calibration of the instrument.

Resolution Calibration (Details in chapter 2)

In general, the resolution bandwidth accuracy affects measurement results. In resolution calibration, an equivalent noise bandwidth can be measured and used as the resolution bandwidth.

USB Mouse Operation (Details in IM AQ6360-02EN)

You can connect a USB mouse to perform the same operations that you can perform by tapping the instrument's touch panel. Connect a USB mouse to a USB port on the instrument's front panel.

User Keys (Details in chapter 7)

Frequently used keys can be registered in the function menu (user keys). By registering user keys, you can execute specific operations with less steps. Up to 24 keys can be registered. By default, none of the keys are registered.

Data Initialization (Details in chapter 7)

Settings can be reset to their factory defaults.

Help (Details in chapter 7)

Explanations of various settings, function menus, and keys can be shown on the instrument's screen.

Key Lock (Details in chapter 7)

Operation of keys other than the registered user keys can be locked to prevent operation mistakes by the user.

Remote (Details in IM AQ6360-17EN)

This instrument can be remotely controlled over a network from a PC or other controllers.

2.1 Wavelength Calibration



WARNING

The instrument has a built-in reference light source for wavelength calibration (/ LFC, /LSC option), and infrared light is always being output from the optical output connector. Never look into the optical output connector. Infrared light entering the eyes can cause severe injury and loss of vision.

French



AVERTISSEMENT

Cet instrument dispose d'une source de lumière de référence (/LFC, /LSC option) intégrée pour les ajustements d'alignement. La lumière infrarouge est toujours émise depuis le connecteur de sortie optique. Ne regardez jamais directement dans le connecteur de sortie optique. La lumière infrarouge risquerait de gravement vous blesser ou de provoquer une perte de vision.

Procedure


Calibrating the Wavelength with the Built-in Reference Light Source (/LFC, /LSC Option)

1. Turn on the instrument.

Turn on the MAIN POWER switch and then press the POWER switch.

For instructions on how to turn on and off the power, see section 2.4 in IM AQ6360-02EN.

- Connect the instrument's optical input connector and optical output connector using a 9.5/125 μm SM (single mode) optical fiber.
- 3. Tap **Menu**. The Main Menu window appears.
- 4. Tap SYSTEM. The function menu appears.
- 5. Tap Wavelength Calibration.



6. Tap Built-in Source.

- 7. Tap Execute. The message "Calibration now! Please wait" appears, and wavelength calibration begins. It will take approximately 1 minute for the wavelength calibration to complete. When it finishes successfully, the message "Wavelength Calibration is completed successfully" appears.
- **8.** Tapping **Cancel** while the wavelength calibration is being executed cancels the calibration.

Note_

- Be sure to execute wavelength calibration after warm-up when you turn on the instrument.
- If the instrument's wavelength error is greater than or equal to ±5 nm, wavelength calibration using the built-in reference light source is not possible.
 (Because readjustment is required, contact your nearest YOKOGAWA dealer.)

Calibrating the Wavelength Using an External Light Source

In addition to the built-in reference light source, the instrument can be calibrated using a light source that you provide. However, the following light sources cannot be used for wavelength calibration.

Laser Type

- · When the specified wavelength is different from that of the calibration light source
- If the instrument's wavelength error is greater than or equal to ±5 nm, readjustment is necessary. Contact your nearest YOKOGAWA dealer.
- · If the calibration light source level is less than or equal to -40 dBm

Emission Line Light Source Type

- · When the specified wavelength is different from that of the calibration light source
- If multiple emission lines are included in the calibration wavelength ±0.5 nm range
- If the instrument's wavelength error is greater than or equal to ±0.5 nm, readjustment is necessary. Contact your nearest YOKOGAWA dealer.
- If the calibration light source level is less than approximately -65 dBm (varies depending on the wavelength)

Gas Cell Absorption Line Type

 When using a reference light source with multiple absorption lines if the instrument's wavelength deviation is greater than the wavelength spacing of the absorption lines (because the adjacent absorption line will be assumed to be the reference wavelength)


Connecting the External Light Source

1. Turn on the instrument.

Turn on the MAIN POWER switch and then press the POWER switch.

For instructions on how to turn on and off the power, see section 2.4 in IM AQ6360-02EN.

2. Connect the external light source's optical output connector to the instrument's optical input connector using a single mode optical fiber.



Optical fiber

Note_

- Use a 9.5/125 µm single mode optical fiber.
- If you have to use an optical fiber with a large core diameter, such as when using an external emission line light source, use an optical fiber with a core diameter of 100 µm or less. Otherwise, wavelength calibration will not be performed correctly.


Setting the Type of External Light Source and the Calibration Wavelength Value

- 3. Tap \equiv Menu. The Main Menu window appears.
- 4. Tap SYSTEM. The function menu appears.
- 5. Tap Wavelength Calibration.

Set the type of external light source (laser, emission line spectrum, gas cell absorption line) and the calibration wavelength value. There are three methods to set the wavelength value.


Laser Type

- 6. Tap External Laser. A parameter input window appears.
- **7.** Set the wavelength value of the laser in the parameter input window. The selectable wavelength range is 1200 nm to 1650 nm.
- 8. Tap nm/ENT. The wavelength value is set.
- 9. Tap Execute. The message "Calibration now! Please wait" appears, and wavelength calibration begins. When the wavelength calibration finishes successfully, the message "Wavelength Calibration is completed successfully" appears.
- **10.** Tapping **Cancel** while the wavelength calibration is being executed cancels the calibration.




Gas Cell Absorption Line Type

- 6. Tap External Gas Cell. A parameter input window appears.
- **7.** Set the wavelength value of the gas cell absorption line in the parameter input window. The selectable wavelength range is 1200 nm to 1650 nm.
- 8. Tap nm/ENT. The wavelength value is set.
- 9. Tap Execute. The message "Calibration now! Please wait" appears, and wavelength calibration begins. When the wavelength calibration finishes successfully, the message "Wavelength Calibration is completed successfully" appears.
- **10.** Tapping **Cancel** while the wavelength calibration is being executed cancels the calibration.




Emission Line Light Source Type

- 6. Tap Emission Line. A parameter input window appears.
- **7.** Set the wavelength value of the emission line light source in the parameter input window. The selectable wavelength range is 1200 nm to 1650 nm.
- 8. Tap nm/ENT. The wavelength value is set.
- 9. Tap Execute. The message "Calibration now! Please wait" appears, and wavelength calibration begins. When the wavelength calibration finishes successfully, the message "Wavelength Calibration is completed successfully" appears.
- **10.** Tapping **Cancel** while the wavelength calibration is being executed cancels the calibration.



When Using the Instrument's Internal Calibration Wavelength Value

- 7. Tap Calibration WL Select. The function menu changes to display the wavelength value.
- 8. Tap the appropriate wavelength value.
- 9. Tap Execute. The message "Calibration now! Please wait" appears, and wavelength calibration begins. When the wavelength calibration finishes successfully, the message "Wavelength Calibration is completed successfully" appears.
- **10.** Tapping **Cancel** while the wavelength calibration is being executed cancels the calibration.



Note _

There is no need to calibrate at multiple wavelengths. If calibration is performed at multiple wavelengths, only the last calibration result is applied.

2.2 Resolution calibration

Procedure

The resolution of the instrument can be calibrated using a light source that you provide.

Connecting the External Light Source


1. Turn on the instrument.

Turn on the $\ensuremath{\text{MAIN POWER}}$ switch and then press the $\ensuremath{\text{POWER}}$ switch.

For instructions on how to turn on and off the power, see section 2.4 in IM AQ6360-02EN.

 Connect the external light source's optical output connector to this instrument's optical input connector using a 9.5/125 µm SM (single mode) optical fiber.





Optical fiber

Note .


For the light source, use a stabilized single-mode laser light.

Set the optical output power to -20 dBm or higher.

Use a light source with a level stability of 0.1 dBp-p or less and an output line width of 5 MHz or less.

- 3. Tap = Menu The Main Menu window appears.
- 4. Tap SYSTEM. The function menu appears.
- **5.** Tap **More** to display the More 4/4 function menu.
- **6.** Tap **Res BW Calibration**. A resolution calibration function menu and a message explaining how to perform resolution calibration appear.

The message also contains the wavelength value of the previous resolution calibration.






If calibration has not been performed or has been cleared, "No User Cal" will appear.


Executing Resolution Calibration

7. Tap **Execute**. The message "Res BW calibration Step @/4 Please wait" (where @ is a number between 1 and 4) appears, and resolution calibration begins.

When the resolution calibration finishes successfully, the message "Resolution bandwidth calibration is completed successfully" appears.

8. Tapping **Cancel** while resolution calibration is being executed cancels the calibration.






<1 eas	s. Conditions>			SPEED: 1x
	ART: 1546.840 nm	STOP: 1551.840 nm	CENTER: 1549.340 nm	SPAN: 5.0 nm
RES	ES: 0.1 nm	SENS: MID	AVG: 1	SMPL: 501(A)

Clearing the Resolution Calibration Value

7. Tap Initialize. The calibration value will be cleared.




Explanation

Typically the filter response of an optical spectrum analyzer is not rectangular, and thus the resolution bandwidth differs slightly from the equivalent noise bandwidth. The resolution calibration function measures the equivalent noise bandwidth at each resolution setting and internally sets the resolution bandwidth to the result.


The resolution bandwidth accuracy affects the results of noise measurements and the results of optical power measurements of wideband light sources. In detail, the resolution bandwidth is used when the following analysis and computation functions are executed.

- WDM analysis
- EDFA-NF (optical amp gain, NF measurement)
- Power analysis
- OSNR and total power of DFB-LD analysis
- · Total power of FP-LD analysis
- · Total power of LED analysis
- · Power spectral density marker, integrated power marker

Before resolution calibration




After resolution calibration



2.2 Resolution Calibration

Measurement resolution used in the analysis algorithm (e.g. EDFA-NF)

For details on the RES BW parameters, see "NF Calculation Parameters" in the explanation of section 5.8.



The analysis algorithm other than EDFA-NF uses the value stored in the AQ6360.

Clearing the Resolution Calibration Value

The calibration table of equivalent noise bandwidth is cleared. After clearing, the factory default resolution bandwidth is used in the analysis algorithm calculations. Use this function when you need to align with existing analysis data.

2.3 Measurement Precautions

Types of Optical Fibers That Can Be Used with This Instrument

This instrument can use single mode optical fibers with a core diameter of 5 to 9.5 μ m and multi-mode (GI) optical fibers with a core diameter of 50 μ m or 62.5 μ m. The optical input section of this instrument has a free-space structure, so even larger core-diameter optical fibers can be connected directly. Particularly when taking in spatial light, optical fibers with a large core diameter are advantageous, but use cables appropriate for the application while referring to the following note.

Note

When a large-core optical fiber with a core diameter of 100 µm or wider is connected, the amount of light that can be collected in is not necessarily proportional to the core diameter area. In particular, using a 400 µm or larger core optical fiber hardly increases the amount of light that can be collected. In addition, even though the maximum resolution of this instrument is 0.1 nm, when using 100 µm or larger core optical fibers, we recommend setting the wavelength resolution to 0.5 nm or greater. Note that this instrument is designed exclusively for optical fiber input. It is not possible to apply a gas laser beam directly into the optical input connector, input LED light by bringing the LED in close contact with the optical input connector section, or input light by any other method without using an optical fiber. Note that optical spectrum measured using such methods is totally unreliable. To measure spatial light, you need to collect the spatial light into the optical fiber and then apply it to this instrument.

Numerical Aperture (NA) of Input Optical Fibers and Level Measurements

The level measurement errors of this instrument varies depending on the numerical aperture (NA) of the optical fiber connected to the input connector section. The absolute level of this instrument is calibrated with a 9.5/125 μ m single mode optical fiber (SSMA type in JIS C6835, PC polishing, mode field diameter: 9.5 μ m, NA: 0.104 to 0.107). If the NA value is not within this range even for single mode optical fibers, the level accuracy is not guaranteed.

0.50 0.40 0.30 Level error (dB) 0.20 0.10 0.00 -0.10 -0.20 -0.30 -0.40 -0 50 0.101 0.102 0.103 0.104 0.105 0.106 0.107 0.108 0.109 0.110 Numerical aperture

Numerical aperture of input optical fibers and level errors (representative characteristics)

Absolute Level Accuracy

The absolute level of this instrument is calibrated with a $9.5/125 \ \mu m$ single mode optical fiber (SSMA type in JIS C6835, PC polishing, mode field diameter: $9.5 \ \mu m$, NA: 0.104 to 0.107). The level accuracy when other optical fibers are used is not guaranteed. For multi-mode (GI) fibers, a relatively accurate spectrum is indicated for low-coherence light, such as white light, natural light, and LEDs.

For high-coherence light, such as a laser beam, interference occurs within the optical fiber, and the intensity distribution of light reflected from the end of the fiber varies depending on the fiber form. As such, moving the fiber may change the spectrum (measurement level).

Ripples in the 1350 to 1450 nm Area

Water (OH-) ions present in the monochromator absorb light in the 1350 to 1450 nm area, resulting in ripples in the measurement waveform. The amount of ripples can be reduced by setting a coarser resolution or using the instrument in a low-humidity environment.

Second Order Diffraction Light

The monochromator of this instrument uses a diffraction grating. When light with a wavelength shorter than the lower limit (1200 nm) of the measurement wavelength range is received, optical spectrum ghost referred to as second order diffraction light, appears. For example, if 700 nm light is input, a ghost optical spectrum will appear at the 1400 nm position. Avoid applying light with a wavelength shorter than the lower limit of the measurement wavelength range.

Luminance at the Installation Location

The light shielding performance of this instrument is designed on the assumption that the instrument will be used in a typical office or factory room (300 to 1000 lx). As such, depending on the lighting conditions of the installation location, the instrument may collect extraneous light, and this may affect the measurement results when weak light is measured. In such situations, darkening the surroundings of this instrument will reduce the inaccuracies.

3.1 Auto Measurement


Procedure


With auto measurement, measurements are made by automatically setting the optimal measurement conditions for the light source to be measured.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SWEEP. A function menu appears for sweeping.
- 3. Tap Auto. The key is highlighted, and auto measurement is executed.




Example of displayed waveform





Screen immediately after auto sweep starts



Explanation

The wavelength range of input light that auto measurement can performed on is 1200 to 1650 nm. The following four items are automatically set to make measurements.

- Center wavelength (CENTER)
- Sweep span (SPAN)
- Reference level (REF LEVEL)
- Resolution (RESOLUTION)

Other measurement conditions (sensitivity, average times, sampling points, and interval settings) are set to the default values. The spectrum waveform is displayed with the horizontal scale and vertical scale adjusted appropriately.

An auto sweep is performed once to set the optimal measurement conditions, and then measurements are made using repeat sweep.

During auto configuration, only the REPEAT, SINGLE, STOP, and UNDO/LOCAL (when in remote mode) keys are enabled.


3.2 Setting the Horizontal and Vertical Scales

Procedure

Setting the Horizontal Scale

Setting the Horizontal Scale Unit to Wavelength or Frequency

- 1. Tap = Menu. The Main Menu window appears.
- 2. Tap SETUP. A function menu appears for setting measurement conditions.
- 3. Tap More 1/2.
- **4.** Tap **Horizontal Scale nm/THz**. Each time you tap, the horizontal scale unit is changed between THz and nm.



Note

The displayed marker values and analysis results also change between wavelength and frequency in sync with the horizontal scale setting.

Setting the Measured Wavelength to Wavelength in Air or Wavelength in Vacuum

- 1. Tap **= Menu**. The Main Menu window appears.
- 2. Tap SETUP. A function menu appears for setting measurement conditions.
- Tap Medium AIR VACUUM. The measured wavelength changes to wavelength in air or wavelength in vacuum.


Note .

- This function takes effect when a measurement is executed after the setting is changed. It is
 not applied to the waveform that has already been measured.
- You can also set the parameter by tapping the w^L/w^L/w^L shortcut key at the bottom of the screen.
 If set to wavelength in vacuum, the shortcut key is highlighted.

Setting the Vertical Scale


Changing to a Log Scale Display

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap LEVEL. A function menu appears for setting the vertical scale.
- **3.** Tap **Log Scale**. The vertical scale is displayed with the currently set log scale value. At the same time, a parameter input window appears.
- 4. Enter the log scale value in the parameter input window.
- 5. Tap µm/ENT or nm/ENT.



Changing to a Linear Scale Display

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap LEVEL. A function menu appears for setting the vertical scale.
- **3.** Tap **Linear Scale**. The vertical scale is displayed with the currently set linear scale value.
- 4. Tap Linear Base Level. A parameter input window appears.
- 5. Set the value at the bottom of the level scale in the parameter input window.
- 6. Tap μm/ENT or nm/ENT.



Setting the Vertical Scale Unit


- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap LEVEL.
- 3. Tap Level Unit.

If the vertical scale is set to log scale, each time you tap, the unit changes between dBm and dBm/nm (dBm/THz).

If the vertical scale is set to linear scale, the unit changes between nW, μ W, mW, or pW and nW/nm (nW/THz), μ W/nm (μ W/THz), mW/nm (mW/THz), or pW/nm (μ W/THz).

Setting the Number of Divisions of the Vertical Scale (for Log Scale)

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap LEVEL.
- 3. Tap Log Scale.
- 4. Tap More to display the More 3/3 function menu.
- **5.** Tap **Y Scale Division**. A function menu appears for selecting the number of divisions.
- 6. Tap 8 or 10. A level axis is displayed with the specified number of divisions.



Note

- This is valid only when the main scale is set to log scale.
- For linear scale, the number of divisions is fixed at 10.

Setting the Reference Level Position on the Screen (for Log Scale)

- **5.** Continuing from step 4, tap **Ref Level Position**. A parameter input window appears.
- **6.** Set the reference level position (REF position) on the screen in the parameter input window.

Enter the number of divisions counted from the screen bottom. The input range is 0 to 10.

The input step when entering with the arrow keys is 1 step for FINE and 1-2-5 step for COARSE.

7. If you entered with the numeric keypad, tap µm/ENT or nm/ENT.

Note_

- This is valid only when the main scale is set to log scale.
- If the REF position value is greater than the number of divisions, it is reduced to the same value as the number of divisions.
- For linear scale, the REF position is fixed at the top (fixed at 10 DIV).

Explanation

Wavelength Display Mode

- Measured waveforms are displayed with the horizontal scale set to wavelength.
- The measurement scale and display scale are set in terms of the wavelength.
- · The horizontal scale unit of marker values and analysis results is wavelength.

Frequency Display Mode

- Measured waveforms are displayed with the horizontal scale set to frequency.
- The measurement scale and display scale are set in terms of the frequency.
- The horizontal scale unit of marker values and analysis results is frequency.

Displayed Units for Horizontal Scale and Marker Values

The unit displayed for marker values (wavelength or frequency) can be set separately from the waveform display's horizontal scale unit set with Horizontal Scale nm THz under SETUP. (Default: nm)

(For example, it is possible to set the horizontal scale to frequency display mode and marker values to wavelength display mode.)

Note .

The Marker Unit nm THz setting changes in sync with the Horizontal Scale setting, but changing the Marker Unit nm THz setting will not change the Horizontal Scale setting under SETUP.

Log Scale **.*dB/D

This key switches the vertical scale to LOG display. After you tap this key, set the level scale.

The setting range is 0.1 to 10.0 dB/DIV. You can set it in steps of 0.1 dB. When COARSE is selected, you can set it in steps of 1-2-5 (e.g., 1 dB/DIV \rightarrow 2dB/DIV \rightarrow 5dB/DIV). When you change this setting, the displayed waveform is redrawn according to the new scale.

If you specify a scale greater than 5 dB/DIV in fixed range mode (measurement sensitivity NORM/HOLD), a warning will be displayed because the top and bottom of the waveform will not be measured correctly.

Measurement Sensitivity and Effective Vertical Scale Range

If the measurement sensitivity is set to NORM/HOLD, the internal amplifier is set to fixed gain. The gain is set automatically from the five available settings depending on the reference level (REF) setting. The effective range of measurement data is limited to the following range relative to the reference (REF) level.

REF-20 dBm < (effective range) < REF+10 dBm

If the level scale is set to 10 dB/DIV, the display will fall outside the effective range, and thus 10 dB from the top edge of the screen and 20 dB from the bottom edge of the screen will be inaccurate.

If the measurement sensitivity is set to NORM/HOLD, we recommend that you use the level scale at 5 dB/DIV or less.

If the measurement sensitivity is NORM/AUTO, MID, or HIGH 1 or 2 (standard model (-10) only), auto gain is used allowing a wide level range to be measured in one sweep. Select the appropriate sensitivity according to the reception level necessary for measurement.

Linear Scale

The main scale is set to linear scale.

The level per DIV varies in sync with the reference level (REF level) setting. For setting the REF level, see section 3.4, "Setting the Reference Level."

Linear Base Level**.*mW

When the vertical scale is set to linear scale, set the value at the low end of the level scale. This is invalid for log scale.

The setting range is 0.0 to REF level \times 0.9. You can set it in steps of 0.1. When COARSE is selected, you can set it in steps of 1. The unit can only be set to the same unit set by REF level.

When you change this setting, the displayed waveform is redrawn according to the new scale.

The scale display at the upper left of the waveform is set to 1/10 of [reference (REF) level – low-end (BASE) level (*W/D).

For setting the REF level, see section 3.4, "Setting the Reference Level."

Level Unit dBm dBm/nm

When the level axis is log scale, you can switch the display to dBm or dBm/nm.

dBm: Power per resolution (absolute power)

dBm/nm: Power per 1 nm (power spectral density)

For details on how to use dBm and dBm/nm, see "Power Spectral Density Display" on the next page.

If you set a calculated waveform to power spectral density, the level unit is automatically set to dBm. If power spectral density is assigned as the calculated waveform to Trace F and the unit is set to dBm/nm, Trace F enters FIX mode, and the waveform is no longer updated.

Level Unit mW mW/nm

When the level axis is linear scale, you can switch the display between nW, μ W, mW, or pW (absolute power), and nW/nm, μ W/nm, mW/nm or pW/nm (power spectral density).

3.2 Setting the Horizontal and Vertical Scales

Power Spectral Density Display

Power per 1 nm is called the power spectral density.

The level axis of the optical spectrum analyzer indicates the absolute power per wavelength resolution. For example, if the resolution is set to 0.100 nm, the power per 0.100 nm will be displayed.

Since the optical spectrum of such devices as a gas laser or a laser diode is narrower than the wavelength resolution of the instrument, the entire power is accommodated within the band of a resolution. Therefore, the measured power (peak level) is equal to the total power of the light source. This instrument has been calibrated to display accurate power under such conditions.

On the other hand, natural light or lights such as fluorescent lamps or LEDs, have, in many cases, optical spectrums wider than the wavelength resolution set for the instrument. Therefore, if the instrument measures these lights, measured power will vary, depending on the resolution setting.

In order to deal with this issue, the instrument has a Leve Unit setting to allow the level axis displays to switch from the absolute power (dBm, mW, μ W, nW, pW) per resolution to power spectral density (dBm/nm, mW/nm, μ W/nm, nW/nm, pW/nm).

In the case of power spectral density displays, a measured value is converted to power per 1 nm. Therefore, whatever resolution is used for measurement, a constant measured value will always be obtained.

The trace computation function can be used to display the power spectral density in the specified bandwidth within the range of 0.1 nm to 10 nm (see section 4.8).

Note.

Specifications such as level accuracy, measurement level range, and level linearity of the instrument are provided for the absolute power display.


3.3 Sub Scale

Procedure

The level scale is displayed based on relative values when a differential waveform (based on LOG values) or normalized waveform is displayed. A level scale based on relative values is called a sub scale.

Displaying a Sub Scale

Follow the procedure in section 4.5, "Displaying Calculated Waveforms," or section 4.6, "Normalized Display" to display differential waveforms or normalized waveforms.



Automatically Scaling the Sub Scale

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap LEVEL. A function menu appears for setting the vertical scale.
- **3.** Tap **More** to display the More 2/3 function menu.
- 4. Tap Auto Sub Scale OFF ON to select ON.

Setting the Sub Scale REF Position

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap LEVEL.
- 3. Tap More to display the More 3/3 function menu.
- 4. Tap Sub Ref level Position. A parameter input window appears.
- 5. Set the REF position in the parameter input window.

Note

A sub scale is displayed when differential waveforms (based on LOG values) or normalized waveforms are displayed. When these waveforms are superimposed on waveforms based on absolute values, the absolute value scale is shown on the left and the relative value scale on the right at the same time. If the left scale (main scale) is changed to LOG (8 DIV) or linear (10 DIV), the sub scale is displayed to correspond to the DIV count on the main scale.

Setting the Sub Scale to Log Display

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap LEVEL. A function menu appears for setting the vertical scale.
- 3. Tap More to display the More 2/3 function menu.
- **4.** Tap **Sub Log**. The sub scale is displayed with the currently set log scale value. At the same time, a parameter input window appears.
- 5. Enter the log scale value in the parameter input window.
- 6. Tap µm/ENT or nm/ENT.

Setting the Sub Scale Unit to dB/km

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap LEVEL.
- **3.** Tap **More** to display the More 2/3 function menu.
- 4. Continuing from step 6, tap Sub Scale **.*dB/km. The sub scale unit changes to dB/km. At the same time, a parameter input window appears.
- 5. Enter the log scale value in the parameter input window.
- 6. Tap µm/ENT or nm/ENT.

When displaying the loss characteristics of the optical fiber per unit of length (km)

- 7. Continuing from step 6, tap Length.
- 8. Enter the optical fiber length in the parameter input window.
- 9. Tap µm/ENT or nm/ENT.

Setting the Sub Scale Offset Value

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap LEVEL.
- 3. Tap More to display the More 2/3 function menu.
- 4. Tap Offset Level. A parameter input window appears.
- 5. Enter the offset value (sub scale REF value) in the parameter input window.
- 6. Tap µm/ENT or nm/ENT.

Setting the Sub Scale to Linear Display

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap LEVEL. A function menu appears for setting the vertical scale.
- 3. Tap More to display the More 2/3 function menu.
- **4.** Tap **Sub Linear**. The sub scale is displayed with the currently set linear scale value. At the same time, a parameter input window appears.
- 5. Enter the linear scale value in the parameter input window.
- 6. Tap µm/ENT or nm/ENT.

Setting the Sub Scale Unit to %/D

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap LEVEL.
- **3.** Tap **More** to display the More 2/3 function menu.
- Tap Sub Scale ***.*%/D. The sub scale unit changes to %. At the same time, a
 parameter input window appears.
- 5. Enter the percentage in the parameter input window.
- 6. Tap µm/ENT or nm/ENT.

Setting the Sub Scale Low-End Value

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap LEVEL.
- 3. Tap More to display the More 2/3 function menu.
- 4. Tap Scale Minimum. A parameter input window appears.
- 5. Enter the sub scale low-end value in the parameter input window.
- 6. Tap µm/ENT or nm/ENT.

Explanation

Sub Scale **.*dB/km

(Sets the sub scale to dB/km.)

The setting range is 0.1 to 10.0 dB/km. You can set it in steps of 0.1. When COARSE is selected, you can set it in steps of 1-2-5 (e.g., 1 dB/DIV \rightarrow 2dB/DIV \rightarrow 5dB/DIV). When you change this setting, the displayed waveform is redrawn according to the new scale.

Sub Scale ***.*%/D

(Sets the sub scale to %.)

The setting range is 0.5 to 125%/D. You can set it in steps of 0.1. When COARSE is selected, you can set it in steps of 1-2-5.

When you change this setting, the displayed waveform is redrawn according to the new scale.

Offset Level

(Sets the offset value. This is valid when the sub scale is dB/D or dB/km. The setting range is as follows:)

dB/D:	0 to \pm 99.9 dB. You can set it in steps of 0.1. When COARSE is
	selected, you can set it in steps of 1.
dB/km:	0 to ±99.9 dB/km. You can set it in steps of 0.1.

Scale Minimum

(Sets the low-end value of the scale.) This is valid when the sub scale is LIN or %. The setting range is as follows:)

- LIN: 0 to sub scale value (***.*/D)×10
- %: 0 to sub scale value (***.*%/D)×10

Length **.***km

(Sets the optical fiber length. This is valid when the sub scale is dB/km.) The setting range is 0.001 to 99.999 km. You can set it in steps of 0.001. When COARSE is selected, you can set it in steps of 1-2-5.

Auto Sub Scale OFF/ON

(Turns on or off the function that displays the sub scale through auto scaling after calculations.)

When this key is set to on and trace C is displayed, SUB LOG or SUB LIN and OFFSET LEVEL change automatically. When these are changed, the displayed waveform is redrawn according to the new scale.

You can also set the parameter by tapping the $\frac{AuT}{SCL}$ shortcut key at the bottom of the screen. When set to on, the shortcut key is highlighted.

Sub Ref level Position **DIV

(Sets the sub scale REF position.)

You can set the REF position at the specified division counted from the bottom of the screen.

The setting range is 0 to 10. You can set it in steps of 1. When COARSE is selected, you can set it in steps of 1-2-5.

Sub Scale Initialize

This function returns the vertical scale (sub scale) to its original condition after the waveform is moved or zoomed through dragging or pinching out or pinching in. The original scale value, offset value, or low-end value specified on the function menu is stored. This is not synchronized to the main scale display.

You can also tap **Y-Init** on the operation tool window to return to the original condition. For details, see chapter 3, "Common Operations" in IM AQ6360-02EN.

3.4 Setting the Reference Level


Procedure

There are two methods to set the reference level.

- · Using the Reference Level parameter
- · Using the one-action keys
- The procedure for each method is explained below.

Using the Reference Level Parameter (log scale)

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap LEVEL. A function menu appears for setting the vertical scale.
- **3.** If the vertical scale is not set to log scale, tap **Log Scale**. If the log scale is displayed, proceed to step 4.
- 4. Tap Reference Level. A parameter input window appears.
- 5. Enter the reference level in the parameter input window.
- 6. Tap µm/ENT or nm/ENT.




Note

The vertical scale setting is applied to the waveform display in real-time.

Using the Reference Level Parameter (linear scale)

- 2. Tap LEVEL. A function menu appears for setting the vertical scale.
- **3.** If the vertical scale is not set to linear scale, tap **Linear Scale**. If the linear scale is displayed, proceed to step 4.
- 4. Tap Reference Level. A parameter input window appears.
- **5.** Enter the reference level in the parameter input window. When you enter a value, a function menu appears for selecting the unit.
- 6. Tap the unit you want to use. The reference level is set.



Note_

If you enter the value using the arrow keys of the parameter input window, the reference level is set with the current unit.

Using the One-Action Keys

Setting the Reference Level to the Peak Level of the Waveform

- **1.** Tap **≡ Menu**. The Main Menu window appears.
- 2. Tap LEVEL.
- **3.** Tap **Peak Level** → **Ref Level**. The specified reference level is displayed, and the displayed waveform is redrawn according to the new reference level.

■ Menu
Reference
-42.6dBm
Log Scale
0.5dB/D
Linear Scale
Linear Base Level
1 now
Peak Level -> Ref Level
Ref Level
OFF ON
Level Unit
dBm dBm/nm
Main Scale Initialize
THUBIZE
11103028
Level

3

Measurement

Setting the Reference Level to the Peak Level Automatically Based on the Measured Waveform for Each Sweep

3. Continuing from step 2, tap Auto Ref Level OFF/ON to select ON.

Note .

- The reference level is set to the peak level of the active trace measurement waveform.
- This does not work when the active trace is set to a type other than WRITE (MAX HOLD, MIN HOLD, CALCULATE, ROLL AVG).
- You can also set the parameter by tapping the REF shortcut key at the bottom of the screen. When set to on, the shortcut key is highlighted.

Setting the Reference Level to the Moving Marker Level

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap MARKER.
- With the moving marker displayed, tap Marker → Ref Level. The specified reference level is displayed, and the displayed waveform is redrawn according to the new reference level.

For details on displaying the moving marker, see section 4.9, "Marker Display."



Explanation

Log Scale (Reference Level)

The setting range for the log scale reference level is -90.0 to 30.0 dBm. You can set it in steps of 0.1. When COARSE is selected, you can set it in steps of 1.

Linear Scale (Reference Level)

The reference level setting range for the linear scale is 1.00 pW to 1000 mW. For 1.00 to 9.99 (pW, nW, μ W, mW), you can set the value in steps of 0.01. For 10.0 to 99.9 (pW, nW, μ W, mW), you can set the value in steps of 0.1. For 100 to 999 (pW, nW, μ W, mW), you can set the value in steps of 1. When COARSE is selected, you can set it in steps of 1-2-5 (e.g., 1pW \rightarrow 2pW \rightarrow 5pW \rightarrow 10pW \rightarrow 20pW). If you change from 999 to 1.00 or 1.00 to 999, the unit will be changed (e.g., pW \rightarrow nW or nW \rightarrow pW).

One-Action Keys

This is the general term for the keys that use data from the active trace waveform (the currently displayed waveform) to set measurement conditions.

To use them, a waveform must be displayed in the active trace.

$\textbf{Peak Level} \rightarrow \textbf{Ref Level}$

The reference level is set to the peak level of the active trace waveform. The specified reference level (peak level value) and waveform are displayed in the reference level setting screen. The reference level setting can be changed after being set initially.

The setting can be changed within the range of -90.0 to +30.0 dBm for log scale or 1.00 pW to 1000 mW for linear scale.

If the peak level value exceeds the allowed range, it is set to the nearest value within the range and a warning is displayed.

Marker \rightarrow Ref Level

The reference level is set to the level of the moving marker placed on the measured waveform.

The specified reference level and waveform are displayed in the reference level setting screen.

The reference level setting can be changed after being set initially.

The setting can be changed within the range of -90.0 to +30.0 dBm for log scale or 1.00 pW to 1000 mW for linear scale.

If the moving marker value exceeds the allowed range (the moving marker is at a point where the level is -210 dBm), it is set to the nearest value within the range and a warning is displayed.

In the following states, the MARKER \rightarrow REF LEVEL key is disabled.

- When the moving marker is off (Marker Active is OFF)
- When both split screens are on hold (Upper Hold and Lower Hold are ON)

Main Scale Initialize

This function returns the vertical scale (main scale) to its original condition after the waveform is moved or zoomed through dragging or pinching out or pinching in. The original scale value or low-end value specified on the function menu is stored. This is not synchronized to the sub scale display.

You can also tap **Y-Init** on the operation tool window to return to the original condition. For details, see chapter 3, "Common Operations" in IM AQ6360-02EN.

3.5 Setting the Center Wavelength (Center Frequency)

Procedure


There are three methods to set the center wavelength (center frequency).

- Using the Center Wavelength or Center Frequency parameter
- Using the Start Wavelength and Stop Wavelength parameters of Start Frequency and Stop Frequency parameters
- · Using the one-action keys

The procedure for each method is explained below.

Using the Center Wavelength or Center Frequency Parameter

- 1. Tap **Menu**. The Main Menu window appears.
- Tap CENTER. A function menu appears for setting the center wavelength or center frequency.
- **3.** For wavelength measurement, tap **Center Wavelength**. For frequency measurement, tap **Center Frequency**. A parameter input window appears.
- 4. Enter the center wavelength or center frequency in the parameter input window.
- 5. Tap nm/ENT.



Note .

- There is no need to tap nm/ENT when using arrow keys to enter the value.
- The assigned value is applied to the measurement conditions area. You can also tap the value in the measurement condition area directly to set it.
- When a setting is changed, NEW appears in the measurement conditions area.
- · If you enter a value outside the setting range, the nearest permitted value is assigned.


For instructions on switching the wavelength and frequency displays, see section 3.2.

Using the Start Wavelength and Stop Wavelength Parameters of Start Frequency and Stop Frequency Parameters

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap **CENTER**. A function menu appears for setting the center wavelength or center frequency.

Setting the Start Wavelength or Start Frequency

- **3.** For wavelength measurement, tap **Start Wavelength**. For frequency measurement, tap **Start Frequency**. A parameter input window appears.
- 4. Enter the start wavelength or start frequency in the parameter input window.
- 5. Tap nm/ENT.



Setting the Stop Wavelength or Stop Frequency

- 6. For wavelength measurement, tap **Stop Wavelength**. For frequency measurement, tap **Stop Frequency**. A parameter input window appears.
- 7. Enter the stop wavelength or stop frequency in the parameter input window.
- **8.** Tap **nm/ENT**.

Note.

- There is no need to tap nm/ENT when using arrow keys to enter the value.
- The assigned value is applied to the measurement conditions area. You can also tap the value in the measurement condition area directly to set it.
- When a setting is changed, NEW appears in the measurement conditions area.
- If you enter a value outside the setting range, the nearest permitted value is assigned.

For instructions on switching the wavelength and frequency displays, see section 3.2.


Using the One-Action Keys

Tap one of the one-action keys in the function menu. These one-action keys appear after you tap **CENTER**.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap CENTER.
- 3. To use a peak wavelength or peak frequency to set the center wavelength, tap Peak WL → Center. To use the RMS 20 dB center wavelength or center frequency, tap Mean WL → Center. To use the currently displayed zoom scale, tap View Scale → Measure. The specified center wavelength or center frequency is displayed, and the displayed waveform is redrawn according to the new center wavelength.


Automatically Setting the Center Wavelength or Center Frequency to the Peak Wavelength or Peak Frequency of the Active Trace Measurement Waveform for Each Sweep

3. Continuing from step 2, tap Auto Center OFF/ON to select ON.



Setting the Center Wavelength or Center Frequency to the Moving Marker Wavelength or Frequency

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap MARKER.
- 3. With the moving marker displayed, tap Marker → Center. The specified center wavelength or center frequency is displayed, and the displayed waveform is redrawn according to the new center wavelength or center frequency. For details on displaying the moving marker, see section 4.9, "Marker Display."



Explanation

Center Wavelength

The setting range is 1200.000 to 1650.000 nm.

When entering with the arrow keys when COARSE is selected, the value changes in steps of 1 nm. When FINE is selected, the value changes in steps of 0.1 nm.

Start Wavelength

The setting range is 975.000 to 1650.000 nm.

Stop Wavelength

The setting range is 1200.000 to 1875.000 nm.

Note

- When you set the start wavelength or stop wavelength, the sweep span will change because the other wavelength is fixed. The center wavelength will also change.
- · Changing the center wavelength does not change the sweep span.

Auto Center OFF / ON

This key sets whether the Peak WL \rightarrow Center function will be applied for each sweep. When this key is set to ON, the peak is automatically searched in the active trace waveform and assigned to the center wavelength for each sweep. The active trace must be set to WRITE.

You can also set the parameter by tapping the $\frac{|AUT|}{|CTR|}$ shortcut key at the bottom of the screen. When set to on, the shortcut key is highlighted.

One-Action Keys

This is the general term for the keys that use data from the active trace waveform (the currently displayed waveform) to set measurement conditions.

To use them, a waveform must be displayed in the active trace.

$\textbf{Peak WL} \rightarrow \textbf{Center}$

The center wavelength is set to the wavelength at the peak value of the active trace waveform.

When executed, the specified center wavelength is displayed in the center wavelength setting screen. The center wavelength can be changed after the setting is made initially.

Mean WL \rightarrow Center

The center wavelength is set to the average (RMS 20 dB center wavelength) of the spectrum in the range from the peak of the active trace waveform down to the threshold (20 dB). The center wavelength can be changed after the setting is made initially.

View Scale \rightarrow Measure

The measurement scale (CENTER, START, STOP, SPAN) is set to the currently set zoom scale (ZOOM CENTER, ZOOM SPAN, ZOOM START, ZOOM STOP). When you tap this key, the measurement scale of the next sweep is set to the current waveform display scale.

Center Frequency

The setting range is 181.5000 to 250.0000 THz.

When entering with the arrow keys when COARSE is selected, the value changes in steps of 0.1 THz. When FINE is selected, the value changes in steps of 0.01 THz.

Start Frequency

The setting range is 147.2500 to 250.0000 THz.

Stop Frequency

The setting range is 181.5000 to 284.2500 THz.

Note .

- When you set the start frequency or stop frequency, the sweep span will change because the other frequency is fixed. The center frequency will also change.
- Changing the center frequency does not change the sweep span.

Auto Center OFF / ON

This key sets whether the Peak WL \rightarrow Center function will be applied for each sweep. When this key is set to ON, the peak is automatically searched in the active trace waveform and assigned to the center frequency for each sweep.

The active trace must be set to WRITE.

You can also set the parameter by tapping the $\frac{AUT}{CTR}$ shortcut key at the bottom of the screen. When set to on, the shortcut key is highlighted.

One-Action Keys

Like the wavelength, you can use one-action keys to set the center frequency.

$\textbf{Peak WL} \rightarrow \textbf{Center}$

The center frequency is set to the frequency at the peak value of the active trace waveform.

When executed, the specified center frequency is displayed in the center frequency setting screen. The center frequency can be changed after the setting is made initially.

Mean WL \rightarrow Center

The center frequency is set to the average (RMS 20 dB center frequency) of the spectrum in the range from the peak of the active trace waveform down to the threshold (20 dB). The center frequency can be changed after the setting is made initially.

$\textbf{View Scale} \rightarrow \textbf{Measure}$

The measurement scale (CENTER, START, STOP, SPAN) is set to the currently set zoom scale (ZOOM CENTER, ZOOM SPAN, ZOOM START, ZOOM STOP). When you tap this key, the measurement scale of the next sweep is set to the current waveform display scale.

Setting the Sweep Span 3.6

Procedure


There are two methods to set the sweep span (span).

- · Using the Span Wavelength or Span Frequency parameter
- Using the Start Wavelength and Stop Wavelength parameters of Start Frequency and Stop Frequency parameters
- Using the one-action keys •

The procedure for each method is explained below.

Using the Span Wavelength or Span Frequency Parameter

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SPAN. A function menu appears for setting the sweep span.
- 3. For wavelength measurement, tap Span Wavelength. For frequency measurement, tap Span Frequency. A parameter input window appears.
- 4. Enter the sweep span in the parameter input window.
- 5. Tap nm/ENT.



Measurement condition area

Note

- There is no need to tap nm/ENT when using arrow keys to enter the value.
- The assigned value is applied to the measurement conditions area. You can also tap the value in the measurement condition area directly to set it.
- When a setting is changed, NEW appears in the measurement conditions area.
- If you enter a value outside the setting range, the nearest permitted value is assigned.


For instructions on switching the wavelength and frequency displays, see section 3.2.

Using the Start Wavelength and Stop Wavelength Parameters of Start Frequency and Stop Frequency Parameters

- 1. Tap **= Menu**. The Main Menu window appears.
- 2. Tap SPAN. A function menu appears for setting the sweep span.

Setting the Start Wavelength or Start Frequency

- **3.** For wavelength measurement, tap **Start Wavelength**. For frequency measurement, tap **Start Frequency**. A parameter input window appears.
- 4. Enter the start wavelength or start frequency in the parameter input window.
- 5. Tap nm/ENT.



Setting the Stop Wavelength or Stop Frequency

- 6. For wavelength measurement, tap **Stop Wavelength**. For frequency measurement, tap **Stop Frequency**. A parameter input window appears.
- 7. Enter the stop wavelength or stop frequency in the parameter input window.
- 8. Tap nm/ENT.

Note -

- There is no need to tap nm/ENT when using arrow keys to enter the value.
- The assigned value is applied to the measurement conditions area. You can also tap the value in the measurement condition area directly to set it.
- When a setting is changed, NEW appears in the measurement conditions area.
- If you enter a value outside the setting range, the nearest permitted value is assigned.

For instructions on switching the wavelength and frequency displays, see section 3.2.

Using the One-Action Keys

Setting the Sweep Span Based on the Measured Waveform


- **1.** Tap **≡ Menu**. The Main Menu window appears.
- 2. Tap SPAN.
- **3.** To set the sweep span to RMS 20 dB width × 6, tap $\Delta \lambda \rightarrow$ **Span**. To set it to the currently displayed zoom scale, tap **View Scale** \rightarrow **Measure**.



Setting the Sweep Span to the Span between Line Markers 1 and 2

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap MARKER. A function menu appears for setting the marker.
- 3. Tap More to display the More 2/3 function menu.
- With line markers 1 and 2 displayed, tap Marker L1-L2 → Span. The sweep span is set to the span between line markers 1 and 2.

For instructions on displaying line markers, see section 4.9.



Note -

- If only line marker L1 is displayed, the measurement stop wavelength is set to the wavelength at the right edge of the screen. If only line marker L2 is displayed, the measurement start wavelength is set to the wavelength at the left edge of the screen.
- Marker L1-L2 \rightarrow Span cannot be used under the following conditions.
 - When both L1 and L2 are off.
 - When both spit screens are on hold.
 - When the span of the active trace is 0 nm.

Explanation

Wavelength Sweep Span

The setting range is 0, and 0.1 to 450.0 nm.

When entering with the arrow keys when COARSE is selected, the value changes in steps of 1-2-5. When FINE is selected, the value changes in steps of 1 nm.

Start Wavelength

The setting range is 975.000 to 1650.000 nm.

When COARSE is selected, the value changes in steps of 1 nm. When FINE is selected, the value changes in steps of 0.1 nm.

Stop Wavelength

The setting range is 1200.000 to 1875.000 nm.

When COARSE is selected, the value changes in steps of 1 nm. When FINE is selected, the value changes in steps of 0.1 nm.

Note

- When you change the sweep span, the start wavelength and stop wavelength will change.
 The center wavelength or center frequency will not change.
- When you change the center wavelength, the start wavelength and stop wavelength will change. The sweep span will not change.
- When you set the start wavelength or stop wavelength, the sweep span will change because the other wavelength is fixed. The center wavelength will also change.

One-Action Keys

This is the general term for the keys that use data from the active trace waveform (the currently displayed waveform) to set measurement conditions. To use them, a waveform must be displayed in the active trace.

$\Delta\lambda ightarrow$ Span

The sweep span is set to six times the spectral width based on the RMS method (20 dB threshold) of the active trace waveform.

View Scale \rightarrow Measure

See the explanation in section 3.5, "Setting the Center Wavelength (Center Frequency)."

Marker L1-L2 \rightarrow Span

The sweep span is set to the span between line markers 1 and 2.

Frequency Sweep Span

The setting range is 0 and 0.01 to 68.50 THz.

When entering with the arrow keys when COARSE is selected, the value changes in steps of 1-2-5. When FINE is selected, the value changes in steps of 0.1 THz.

Start Frequency

The setting range is 147.2500 to 250.000 THz. When COARSE is selected, the value changes in steps of 0.1 THz. When FINE is selected, the value changes in steps of 0.01 THz.


Stop Frequency

The setting range is 181.5000 to 284.2500 THz. When COARSE is selected, the value changes in steps of 0.1 THz. When FINE is selected, the value changes in steps of 0.01 THz.

3.7 Setting the Wavelength (Frequency) Resolution

Procedure

- 1. Tap **= Menu**. The Main Menu window appears.
- 2. Tap SETUP. A function menu appears for setting measurement conditions.
- **3.** Tap **Resolution**. The function menu shows the available resolutions.
- **4.** Tap the resolution you want to use. The screen returns to the previous level, the Resolution key shows the assigned value.



Note -

- If you enter a value in the parameter input window that appears when you tap Resolution, the nearest permitted resolution is assigned.
- The assigned value is applied to the measurement conditions area. You can also tap the value in the measurement condition area directly to set it.
- If the span, sampling points, or resolution setting is inappropriate, CAL is displayed.

What to Do When "UNCAL" Is Displayed

- Perform any of the following:
- Decrease the span.
- Increase the sampling points.
- · Lower the resolution (increase the value).
- Set Sampling Points under SETUP to AUTO.

When the span, sampling points, and resolution settings become appropriate, the $\begin{bmatrix} UN \\ CAL \end{bmatrix}$ disappears.

Explanation

Conditions That Cause "UNCAL" to Be Displayed

CAL is displayed when you start a single sweep or repeat sweep if the following relationship between the span, resolution, and sampling points is true.

Span Setting resolution

Ripples in the 1350 to 1450 nm Area


Water (OH-) ions present in the monochromator absorb light in the 1350 to 1450 nm area, resulting in ripples in the measurement waveform. The amount of ripples can be reduced by setting a coarser resolution or using the instrument in a low-humidity environment.

3.8 Setting the Sampling Points and Interval

Procedure

There are three methods to set the sampling points.

- · Setting the sampling points directly
- Setting the sampling interval
- Automatically setting the optimum sampling points or interval according to the sweep span (span) and resolution setting
 - 1. Tap **Menu**. The Main Menu window appears.
 - 2. Tap SETUP. A function menu appears for setting measurement conditions.
 - To set the sampling points, tap Sampling Points. To set the sampling interval, tap Sampling Interval. A parameter input window appears.
 To automatically set the sampling points and interval according to the span and wavelength (frequency) resolution settings, tap Sampling Points AUTO.
 - 4. Enter the sampling points or interval in the parameter input window.
 - 5. Tap µm/ENT or nm/ENT. The sampling points or interval will be set.



— Measurement condition area

Note.

- The assigned value is applied to the measurement conditions area. You can also tap the value in the measurement condition area directly to set it.
- If the span, sampling points, or resolution setting is inappropriate, CAL
 is displayed.
- For instructions on what to do when $\begin{bmatrix} UN\\ CAL \end{bmatrix}$ is displayed, see section 3.7, "Setting the Wavelength (Frequency) Resolution."

Explanation

Sampling Points (the number of points measured in a single sweep)

Sampling points are the number of points measured within the range of the specified span.

The setting range is 101 to 50001.

Relationship between Sampling Points, Interval, and Span

The relationship between sampling points, interval, and span is as follows:

Sampling points =
$$\frac{\text{Span}}{\text{Interval}}$$
 + 1

Given the same span, the sampling points are automatically determined when the interval is known, and vice versa.

For the span setting range, see the explanation in section 3.6, "Setting the Sweep Span."

Note.

- Increasing the sampling points or decreasing the sampling interval reduces the sweeping speed.
- Settings that would cause the number of samples in the sweep range to be extremely small cannot be specified.
- · Changing the sampling points also changes the sampling interval accordingly.

Relationship between the Interval and Wavelength (Frequency) Resolution

If settings are entered such that the sampling interval determined by the span and sampling points settings is extremely long relative to the wavelength (frequency) resolution, data dropout may occur. In such a situation, $\begin{bmatrix} U \\ C \\ A \end{bmatrix}$ is displayed as described below. Enter settings that are appropriate for the resolution.

Conditions That Cause "UNCAL" to Be Displayed


LNCAL is displayed when you start a single sweep or repeat sweep if the following relationship between the span, resolution, and sampling points is true.

Span_____x 5 > specified sampling points – 1 Setting resolution

3.9 Setting the Sensitivity

Procedure

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SETUP. A function menu appears for setting measurement conditions.
- 3. Tap Sensitivity. The function menu shows the available six sensitivity options.
- **4.** Tap the option you want to use. The screen returns to the previous level, the Sensitivity key shows the assigned value.



Note -

- The assigned value is applied to the measurement conditions area. You can also tap the value in the measurement condition area directly to set it.
- HIGH 1 and HIGH 2 are available only on the standard model (-10).

3.10 Setting the Sweep Speed

Procedure

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SETUP. A function menu appears for setting measurement conditions.
- 3. Tap Sweep Speed. The value switches between 1x and 2x each time you tap.



Explanation

Sweep Speed

Sets the sweep speed.

1x This is the instrument's standard sweep speed.

2x Select this value to set the sweep speed to approximately twice the speed of the 1x value.

Measurements using this value have the following characteristics.

- If you select this value when "UNCAL" is displayed, for waveforms that have sharp spectrum shape changes, such as those produced by the DFB-LD, the level and wavelength measurement accuracies may be lower than those when you select 1x. First check the measurement spectrum, and then select this value if appropriate.
- The noise level is approximately 2 dB higher than that when you select 1x.

Note.


The assigned value is applied to the measurement conditions area. You can also tap the value in the measurement condition area directly to set it.

3.11 **Setting the Average Times**

Procedure

- Tap

 Menu. The Main Menu window appears.
- 2. Tap SETUP. A function menu appears for setting measurement conditions.
- 3. Tap Average Times. A parameter input window appears.
- 4. Enter the average times in the parameter input window.
- 5. Tap µm/ENT or nm/ENT. The Average Times shows the assigned value.



Measurement condition area

Note

Increasing the averaging times reduces the sweeping speed but the S/N improves.

Explanation

Averaging

Averaging is a function that makes multiple measurements at each measurement point and shows the average values.

You can use this function when it is difficult to make accurate measurements due to unstable waveforms such as when the light source level is fluctuating or when measuring a modulated signal of several kHz or less. You can also use this function when even higher measurement sensitivity is required.

Average Times

This key is used to set the average times for each point.

The setting range is 1 to 999.

When entering with the arrow keys when COARSE is selected, the value changes in steps of 1-2-5. When FINE is selected, the value changes in steps of 1.

Note


- When the sweep speed is set to 2x, averaging is not performed. The number of averaging times can be set when the sweep speed is set to 1x.
- The assigned value is applied to the measurement conditions area. You can also tap the value in the measurement condition area directly to set it.

3.12 Selecting Traces

Procedure


The following procedure selects a trace for writing and displaying waveform data.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap TRACE. A function menu appears for traces.
- 3. Tap Active Trace. Traces A through G are displayed in a function menu.
- **4.** Tap the trace you want to use. The active trace is set to that trace (in the following explanation, trace B is used as an example).
- 5. Tap View B to select DISP.
- 6. Tap Write B. Trace B is set to write mode.



Note

- Waveforms of traces for which View A to View G are set to BLANK cannot be displayed on screen.
- You can also use the TRACE SETTINGS window to select the active trace, show or hide waveforms, and select write mode or calculation mode. To show the TRACE SETTINGS window, tap the trace setting area in the upper right of the screen. For details, see section 3.2, "Menu Operations" in IM AQ6360-02EN.



TRACE SETTINGS window

Explanation

Active Trace

Active trace refers to a target trace to which settings and changes can be applied. A trace shows a waveform and measurement conditions. The instrument has a total of seven independent traces (A through G). You can show or hide each trace or display several traces simultaneously on the waveform screen.

The function menu for setting traces is explained below.

Active Trace...ABCDEFG

Selects the active trace from traces A to G.

Displaying Traces

You can select whether to display the active trace on the screen.

View @...DISP / BLANK

"View @ DISP": The waveform is displayed on the screen. The trace display changes to "DSP".

"View @ BLANK": The waveform is not displayed on the screen. The trace display changes to "BLK".

Each time you tap the key, the highlight toggles between "View @ DISP" and "View @ BLANK".

Note that if BLANK is set, markers applied to the trace set in DISP will be cleared. The ampersand (@) indicates the currently selected trace. It is set to one of the letters from A to G.

Write mode

Write @

Sets the active trace to write mode.

When a trace is set to write mode, waveform data is written to it and updated during measurement. The trace display next to the data area also changes to "WRITE".

The ampersand (@) indicates the currently selected trace. It is set to one of the letters from A to G.

Fix mode

Fix @

Sets the active trace to fix mode.

When a trace is set to this mode, its waveform data do not change even when

measurement is performed. As such, the waveform on the screen is not redrawn. The trace display changes to "FIX".

If you tap **Fix** on the function menu during sweeping, the waveform display is fixed at that point.

The ampersand (@) indicates the currently selected trace. It is set to one of the letters from A to G.


TRACE SETTINGS Window

You can use the TRACE SETTINGS window to show or hide other traces and change the mode without changing the active trace.

3.13 Starting a Measurement (Sweep)

Procedure

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SWEEP. A function menu appears for sweeping.
- 3. Tap Single or Repeat. Sweeping will begin.
- 4. To set the sweep interval, tap Sweep Interval. A parameter input window appears.
- 5. Enter a value in the parameter input window, and then tap µm/ENT or nm/ENT.
- 6. To stop the sweep, tap Stop.



Note.

- You can also start or stop sweeping by tapping the SGL STP shortcut key at the bottom of the screen.
- During a sweep, a sweep bar indicating the current sweep status is displayed below the horizontal axis.
- During a sweep, a sweep icon indicating the sweep status is displayed in the lower left of the screen. (The sweep progress from the start wavelength to the sweep wavelength is indicated as a percentage.)

Explanation

Sweep Interval

This key is used to set the time from the start of one sweep to the start of the next sweep. If the time required for sweeping is greater than the specified time, the next sweeping is started immediately after the current sweeping ends.

Tapping this key shows the currently set time in the parameter input window. The setting range is MINIMUM or 1 to 99999 s. If you enter a zero with the numeric keypad, the value is set to MINIMUM.


3.14 Specifying a Sweep Range

Procedure

Sweeping between Line Markers

You can sweep between wavelength line marker 1 and wavelength line marker 2.

- **1.** Display wavelength line marker 1 and wavelength line marker 2 at the boundaries of the range you want to sweep.
 - For the procedure, see section 4.9, "Marker Display."
- Tap Menu. The Main Menu window appears.
- 3. Tap SWEEP. A function menu appears for sweeping.
- 4. Tap Sweep Marker L1-L2 OFF/ON to select ON.
- 5. Tap Repeat or Single. Sweeping between line markers will begin.
- 6. To cancel, tap Sweep Marker L1-L2 OFF/ON to select OFF. Sweeping will be performed over the entire screen.



Note _

- If both L1 and L2 are set, sweeping is performed between line markers 1 and 2.
- If only L1 is set, sweeping is performed from line marker 1 to the right edge of the screen.
- If only L2 is set, sweeping is performed from the left edge of the screen to line marker 2.
- If neither L1 or L2 is set, sweeping is performed from the specified start wavelength to the stop wavelength.
- The Sweep Marker L1-L2 OFF/ON setting is shared with Sweep Marker L1-L2 OFF/ON of MARKER(More 3/3) on the Main Menu window.
- You can also set the parameter by tapping the ^[sup]₁₋₂ shortcut key at the bottom of the screen. When set to on, the shortcut key is highlighted.

3.15 Pulse Light Measurement

When pulse light is input to this instrument, it is measured as a spectrum averaged over time. The average level of measured pulse light is displayed as the spectrum level. For example, if the pulse light is a perfect rectangular wave, the measured level will be (peak level of the pulse light [mW]) × (duty cycle of the pulse light).

Thus, if the duty cycle of the pulse light is small, the measured level will be small.

The measurable repetition frequency of pulse light varies depending on the measurement sensitivity. Refer to the table below. Lower repetition frequency can be measured by increasing the average times. If average times is set to n, the measurable repetition frequency is approximately 1/n for the frequencies in the table below.

Sensitivity setting and measurable repetition frequency (when average times is 1)

Sensitivity setting	Repetition frequency
NORM/HOLD	1 MHz or higher
NORM/AUTO	1 MHz or higher
NORMAL	200 kHz or higher
MID	50 kHz or higher
HIGH1*	10 kHz or higher
HIGH2*	2 kHz or higher

* HIGH 1 and HIGH 2 are available only on the standard model (-10).


These values are not guaranteed. When measuring, use these as values as guidelines.

3.16 Smoothing

Procedure

Setting Waveform Smoothing

- 2. Tap SETUP.
- 3. Tap More 1/2.
- 4. Tap Smoothing OFF ON to select ON.



Note _

You can also set the parameter by tapping the $\frac{SMO}{OTH}$ shortcut key at the bottom of the screen. When set to on, the shortcut key is highlighted.

Explanation

Smoothing Function

The smoothing function attenuates the noise in the measured waveform.


Using the smoothing function allows areas on the waveform with a large amount of noise to be "smoothed out" when measured. Note that when noise is superimposed on abrupt changes in the spectrum, the peaks and valleys of the spectrum are integrated thereby reducing the measurement resolution.


Therefore, do not leave the smoothing function turned on at all times, and use it while checking the effects on the measured spectrum.

Also, if a relatively small number of samples is set relative to the measurement span (for example, when UNCAL is displayed), smoothing may not be performed properly.

Waveform with smoothing turned off

Waveform with smoothing turned on





4.1 Zooming a Waveform

Procedure

The following methods are available to zoom a waveform.


- · By specifying a center wavelength and display sweep span
- By specifying start and stop wavelengths
- · By specifying the range with the mouse
- · Pinching out or pinching in the waveform display area

The procedure for each method is explained below.

By Specifying a Center Wavelength and Display Sweep Span

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap ZOOM. A function menu appears for setting the waveform zoom.
- 3. Tap Zoom Center Wavelength. A parameter input window appears.
- 4. Enter the zoom center wavelength in the parameter input window.
- 5. Tap nm/ENT.
- 6. Tap Zoom Span Wavelength. A parameter input window appears.
- 7. Enter the display sweep span (the range to zoom) in the parameter input window.
- 8. Tap nm/ENT.

Example of displayed waveform



After changing the display scale (zooming), ZOOMING is displayed

Note

- There is no need to tap nm/ENT when using arrow keys to enter the value.
- If you enter a value outside the setting range, the nearest permitted value is assigned.

Setting the Zoom Center Wavelength to the Peak Wavelength of the Displayed Waveform

 Tap Peak → Zoom Ctr. The zoom center wavelength is set to the peak wavelength. Proceed to step 6 above.


Restoring the Zoomed Waveform to Its Original Size

9. Tap Initialize.

By Specifying Start and Stop Wavelengths

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap ZOOM. A function menu appears for setting the waveform zoom.
- 3. Tap Zoom Start Wavelength. A parameter input window appears.
- 4. Enter the zoom start wavelength in the parameter input window.
- 5. Tap nm/ENT.
- 6. Tap Zoom Stop Wavelength. A parameter input window appears.
- 7. Enter the zoom stop wavelength in the parameter input window.
- 8. Tap nm/ENT.

Example of displayed waveform




After changing the display scale (zooming), ZOOMING is displayed

Note.

- There is no need to tap nm/ENT when using arrow keys to enter the value.
- If you enter a value outside the setting range, the nearest permitted value is assigned.

By Specifying the Range with the Mouse

- **1.** In the waveform display area, drag the area you want to zoom. The area is displayed with a dotted frame (zoom area).
- When you release the left mouse button, the dotted frame is zoomed. At the same time, the overview window shows the zoom area with a dotted frame.



After changing the display scale (zooming), ZOOMING is displayed.

Note _

- If you change the display scale to a value different from the measurement scale, ZOOMING appears on screen. Also, an overview window that shows the measurement scale is displayed in the corner of the measurement screen.
- The display scale is independent of the measurement scale.
- Changing the zoom function settings does not change the measurement conditions. When you tap View Scale → Measure, the measurement scale of the next sweep is set to the current waveform display scale.

Pinching Out or Pinching In the Waveform Display Area


The instrument's screen is a touch panel. You can zoom the waveform as you like by pinching out or pinching in the waveform display area. For details, see section 3.1 in IM AQ6360-02EN.

4

Setting the Measurement Scale by Using the Current Waveform Display Scale

With the waveform zoomed, tap View Scale \rightarrow Measure.

The measurement scale of the next sweep (CENTER, START, STOP, SPAN) is set to the current waveform display scale (ZOOM CENTER, ZOOM SPAN, ZOOM START, ZOOM STOP).



Configuring the Overview Window

When the waveform display is enlarged or reduced using the zoom function, an overview window is displayed at the very bottom of the waveform display area (only displayed when a zoom is in use).


Showing/Hiding the Window and Setting the Display Position

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap ZOOM.
- 3. Tap More to display the More 2/2 function menu.
- **4.** Tap **Overview Display OFF/L/R**. Each time you tap, the window changes between hidden, displayed on the left, and displayed on the right.

Setting the Window Size

- **2.** Tap **ZOOM**.
- **3.** Tap **More** to display the More 2/2 function menu.
- Tap Overview Size LARGE/SMALL. The window switches between large and small.

Example of a screen with Overview Display OFF/L/R set to L and Overview Size LARGE/SMALL set to SMALL



Changing Settings Using the Mouse

A mouse can be used in the overview window to change the display scale settings.

Changing the Center Wavelength (Center Frequency)

- **1.** Move the mouse pointer into the overview window.
- **2.** Drag within the zoom area in the dotted frame. While doing so, the mouse pointer changes to a hand tool.

Changing the Zoom Start/Stop Wavelength

- 1. Move the mouse pointer into the overview window.
- Drag a vertical dotted line of the zoom area.
 While doing so, the mouse pointer changes to an arrow.

Specifying a New Zoom Area

- 1. Move the mouse pointer into the overview window.
- Drag outside of the zoom area. A new zoom area is created. While doing so, the mouse pointer changes to a plus (+) sign.

Note.

For information on power measurement inside the zoom area, see section 5.12.

Explanation

Zoom Center Wavelength

The setting range is 1200.000 to 1650.000 nm.

When entering with the arrow keys when COARSE is selected, the value changes in steps of 1 nm. When FINE is selected, the value changes in steps of 0.1 nm.

Wavelength Display Sweep Span

The setting range is 0, and 0.1 to 450.0 nm.

When entering with the arrow keys when COARSE is selected, the value changes in steps of 1-2-5. When FINE is selected, the value changes in steps of 1 nm.

Zoom Start Wavelength


The setting range is 975.000 to 1649.950 nm.

When entering with the arrow keys when COARSE is selected, the value changes in steps of 1 nm. When FINE is selected, the value changes in steps of 0.1 nm.

Zoom Stop Wavelength

The setting range is 1200.050 to 1875.000 nm.

When entering with the arrow keys when COARSE is selected, the value changes in steps of 1 nm. When FINE is selected, the value changes in steps of 0.1 nm.



Wavelength display sweep span

Note.

- When you change the zoom center wavelength, the zoom start wavelength and zoom stop wavelength will change. The wavelength display sweep span will not change.
- When you change the wavelength display sweep span, the zoom start wavelength and zoom stop wavelength will change. The zoom center wavelength will not change.
- When you set the zoom start wavelength or zoom stop wavelength, the wavelength display sweep span will change because the other wavelength is fixed. The center zoom wavelength will also change.

Zoom Center Frequency

The setting range is 181.5000 to 250.0000 THz.

When entering with the arrow keys when COARSE is selected, the value changes in steps of 0.1 THz. When FINE is selected, the value changes in steps of 0.01 THz.

Frequency Display Sweep Span

The setting range is 0 and 0.01 to 68.50 THz.

When entering with the arrow keys when COARSE is selected, the value changes in steps of 1-2-5. When FINE is selected, the value changes in steps of 0.1 THz.

Zoom Start Frequency


The setting range is 147.2500 to 249.9950 THz.

When entering with the arrow keys when COARSE is selected, the value changes in steps of 0.1 THz. When FINE is selected, the value changes in steps of 0.01 THz.

Zoom Stop Frequency

The setting range is 181.5050 to 284.2500 THz.

When entering with the arrow keys when COARSE is selected, the value changes in steps of 0.1 THz. When FINE is selected, the value changes in steps of 0.01 THz.



Note.

- When you change the zoom center frequency, the zoom start frequency and zoom stop frequency will change. The frequency display sweep span will not change.
- When you change the frequency display sweep span, the zoom start frequency and zoom stop frequency will change. The zoom center frequency will not change.
- When you set the zoom start frequency or zoom stop frequency, the frequency display sweep span will change because the other frequency is fixed. The center zoom frequency will also change.

4

4.2 Updating or Fixing Waveforms

Procedure

Selecting a Trace to Update or Fix


- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap TRACE. A function menu appears for setting traces.
- 3. Tap Active Trace. Traces A through G are displayed in a function menu.
- **4.** Tap the trace you want to update or fix. The active trace is set to the selected trace, and the operation below will be applied to it.
- **5.** Tap **View** of the selected trace to select DISP. Each time you tap, the value switches between DISP and BLANK. (In the following explanation, trace B is used as an example.)

Updating a Waveform

- 6. Tap Write. The trace setting area display changes to WRITE.
- 7. Perform a measurement. The waveform data will be updated.

Fixing a Waveform

- 6. Tap Fix. The trace setting area display changes to FIX.
- **7.** The waveform data is fixed. When a measurement is performed, the waveform data will not be updated.



Note

- Only a single trace can be the active trace. If you need to change several traces, change them one at a time.
- If all traces are set to FIX, a warning appears, and measurements cannot be performed.
- You can also use the TRACE SETTINGS window to select the active trace, show or hide waveforms, and select write mode or calculation mode. To show the TRACE SETTINGS window, tap the trace setting area in the upper right of the screen. For details, see section 3.2, "Menu Operations" in IM AQ6360-02EN.

Explanation

Active Trace

Active trace refers to a target trace to which settings and changes can be applied. A trace shows a waveform and measurement conditions. The instrument has a total of seven independent traces (A through G). You can show or hide each trace or display several traces simultaneously on the waveform screen.

The function menu for setting traces is explained below.

Active Trace...ABCDEFG

Selects the active trace from traces A to G.

You can also switch the active trace by tapping the trace setting area of the screen.

Displaying Traces

You can select whether to display the active trace on the screen.

View @...DISP / BLANK

"View @ DISP": The waveform is displayed on the screen. The trace display changes to "DSP".

"View @ BLANK": The waveform is not displayed on the screen. The trace display changes to "BLK".

Each time you tap the key, the highlight toggles between "View @ DISP" and "View @ BLANK". Note that if BLANK is set, markers applied to the trace set in DISP will be cleared.

The ampersand (@) indicates the currently selected trace. It is set to one of the letters from A to G.

Write mode

Write @

Sets the active trace to write mode.

When a trace is set to write mode, waveform data is written to it and updated during measurement. The trace display next to the data area also changes to "WRITE".

The ampersand (@) indicates the currently selected trace. It is set to one of the letters from A to G.

Fix mode

Fix @

Sets the active trace to fix mode.

When a trace is set to this mode, its waveform data do not change even when measurement is performed. As such, the waveform on the screen is not redrawn. The trace display changes to "FIX".

If you tap **Fix** on the function menu during sweeping, the waveform display is fixed at that point.

The ampersand (@) indicates the currently selected trace. It is set to one of the letters from A to G.

4.3 MAX/MIN HOLD Display

Procedure

Selecting a Trace to Hold

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap TRACE. A function menu appears for setting traces.
- 3. Tap Active Trace. Traces A through G are displayed in a function menu.
- **4.** Tap the trace you want to hold the maximum or minimum value of. The active trace is set to the selected trace, and the operation below will be applied to it.
- **5.** Tap **View** of the selected trace to select DISP. Each time you tap, the value switches between DISP and BLANK. (In the following explanation, trace B is used as an example.)

Holding the Maximum/Minimum Value


- 6. Tap Hold. A function menu appears for selecting MAX/MIN.
- 7. To hold the maximum value, tap Max Hold.
 - To hold the minimum value, tap **Min Hold**.

The maximum or minimum value will be held.

8. Tap **Repeat**. Sweeping will begin.

If Max Hold is selected, the waveform data is updated when the measured value is greater than the previous value.

If Min Hold is selected, the waveform data is updated when the measured value is less than the previous value.



Note

- Max Hold/Min Hold is valid only when the sweep mode is Repeat. It does not work if you repeat single sweeps.
- You can also use the TRACE SETTINGS window to select the active trace, show or hide waveforms, and select write mode or calculation mode. To show the TRACE SETTINGS window, tap the trace setting area in the upper right of the screen. For details, see section 3.2, "Menu Operations" in IM AQ6360-02EN.

Explanation

MAX/MIN HOLD Mode (maximum/minimum value detection mode)

The maximum or minimum value of the waveform data is written in each sweep. For traces set to MAX/MIN HOLD mode, for every sweep, the data at each measurement point is compared with the previous measured value, and the larger (MAX HOLD) or smaller (MIN HOLD) level data is written.

If you want to measure the maximum or minimum value of a waveform that changes each time a sweep is performed, set the trace you want to measure to MAX/MIN HOLD mode and perform repeat sweeps.

The trace display next to the data area shows "MAX HOLD" or "MIN HOLD".

Note that the Noise Mask value does not affect maximum/minimum value detection. The value is applied when the waveform is displayed.

4.4 Sweep Average


Procedure

Selecting a Trace to Average

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap TRACE. A function menu appears for setting traces.
- 3. Tap Active Trace. Traces A through G are displayed in a function menu.
- **4.** Tap the trace you want to average. The active trace is set to the selected trace, and the operation below will be applied to it.
- **5.** Tap **View** of the selected trace to select DISP. Each time you tap, the value switches between DISP and BLANK. (In the following explanation, trace B is used as an example.)

Setting the Average Times

- 6. Tap Roll Average. A parameter input window appears.
- 7. Enter the average times in the parameter input window.
- **8.** Perform a measurement. The sweep average value is updated each time a measurement is performed.



Note -

- The setting range for average times is 2 to 100.
- You can also use the TRACE SETTINGS window to select the active trace, show or hide waveforms, and select write mode or calculation mode. To show the TRACE SETTINGS window, tap the trace setting area in the upper right of the screen. For details, see section 3.2, "Menu Operations" in IM AQ6360-02EN.

Explanation

ROLL AVG Mode (sweep average value display)

The rolling average value of the waveform data for each sweep.

When a trace is set to ROLL AVG mode, each time a measurement is performed, the rolling average of the current measurement and past measurements is calculated, and the measurement data is updated.

Set the average times between 2 and 100.

The trace display next to the data area changes to "ROLL AVG".

Averaging is performed according to the following equation.

Wj (i) =Wj-1 (i) • (n - 1)/ n + W (i) • 1 / n (i=1, 2, ..., N)

Wj (i): Newly displayed waveform

Wj-1(i): Previously displayed waveform

W (i): Newly obtained waveform

N: Sampling points

n: Number of averaging operations

Note.

Sweep averaging is not affected by the noise mask value. Noise mask is executed when the sweep average results are displayed.

4.5 Displaying Calculated Waveforms

Procedure

Selecting Traces for Calculation


- 1. Tap **= Menu**. The Main Menu window appears.
- 2. Tap TRACE. A function menu appears for setting traces.
- **3.** Tap **Active Trace**. Traces A through G are displayed in a function menu.
- Tap trace C, F, or G, which can be used for trace-to-trace calculation. The calculated results are displayed in the selected trace.

Calculations that can be performed differ depending on the trace selected.

5. Tap **View** of the selected trace to select DISP. Each time you tap, the value switches between DISP and BLANK.

Selecting a Calculation

- 6. Tap Calculate. The LOG and linear selection menus are displayed.
- 7. To perform log calculations, tap Log Math. To perform linear calculations, tap Linear Math. A function menu appears showing the calculation details.
- 8. Tap the calculation you want to perform. The calculation will be executed.



Note

- Trace-to-trace calculations can only be performed on C, F, or G. If the active trace is set to something other than trace C, F, or G, the Calculate key is disabled.
- If the calculation trace is remeasured or if the measurement center wavelength or measurement span is changed, the calculation is performed again and redisplayed.
- If the measurement condition (resolution) of the calculation trace is in conflict, a warning is displayed.

Calculation Mode (calculation result display)

In calculation mode, the results of calculations performed between data from different traces are written.

When a trace is set to calculation mode, subtraction between data from different traces, normalized display, power display per specified bandwidth, or curve-fit display is performed according to the specified calculation mode.

Note that only traces C, F, and G can be set to calculation mode.

Also, the available calculations vary from trace to trace.

Executable Trace-to-Trace Calculations

Trace C

LOG calculations: A-B, B-A, A+B Linear calculations: A+B, B-A, A-B, 1-k(A/B), 1-k(B/A)

Trace F

LOG calculations: C-D, D-C, C+D, D-E, E-D, D+E Linear calculations: C+D, C-D, D-C, D+E, D-E, E-D Power/NBW (A, B, C, D, E)

Trace G

LOG calculations: C-F, F-C, C+F, E-F. F-E. E+F Linear calculations: C+F, C-F, F-C, E+F, E-F, F-E Normalize (A, B, C) Curve Fit (A, B, C) Peak Curve Fit (A, B, C) Marker Fit

Calculation results are written to their corresponding traces.

Details of Calculation

The following are explanations given for traces C, F, and G.

Trace C: Calculate C

Log Math

This key is used to perform LOG calculations on trace-to-trace data and write the results to trace C.

Calculations can be applied to trace A and trace B.

If both traces selected for calculation are set to "BLANK", then the sub scale is displayed on the left side of the screen. Otherwise it is displayed on the right side. The calculation results are displayed using the sub scale.

C=A-B(LOG) Subtracts trace B from trace A in LOG form.

C=B-A(LOG) Subtracts trace A from trace B in LOG form.

C=A+B(LOG) Adds trace A and trace B in LOG form.

Linear Math

This key is used to perform linear calculations on trace-to-trace data and write the results to trace C.

Calculations can be applied to trace A and trace B.

The calculation results are displayed using the main scale.

- C=A+B(LIN) Adds trace A and trace B in linear form.
- C=A-B(LIN) Subtracts trace B from trace A in linear form.
- C=B-A(LIN) Subtracts trace A from trace B in linear form.
- C=1-k(A/B) Given Trace A and Trace B, calculates 1-k(A/B).

Calculates 1-k × (trace A/Trace B) (linear value), and writes the results to trace C.

The coefficient k may be changed in the range of 1.0000 to 20000.0000 (in steps of 0.0001) from the parameter input window. The coefficient k setting applies to both the <C=1-k(A/B)> key and <C=1-k(B/A)> key.

The trace display next to the data area also changes to "1-k(A/B)". C=1-k(B/A) Given Trace A and Trace B, calculates 1-k(B/A).

Calculates 1-k × (trace B/Trace A) (linear value), and writes the results to trace C.


The trace display next to the data area also changes to "1-k(B/A)".

Specific Examples


As shown below, this <1-kA/B \rightarrow C k=*****.*> key or <1-kB/A \rightarrow C k=*****.*> key may be used to estimate the transmission efficiency from the reflection light spectrum, or estimate the reflectivity from the transmission light spectrum for DUT.

(1)Estimating the transmission efficiency (trace C) from the reflected light spectrum (trace A)

Transmitted light spectrum (TRACE C) = 1-k (TRACE A/TRACE B)



(2)Estimating the reflectivity (trace C) from the transmitted light spectrum (trace A) Reflected light spectrum (TRACE C) = 1-k (TRACE A/TRACE B)



The value of k is an absorption coefficient which is used in determining the DUT reflectivity and transmission efficiency. Different algorithms are used depending on whether transmission efficiency or reflectivity is estimated, so the k value also varies accordingly.

The following equation can be used to determine "kr" and "kt". In the equation, Pin is the level prior to DUT input; Pout is the level after DUT input; Pre is the DUT reflection level; "kr" is the absorption coefficient used to determine the reflectivity; and "kt" is the absorption coefficient used to determine the transmission efficiency. (Each level is a linear value.)

Estimating the reflected light spectrum from the transmitted light spectrum kt = (Pin - Pre)/Pout

Estimating the transmitted light spectrum from the reflected light spectrum kr = (Pin - Pout)/Pre

Trace F: Calculate F

Log Math

This key is used to perform LOG calculations on trace-to-trace data and write the results to trace F.

Calculations can be applied to trace C, trace D, and trace E.

If both traces selected for calculation are set to "BLANK", then the sub scale is displayed on the left side of the screen. Otherwise it is displayed on the right side. The calculation results are displayed using the sub scale.

F=C-D(LOG) Subtracts trace D from trace C in LOG form.

 $\mathsf{F=D-C}(\mathsf{LOG})\;$ Subtracts trace C from trace D in LOG form.

F=C+D(LOG) Adds trace C and trace D in LOG form.

F=D-E(LOG) Subtracts trace E from trace D in LOG form.

F=E-D(LOG) Subtracts trace D from trace E in LOG form.

F=D+E(LOG) Adds trace D and trace E in LOG form.

Linear Math

This key is used to perform linear calculations on trace-to-trace data and write the results to trace F.

Calculations can be applied to trace C, trace D, and trace E. The calculation results are displayed using the main scale.

The calculation results are displayed using the main seak

F=C+D(LIN) Adds trace C and trace D in linear form.

F=C-D(LIN) Subtracts trace D from trace C in linear form.

 $\label{eq:F=D-C(LIN)} \mbox{ Subtracts trace C from trace D in linear form.}$

F=D+E(LIN) Adds trace D and trace E in linear form.

F=D-E(LIN) Subtracts trace E from trace D in linear form.

F=E-D(LIN) Subtracts trace D from trace E in linear form.

Power/NBW

See section 4.8.

Trace G: Calculate G

Log Math

This key is used to perform LOG calculations on trace-to-trace data and write the results to trace G.

Calculations can be applied to trace C, trace E, and trace F.

If both traces selected for calculation are set to "BLANK", then the sub scale is displayed on the left side of the screen. Otherwise it is displayed on the right side. The calculation results are displayed using the sub scale.

G=C-F(LOG) Subtracts trace F from trace C in LOG form.

G=F-C(LOG) Subtracts trace C from trace F in LOG form.

G=C+F(LOG) Adds trace C and trace F in LOG form.

G=E-F(LOG) Subtracts trace F from trace E in LOG form.

G=F-E(LOG) Subtracts trace E from trace F in LOG form.

G=E+F(LOG) Adds trace E and trace F in LOG form.

Linear Math

This key is used to perform linear calculations on trace-to-trace data and write the results to trace G.

Calculations can be applied to trace C, trace E, and trace F. The calculation results are displayed using the main scale.

G=C+F(LIN) Adds trace C and trace F in linear form.

G=C-F(LIN) Subtracts trace F from trace C in linear form.

G=F-C(LIN) Subtracts trace C from trace F in linear form.

G=E+F(LIN) Adds trace E and trace F in linear form.

G=E-F(LIN) Subtracts trace F from trace E in linear form.

G=F-E(LIN) Subtracts trace E from trace F in linear form.

Normalize

This is one of the trace calculation modes. The trace data is normalized and displayed. The normalization results can be written to trace G and displayed. One trace can be normalized, either trace A, B, or C.

The peak of a normalized waveform is 1 if the sub scale is linear or 0 dB if it is LOG. Data is displayed when sweeping is finished to the end.

If both traces selected for calculation are set to "BLANK", then the sub scale is displayed on the left side of the screen. Otherwise it is displayed on the right side. The calculation results are displayed using the sub scale.

The trace display next to the data area changes to "NORM @".

- G=NORM A Normalizes trace A and writes the normalized data to trace G.
- G=NORM B Normalizes trace B and writes the normalized data to trace G.
- G=NORM C Normalizes trace C and writes the normalized data to trace G.

Curve Fit

See section 4.7.

Peak Curve Fit


See section 4.7.

4

Normalized Display 4.6


Procedure

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap TRACE. A function menu appears for setting traces.
- 3. Tap Active Trace to select trace G. A function menu appears for trace G.
- 4. Tap View G DISP/BLANK to select DISP. Each time you tap, the value switches between DISP and BLANK.
- 5. Tap Calculate G.
- 6. Tap Normalize.
- 7. To normalize trace A, tap G=NORM A. To normalize trace B, tap G=NORM B. To normalize trace C, tap G=NORM C.



Example of waveform before normalization

Example of waveform after normalization



Note .


- Normalization is not possible if the waveform level is too low.
- · For a description of Normalize, see section 4.5.

4.7 Curve Fitting

Procedure


Setting the Target Trace

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap TRACE. A function menu appears for setting traces.
- 3. Tap Active Trace to select trace G. A function menu appears for trace G.
- **4.** Tap **View G DISP/BLANK** to select DISP. Each time you tap, the value switches between DISP and BLANK.
- 5. Tap Calculate G.
- 6. Tap Curve Fit. A menu for selecting the trace to curve fit is displayed.
- To curve fit trace A, tap G=CRV FIT A. To curve fit trace B, tap G=CRV FIT B. To curve fit trace C, tap G=CRV FIT C.



Setting the Calculation Target Range

- 8. Tap Threshold. A parameter input window appears.
- 9. Enter the threshold in the parameter input window.
- **10.** Tap **µm/ENT** or **nm/ENT**.
- **11.** Tap **Operation Area**. A menu for setting the calculation target range is displayed.
- **12.** Tap the range to be calculated.




Note.

For a description of the calculation target range, see the explanation.

Selecting the Curve Fitting Algorithm

- 13. Tap Fitting Algorithm. An algorithm setting menu is displayed.
- **14.** Tap the algorithm you want to use.




Note


For a description of the curve fitting algorithm, see the explanation.

Peak Curve Fitting

- 6. Continuing from step 5, tap Peak Curve Fit.
- To peak curve fit trace A, tap G=PKCVFIT A. To peak curve fit trace B, tap G=PKCVFIT B. To peak curve fit trace C, tap G=PKCVFIT C.

Step 8 and thereafter are the same as for curve fitting.





Explanation

Curve Fit Target Range

Curve fitting is performed on the specified trace waveform, and the results are written in trace G.

Calculations are performed on data from the threshold to the peak.

Set the threshold in the range of 0 to 99 dB (steps of 1).


The display in the trace setting area next to the data area changes to CRV FIT @ and MKR FIT.

Curve Fit Target Trace


Function menu display

- G=CRV FIT A Curve-fits trace A.
- G=CRV FIT B Curve-fits trace B.
- G=CRV FIT C Curve-fits trace C.
- G=MKR FIT Curve-tits the placed markers using the current measurement scale. Curve fitting is performed even when markers are placed on different traces.

Example of a curve-fitted waveform (data range: OUTSIDE L1-L2)



Example of a marker-fitted waveform (data range: ALL)



Peak Curve Fit Target Range

Peak curve fitting is performed on the specified trace waveform, and the results are written in trace G.

Calculations are performed on mode peaks that are greater than or equal to the threshold.

Set the threshold in the range of 0 to 99 dB (steps of 1).

The display in the trace setting area next to the data area changes to PKCVFIT @.

Peak Curve Fit Target Trace

Function menu display

G= PKCVFIT A Peak-curve-fits trace A.

G= PKCVFIT B Peak-curve-fits trace B.

G= PKCVFIT C Peak-curve-fits trace C.

Range of Target Data for Calculation

Vertical axis

Data from the threshold to the peak. Set the threshold in the range of 0 to 99 dB (steps of 1).

Horizontal axis

Function menu display


ALL Includes all trace data in the calculation.

INSIDE L1-L2 Includes the data between the line markers in the calculation.

OUTSIDE L1-L2 Includes the data outside the line markers in the calculation.


When INSIDE L1- L2 is selected

: Calculation target range



When OUTSIDE L1- L2 is selected

: Calculation target range



Curve Fitting Algorithm

Function menu display	Description
GAUSS	Normal distribution curve
LORENZ	Lorenz curve
3RDPOLY	3rd order polynomial
4THPOLY	4th order polynomial
5THPOLY	5th order polynomial

Note _


If G=MKR FIT is selected, fitting cannot be performed if only a small number of markers are placed. A warning appears when the number of markers is as follows. WARNING 111 : <G=MKR FIT>failed

GAUSS , LORENZ:	Fewer than three markers
3RD POLY:	Fewer than four markers
4TH POLY:	Fewer than five markers
5TH POLY:	Fewer than six markers

4.8 Power Spectral Density Trace

Procedure

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap TRACE. A function menu appears for setting traces.
- 3. Tap Active Trace to select trace F. A function menu appears for trace F.
- Tap View F DISP/BLANK to select DISP. Each time you tap, the value switches between DISP and BLANK.
- 5. Tap Calculate F.
- 6. Tap Power/NBW.
- 7. To display the power spectral density of trace A, Tap F=Pwr/NBW A. To display the power spectral density of trace B, tap F=Pwr/NBW B. To display the power spectral density of trace C, tap F=Pwr/NBW C. To display the power spectral density of trace D, tap F=Pwr/NBW D. To display the power spectral density of trace E, tap F=Pwr/NBW E.
- 8. Tap Bandwidth. A parameter input window appears.
- 9. Enter the bandwidth in the parameter input window.
- 10. Tap µm/ENT or nm/ENT.



Explanation

Power Spectral Density Trace

The power spectral density in the specified bandwidth is calculated, and the results are written in Trace F. The target trace is a single trace selected from Traces A to E. The trace display next to the data area changes to "PWR/NBW @".

In setting the unit (LEVEL UNIT) of the vertical axis in section 3.2, "Setting the Horizontal and Vertical Scales," the power per nanometer can be displayed, but here the power per the specified band in the range of 0.1 nm to 10 nm in 0.1 nm resolution can be displayed. With the analysis function using the ANALYSIS key, only PMD can be analyzed.

Level Axis Unit (Section 3.2)

Level axis units, namely dBm/nm and mW/nm, are units for displaying power per nanometer. If trace F is set to Power/NBW, the unit is automatically changed to dBm or mW.

If trace F is set to Power/NBW and you change the level axis to dBm/nm or mW/nm, trace F enters FIX mode, and the waveform is no longer updated.

4.9 Marker Display

Procedure

Displaying the Moving Marker

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap MARKER. A function menu appears for setting the marker.
- 3. Tap Marker Active OFF/ON to select ON.

Note _

- If the active trace is not set to DISP, you cannot use the moving marker. Set View @ DISP/ BLANK under TRACE to DISP.
- When Marker Active OFF/ON is set to ON, tapping the waveform display area and selecting Marker from the pop-up list displays a operation tool window for the moving marker. The operation tool window allows you to quickly set frequently used functions.

Turns on or off the moving marker Places a fixed marker

Active	Peak Bottom	Next Level Left	Next Right	Set X

Move the marker

The moving marker is also displayed when you tap **PEAK SEARCH** in the Main Menu window.

Single search function

Moving the Moving Marker


- 4. Enter the wavelength using the numeric keypad, and then tap nm/ENT.
- 5. Or, refer to the following information, and move the moving marker.

Direction	Procedure
Move to the right	Drag to the right the dotted line that appears when you tap the moving marker. Tap the right arrow key in the operation tool window.
Move to the left	Drag to the left the dotted line that appears when you tap the moving marker.
	Tap the left arrow key in the operation tool window.

Placing Fixed Markers


- **4.** With the moving marker displayed, tap Set Marker. A function menu with Set and a parameter input window appear.
- **5.** Enter a marker number in the parameter input window, and tap **Set**. A fixed marker is placed at the current moving marker position.

If you do not enter a marker number, the number is assigned automatically in order from 001.



Clearing a Fixed Marker

- 6. Tap Clear Marker.
- 7. Enter the fixed marker number you want to clear in the parameter input window.
- 8. Tap Clear.



Clearing All Markers

6. Tap **All Marker Clear**. All markers (moving marker and fixed markers) displayed on the screen will be cleared.

The Marker Active settings is also set to OFF.

Using the Moving Marker to set the Center Wavelength to Be Measured, the Zoom Center Wavelength, and the Reference Level

Setting the Center Wavelength to Be Measured to the Moving Marker Wavelength

With the moving marker displayed, tap **Marker** \rightarrow **Center**. The value of the center wavelength to be measured is displayed in a parameter input window. For a description of the center wavelength, see section 3.5, "Setting the Center Wavelength (Center Frequency)."

You can adjust the center wavelength further in the parameter input window.

Note _

Marker \rightarrow Center cannot be used under the following conditions.

- When the moving marker is off
- · When both spit screens are on hold.
- When the span of the measured data is 0 nm.

Setting the Zoom Center Wavelength to the Moving Marker Wavelength

With the moving marker displayed, tap **Marker** \rightarrow **Zoom Ctr**. The value of the zoom center wavelength is displayed in a parameter input window. For a description of the zoom center wavelength, see section 4.1, "Zooming a Waveform."

You can adjust the zoom center wavelength further in the parameter input window.

Note.


Marker \rightarrow Zoom Ctr cannot be used under the following conditions.

- When the moving marker is off
- When both spit screens are on hold.
- When the span of the measured data is 0 nm.

Setting the Reference Level to the Moving Marker Level

With the moving marker displayed, tap **Marker** \rightarrow **Ref Level**. The value of the reference level is displayed in a parameter input window. For a description of the reference level, see section 3.4, "Setting the Reference Level." The displayed waveform is redrawn according to the new reference level.


You can adjust the reference level further in the parameter input window.



Setting the Marker Difference Value Display

You can set the marker difference display displayed in the data area to OFFSET or SPACING.

- 1. Tap **= Menu**. The Main Menu window appears.
- 2. Tap MARKER.
- **3.** Tap **More** to display the More 3/3 function menu.
- 4. Tap Marker Display. A menu for selecting the difference value display appears.
- 5. Tap Offset or Spacing.




Note

When Offset is selected, the difference between the moving marker ($\mathbf{\nabla}$) and each fixed marker is displayed. When Spacing is selected, the difference between the moving marker and the smallest numbered fixed marker is displayed along with the differences between fixed markers.

Automatically Updating the Level Values of the Fixed Markers


The level values of fixed markers are updated each time the displayed waveform is updated.

- 1. Tap **E Menu**. The Main Menu window appears.
- 2. Tap MARKER.
- 3. Tap More to display the More 3/3 function menu.
- 4. Tap Marker Auto Update OFF ON to select ON.



Setting the Unit of Marker Values

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap MARKER.
- 3. Tap More to display the More 3/3 function menu.
- **4.** Tap **Marker Unit nm THz**. Each time you tap, the value switches between nm and THz.




Note

The unit displayed for marker values (wavelength or frequency) can be set separately from the waveform display's horizontal scale unit set with Horizontal Scale nm THz.

Displaying Wavelength Line Markers


- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap MARKER. A function menu appears for setting the marker.
- 3. Tap More to display the More 2/3 function menu.
- **4.** Tap Line Marker 1 OFF/ON or Line Marker 2 OFF/ON to select ON. Line marker values are displayed in the upper left of the waveform area.



Note.

- Wavelength line markers cannot be displayed if the active trace measurement span is 0.000 nm.
- When both wavelength line markers 1 and 2 are displayed, the wavelength difference (L2– L1) is shown below the marker values.
- Tapping the waveform display area and selecting X Line Marker from the pop-up list displays
 a operation tool window for the wavelength line markers. The operation tool window allows
 you to quickly set frequently used functions.

Move the line marker



Turn on and select the line marker

Moving the Line Markers

5. Refer to the following information, and move the line markers.

Direction	Procedure
Move to the right	Drag the line marker to the right. Tap the right arrow key in the operation tool window.
Move to the left	Drag the line marker to the left. Tap the left arrow key in the operation tool window.

Clearing the Line Markers

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap MARKER. A function menu appears for setting the marker.
- 3. Tap More to display the More 2/3 function menu.
- 4. Tap Line Marker 1 OFF/ON or Line Marker 2 OFF/ON to select OFF.

Setting Measurement Sweep Span & Display Sweep Span with Line Markers

Setting the Measurement Sweep Span to the Span between Line Markers 1 and 2 <<See section 3.6 for details>>


With line markers 1 and 2 displayed, tap **Marker L1-L2** \rightarrow **Span**. The value of the sweep span is displayed in a parameter input window. The measurement sweep span, measurement start wavelength, and measurement stop wavelength will be changed. You can adjust the measurement sweep span further in the parameter input window. The setting range is 0.1 to 450.0 nm (in steps of 0.1 nm).

Setting the Zoom Span of the Display Scale to the Span between Line Markers 1 and 2

With line markers 1 and 2 displayed, tap **Marker L1-L2** \rightarrow **Zoom Span**. The value of the display sweep span is displayed in a parameter input window. The displayed waveform is redrawn according to the new Zoom Span.

Note.

- If only line marker L1 is displayed, the zoom stop wavelength is set to the wavelength at the right edge of the screen. If only line marker L2 is displayed, the zoom start wavelength is set to the wavelength at the left edge of the screen.
- Marker L1-L2 → Span and Marker L1-L2 → Zoom Span cannot be used under the following conditions.
 - When both L1 and L2 are off.
 - When both spit screens are on hold.
 - When the span of the active trace is 0 nm.




Note .

For instructions on how to analyze between line markers, see section 5.12, "Specifying an Analysis Range."


Displaying Level Line Markers

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap MARKER. A function menu appears for setting the marker.
- 3. Tap More to display the More 2/3 function menu.
- **4.** Tap Line Marker 3 OFF/ON or Line Marker 4 OFF/ON to select ON. Line marker values are displayed in the upper left of the waveform area.



Note

- When both level line markers 3 and 4 are displayed, the level difference (L4–L3) is shown below the marker values.
- Tapping the waveform display area and selecting Y Line Marker from the pop-up list displays
 a operation tool window for the level line markers. The operation tool window allows you to
 quickly set frequently used functions.



Moving the Level Line Markers

5. Refer to the following information, and move the level line markers.

Direction	Procedure
Move up	Drag the line marker up. Tap the up arrow key in the operation tool window.
Move down	Drag the line marker down. Tap the down arrow key in the operation tool window.

Clearing All Markers


Tap Line Marker All Clear. All line markers (wavelength line markers and level line markers) displayed on the screen will be cleared.

Displaying Advanced Markers

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap MARKER. A function menu appears for setting the markers.
- 3. Tap Advanced Marker.


A function menu appears for setting the advanced marker markers.

- 4. Tap Adv. Marker Active OFF/ON to select ON.
- Tap any of the keys from Marker 1 Select to Marker 4 Select.
 A function menu appears for setting the advanced marker type and the trace to place the marker on.
- 6. Tap Marker Trace. Traces A through G are displayed in a function menu.
- **7.** Tap the trace to place the marker on. The marker can now be displayed on the selected trace waveform.



Note _

- If the active trace is not set to DISP, you cannot use the advanced markers. Set View@DISP/BLANK under TRACE to DISP.
- If Adv. Marker Active OFF/ON is set to ON, the moving marker (Marker Active OFF/ON) described on page 4-29 will automatically turn off. Likewise, if you turn on the moving marker (Marker Active OFF/ON) described on page 4-29, Adv Marker Active OFF/ON is set to OFF.
- When Adv. Marker Active OFF/ON is set to ON, tapping the waveform display area and selecting Marker from the pop-up list displays a operation tool window for the advanced markers. The operation tool window allows you to quickly set frequently used functions.



Displaying the Moving Marker

- eb 16 19:55 /DSP **≡ M**enu YCKCGAWA ♠ <a br/>
 <a br/>
 CADVANCED MARKER> BANDWIDTH: 0.1nm M1(NORM) : (TrA) 1549.3000nm 8.15dBm M2(OFF) : M3(OFF) : Marker Trace Meas. Conditions SPEED
 Yeas. Conditions>


 START:
 1546.800 nm

 RES:
 0.1 nm

 SENS:
 MID
 CENTER: 1549.300 nm SPAN: 5.0 nm RES: 28.2 SMPL 501(A) NORMAL MKR1 X 1549.3000nm Moving marker 8. ntegral ▲ ▼ FINE _ -11 8 9 🖪 Integral Range ±25.0 7 4 5 6 µm/ -31. 1 2 3 nm/ ENT 10.0 0 . --51. 71.8 1546.80 0.50 nr LVL WL NOI SRC SRC VAC AUT AUT AUT AUT AUT AUT AUT SWE SMC RPT SGL STP
- **8.** Tap **Normal**. The moving marker appears on the waveform.

Displaying the Power Spectral Density Marker

- 8. Tap Power Density. A power spectral density marker appears on the waveform.
- 9. Tap Return. The menu returns to the previous level.
- 10. Tap Bandwidth. A parameter input window appears.
- **11.** Enter the normalization bandwidth in the parameter input window.
- 12. Tap µm/ENT or nm/ENT.




Note

The power spectral density marker cannot be assigned to a differential waveform (based on LOG values) or normalized waveform.

Displaying the Integrated Power Marker

- 8. Tap Integral Power. An integrated power marker appears on the waveform.
- 9. Tap Integral Range. A parameter input window appears.
- 10. Enter the integration frequency range in the parameter input window.
- 11. Tap µm/ENT or nm/ENT.



Note -

The integrated power marker cannot be assigned to a differential waveform (based on LOG values) or normalized waveform.

Moving an Advanced Marker

Enter a wavelength in the parameter input window, and tap **nm/ENT**. The parameter input window appears at the same time when an advanced marker is displayed in step 8.

Or, move the advanced marker by referring to the information below.

Direction	Procedure
Move to the right	Drag to the right the dotted line that appears when you tap the advanced marker.
	Tap the right arrow key in the operation tool window.
Move to the left	Drag to the left the dotted line that appears when you tap the advanced marker.
	Tap the left arrow key in the operation tool window.


4

Performing a Single Search Using an Advanced Marker

- 1. Tap = Menu. The Main Menu window appears.
- 2. Tap MARKER. A function menu appears for setting the markers.
- 3. Tap Advanced Marker.

A function menu appears for setting the advanced marker markers.

4. Tap Search. A function menu appears for searching.



Note .

If the advanced marker is turned off, the Search key will be unavailable.

Finding the Peak Wavelength/Level

5. Tap **Peak Search**. An advanced marker is set to the peak (maximum value) of the waveform, and the marker values are displayed in the data area.

Finding the Bottom Wavelength/Level

5. Tap **Bottom Search**. An advanced marker is set to the bottom (minimum value) of the waveform, and the marker value is displayed in the data area.

Finding the Next Peak/Bottom Level

6. When the advanced marker is displayed at the peak or bottom of the waveform, tap **Next Level Search**. On the marker trace waveform, the moving marker at the peak or bottom is set to the next peak (local maximum value) or bottom (local minimum value).

Finding the Level Peak/Bottom to the Right of the Advanced Marker

6. When the advanced marker is displayed at the peak or bottom of the waveform, tap Next Search Right. The advanced marker is set to the next peak (local maximum value) or bottom (local minimum value) on the right.

Finding the Level Peak/Bottom to the Left of the Advanced Marker


6. When the advanced marker is displayed at the peak or bottom of the waveform, tap Next Search Left. The advanced marker is set to the next peak (local maximum value) or bottom (local minimum value) on the left.

Turning Off the Advanced Marker Display

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap MARKER. A function menu appears for setting the markers.
- 3. Tap Advanced Marker.

A function menu appears for setting the advanced marker markers.

- **4.** Tap any of the keys from **Marker 1 Select** to **Marker 4 Select** that you want to turn off.
- 5. Tap off.



Note _

The advanced marker display automatically turns off if you perform any of the following operations.

- Execute auto measurement (section 3.1)
- Clear all traces (section 4.12)
- Change the vertical axis settings (section 3.2) and execute a measurement (section 3.13)
- Change the number of samples (section 3.8) and execute a measurement (section 3.13)


Clearing All Advanced Markers

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap MARKER. A function menu appears for setting the markers.
- 3. Tap Advanced Marker.

A function menu appears for setting the advanced marker markers.

4. Tap **All Clear**. All displayed advanced markers (moving markers, power spectral density markers, and integrated power markers) are cleared.

Tapping **Adv. Marker Active OFF/ON** and selecting OFF also clears all advanced markers.



Explanation

Markers

Moving Marker

You can move the moving marker to any wavelength by entering the wavelength in the parameter input window. You can also drag the moving marker.

The moving marker moves along the waveform and show the marker values (wavelength and level) in the data area. If you fix the moving marker at a given position, a fixed marker is displayed.

The moving marker works on the active trace.

Fixed Markers

A marker fixed to a specific number using the moving marker is called a fixed marker. You can place up to 1024 fixed markers. Fixed markers can be placed across different traces.

Fixed markers are assigned marker numbers in order from 001. You can also enter a specific number in the parameter input window. The maximum number that can be assigned is 1024.

Marker Data in the Data Area

The data area shows the marker values (wavelength value and level value) of the displayed moving marker and fixed markers.

When there are five or more fixed markers, all the fixed markers cannot be displayed in the data area. To view the values of markers that are not displayed, drag the data area to scroll it. Scrolling is possible when the moving marker is on and active.

Trace with moving marker (Active trace)

Wavelength and level of the moving marker Moving marker value – fixed marker value

		/	
YOKOGAWA 🔶			
TR A ΔΝΡΚ : 1552.2800nm TR A Δ0001: 1550.7000nm Δ0002: Δ0003: Δ0004: Δ0005:		Δ-Δn: / 1.5800nm	-0.04dB
	//		

Trace with fixed marker 1

Wavelength and level of fixed marker 1

A number is displayed with a fixed marker.

				— Moving	marker		
- 10.0 dBm	R E F·····	 	 ញ				
-30.0		 []				 	

Marker Display

This key is used to set whether to display the difference relative to the moving marker (Offset) or the difference relative to the next marker (Spacing) in the marker display. (Default: Offset)

If the active trace span is 0 nm, the wavelength difference relative to the moving marker is 0.000 nm.

If a fixed marker is placed at the -210 dBm wavelength value, "???????" is displayed as the level difference from that fixed marker.

When a fixed marker is positioned and the moving marker is set to a wavelength value of -210 dBm, the level difference is set to -210.00 dB, regardless of the fixed marker's level.

Offset

Sets the difference value display as the difference between each marker and the moving marker (Offset).

YOKOGAWA	٠
TOROGAWA	•

TR A Δ0001: 1555.5200nm -19.96dBm Δ-Δh: TR A Δ0001: 1550.7000nm -19.94dBm 4.8200nm -0.02dB TR A Δ0002: 1552.2800nm -19.98dBm 3.2400nm 0.02dB TR A Δ0003: 1553.9000nm -19.92dBm 1.6200nm -0.04dB Δ0004: Δ0005: -0.04dB -0.04dB	TR A Δ0002: 1552.2800nm TR A Δ0003: 1553.9000nm Δ0004:	-19.98dBm	3.2400nm	0.02dB	

Spacing

Sets the difference value display as the difference between each marker and the next marker.

	 -	
	~ A1	

YUKUGAWA 🕈			
TR A ΔΝΡΚ : 1555.5200nm TR A Δ0001: 1550.7000nm TR A Δ0002: 1552.2800nm TR A Δ0003: 1553.9000nm Δ0004: Δ0005:	-19.96dBm -19.94dBm -19.98dBm -19.92dBm	SPACING: -4.8200nm 1.5800nm 1.6200nm	0.02dB -0.04dB 0.06dB

Line Markers

There are four line markers: two wavelength line markers and two level line markers. Wavelength line markers show wavelengths and wavelength difference while level line markers show levels and level difference.

In addition, line markers can be used to specify a sweep range or analysis range.

Wavelength Line Markers

When line markers are displayed, the marker values are shown in the upper left of the waveform area.

When both wavelength line markers 1 and 2 are displayed, the wavelength difference (L2–L1) is shown below the marker values.

Level Line Markers

When line markers are displayed, the marker values are shown in the upper left of the waveform area.

When both level line markers 3 and 4 are displayed, the level difference (L4–L3) is shown below the marker values.

<meas. conditions=""></meas.>
START: 1543.200 nm / STOP: 1563.200 nm CENTER:
RES: 0.2 nm / SENS: NORM/HOLD AVG:
10.0
L1:1552.2667nm
L2:1557.1333nm
L3: -24.57dBm
L4: -48.24dBm
1211 49666.000
-10.0 KEF 14.12
dBm
-30.0

Marker values are displayed.


Wavelength difference (L2 - L1) and level difference (L4 - L3) are displayed.

Note _

You can move a line marker by dragging it. When you move a line marker, the line marker in the overview window also moves accordingly.

Line Markers in the Overview Window

The instrument displays an overview window when the display scale is increased or decreased. When line markers are displayed, they are also displayed on the overview window.



Line markers are synchronized.

Advanced Markers

There are four advanced markers.

There are three types of advanced markers: moving marker, power spectral density marker, and integrated power marker. Advanced markers can be placed on any of the waveforms from trace A to G.

Moving Markers


You can move a moving marker to any wavelength by entering the wavelength in the parameter input window. You can also drag a moving marker.

Moving markers move along the waveform and show marker values (wavelength and level) in the data area.

If two markers are displayed, the wavelength difference and level difference between the markers are displayed.

When marker 1 (M1) and marker 2 (M2) are displayed: marker 2 – marker 1 (M2–1) When marker 3 (M3) and marker 4 (M4) are displayed: marker 4 – marker 3 (M4–3) The moving markers of the advanced marker function are the same as the moving marker of the marker function. However, the fixed marker function is not available.

Marker number



Moving marker ——

A number is displayed with the moving marker. When active, the marker is solidly filled.

Power Spectral Density Markers

Power spectral density markers show power values per normalization bandwidth by assuming the marker position on the waveform to be the center. The power values are displayed in the data area. They are used to determine converted power values per given bandwidth such as when measuring the signal noise level.

The selectable normalization bandwidth range is 0.1 to 10.0 nm. When entering with the arrow keys when COARSE is selected, the value changes in steps of 1 nm. When FINE is selected, the value changes in steps of 0.1 nm.

The way to move the markers and the data display between markers are the same as with the above-mentioned moving markers.

Advanced marker type: /BW (power spectral density marker)

Normalization bandwidth

Power values at the power spectral density markers

YOKOG	MA 🔶			
<adva< td=""><td>ICED MARKER> BANDWIDTH: 0.</td><th>1nm -</th><td></td><td></td></adva<>	ICED MARKER> BANDWIDTH: 0.	1nm -		
M1(/BV	V) :(TrA) 1553.8800nm -22.96dE	m/BW	M2-1:	-1.4200nm
M2(/BV	V) : (TrA) 1552.4600nm -47.86dE	m/BW		-24.90dB
M3(/BV	V) : (TrA) 1554.1400nm -53.62dE	m/BW	M4-3:	0.6000nm
M4(/BV		Im/BW		-15.51dB
-				

Integrated Power Markers

Integrated power markers show integrated power values over specified frequency ranges by assuming the marker position on the waveform to be the center. The power values are displayed in the data area. These markers are used to determine the integrated power of a widely spread spectrum such as to determine the signal level from a modulated optical signal spectrum. The selectable range of frequencies to integrate over is 1.0 to 999.9 GHz. When entering with the arrow keys when COARSE is selected, the value changes in steps of 10 GHz. When FINE is selected, the value changes in steps of 1 GHz. To determine the signal level of a modulated optical signal, set the integration frequency range so that the point approximately –30 dB below the spectrum peak is included.

The waveform in the integration range appears highlighted (in blue). The way to move the markers and the data display between markers are the same as with the above-mentioned moving markers.

Advanced marker type: INTG (integrated power marker)

Integrated power marker power values

OKOG	CED MARKER>	BAN	OWIDTH: 0.1nm	_	
M1(IN	G) :(TrA) 155	3.8800nm	-21.81dBm(7.0GHz)	12-1:	-1.4200nm -1.56dB
M2(INT M3(INT	G) :(TrA) 155 G) :(TrA) 155		-23.37dBm(25.0GHz) -53.12dBm(4.0GHz)	M4-3:	-1.56dB 0.6000nm
M4(INT	G) : (TrA) 155	4.7400nm	-62.88dBm(25.0GHz)		-9.76dB

Note

When advanced markers are in use, the marker levels at the end of measurements are automatically updated.

4.10 Displaying a Split Screen

Procedure

The screen can be split vertically into two windows (split mode). The trace waveform can be assigned to either window.


Splitting the Screen

- 1. Tap **= Menu**. The Main Menu window appears.
- 2. Tap DISPLAY. A function menu appears for setting the screen.
- **3.** Tap **Split Display**. The screen is split vertically into two windows, and a function menu appears for assigning traces.

Selecting the Window (Top or Bottom) to Display the Traces In

4. Tap the trace you want to change the screen assignment of. Select a trace from Trace A to Trace G. Each time you tap, the trace assignment changes between the top and bottom windows.

By default, traces A, B, D, and E are assigned to the top window and traces C, F, and G are assigned to the bottom window.



Fixing a Trace

4. Tap Hold.

Fixing/Releasing a Trace in the Upper Window

Tap Upper Hold OFF / ON. The traces assigned to the top window as well as the scale are fixed.

To release them, tap **Upper Hold OFF / ON** again. The display scale and waveforms are updated to the most recent states.

Fixing/Releasing a Trace in the Lower Window

5. Tap Lower Hold OFF / ON. The traces assigned to the bottom window as well as the scale are fixed.

To release them, tap **Lower Hold OFF / ON** again. The display scale and waveforms are updated to the most recent states.

Returning to the Normal Display

- 2. Tap DISPLAY. A function menu appears for setting the screen.
- 3. Tap Normal Display. The screen returns to the normal display (one window).

Explanation

Hold

The hold function is used to display waveforms measured with different wavelength ranges in the top and bottom windows of the screen. For example, you can measure trace A in the top window and hold it, change the measurement conditions, and measure trace B in the bottom window. The hold function has the following features. They are the same for the top and bottom windows.


- The display scale is fixed.
- The traces are fixed.
- Setting the window showing the active trace (Write @) to hold automatically fixes the active trace. (Fix @)
- When the screen is changed from Hold to Normal Display, the display scale is set to the last specified display scale.
- Changing a held trace (fix state) to any other state automatically releases the hold. When this happens, a warning message will be displayed.

4.11 Noise Mask

Procedure

This key is used to display a waveform so that parts of the waveform at or below the specified value are masked. In addition, when a noise mask value is set, the waveform is overwritten in real time.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap DISPLAY. A function menu appears for setting the screen.
- 3. Tap Noise Mask. A parameter input window appears.
- 4. Enter the noise mask value in the parameter input window.
- 5. Tap µm/ENT or nm/ENT.
- 6. Tap Mask Line VERT/HRZN to select VERT or HRZN.



Note.


- The noise mask setting range is OFF (-999) and -100 to 0. When entering with the arrow keys when COARSE is selected, the value changes in steps of 10. When FINE is selected, the value changes in steps of 1.
- You can also set the parameter by tapping the key at the bottom of the screen. When the noise mask is not off, the shortcut key is highlighted.

Explanation

Noise Mask Type


HRZN

Displays the waveform with level values at or below the mask value as the mask value.



VERT

Displays the waveform with level values at or below the mask value as the display lower limit value (–210 dBm).



Note


The noise mask function is disabled when the vertical scale is linear.

4.12 Copying and Clearing Traces

Procedure

Copying Traces

- **1.** Tap **≡ Menu**. The Main Menu window appears.
- 2. Tap TRACE. A function menu appears for setting traces.
- 3. Tap More to display the More 2/2 function menu.
- 4. Tap Trace Copy.
- **5.** Tap **Source Trace**to select the copy source trace (A to G). When you make the selection, the menu returns to the previous level.
- **6.** Tap **Destination Trace**to select the copy destination trace (A to G). When you make the selection, the menu returns to the previous level.



7. Tap Copy Execute. The copy will be executed.

Note .


- · After the copy is executed, the copy destination trace status changes to FIX and DISP.
- If the copy source and destination trace are the same, Copy Execute will be disabled.

Clearing Traces

- **1.** Tap **Menu**. The Main Menu window appears.
- 2. Tap TRACE. A function menu appears for setting traces.
- 3. Tap More to display the More 2/2 function menu.
- 4. Tap Trace Clear.


You can also tap Trace Clear in the function menu that appears when you tap DISPLAY on the Main Menu window.

- 5. Tap the trace (A to G) you want to clear the data of.
- 6. To clear the data of all traces, tap All Trace.



Trace List

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap TRACE. A function menu appears for setting traces.
- 3. Tap Trace List.



4.13 Single Search


Procedure

Selecting the Single Search

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap PEAK SEARCH. A function menu appears for detecting peak values.
- 3. Tap More to display the More 2/2 function menu.
- Tap Search Mode to select SINGL.
 In the default settings, SINGL (single search) is selected.
- 5. Tap More to display the More 1/2 function menu.

Finding the Peak Wavelength/Level

6. Tap **Peak Search**. A moving marker is set to the peak (maximum value) of the waveform, and the marker values are displayed in the data area.



Finding the Bottom Wavelength/Level

6. Continuing from step 5, tap **Bottom Search**. A moving marker is set to the bottom (minimum value) of the waveform, and the marker value is displayed in the data area.

Note_

If the active trace is not set to DISP, you cannot use the moving marker. Set View @ DISP BLANK under TRACE to DISP.

Finding the Next Peak/Bottom Level

6. When the moving marker is displayed at the peak or bottom of the waveform, tap **Next Level Search**. On the marker trace waveform, the moving marker at the peak or bottom is set to the next peak (local maximum value) or bottom (local minimum value).

Finding the Level Peak/Bottom to the Right of the Moving Marker


6. When the moving marker is displayed at the peak or bottom of the waveform, tap Next Search Right. The moving marker is set to the next peak (local maximum value) or bottom (local minimum value) on the right.

Finding the Level Peak/Bottom to the Left of the Moving Marker

6. When the moving marker is displayed at the peak or bottom of the waveform, tap Next Search Left. The moving marker is set to the next peak (local maximum value) or bottom (local minimum value) on the left.


Setting the Minimum Peak/Bottom Difference of the Mode Judgment Reference

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap **PEAK SEARCH**. A function menu appears for detecting peak values.
- 3. Tap More to display the More 2/2 function menu.
- 4. Tap Mode Diff. A parameter input window appears.
- **5**. Enter the minimum peak/bottom difference of the mode judgment reference in the parameter input window.
- 6. Tap nm/ENT.



Auto Search

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap **PEAK SEARCH**. A function menu appears for detecting peak values.
- **3.** Tap **More** to display the More 2/2 function menu.
- 4. Tap Auto Search to select ON.



Explanation

The instrument detects the peak (the maximum level value) or bottom (the minimum level value) of the measured waveform.

Peak Search

A peak search (a search for the maximum level value) is performed on the active trace waveform. The moving marker is displayed at the peak point, and the marker value is displayed in the data area. If the peak level is off the screen, its marker is displayed at the top or bottom edge of the screen. Even in this situation, the correct marker value is displayed.

For details on using the moving marker after executing a measurement, see section 4.9, "Marker Display."

Bottom Search

A bottom search (a search for the minimum level value) is performed on the active trace waveform. The moving marker is displayed at the bottom point, and the marker value is displayed in the data area. If the bottom is off the screen, its marker is displayed at the top or bottom edge of the screen. Even in this situation, the correct marker value is displayed.

For details on using the moving marker after executing a measurement, see section 4.9, "Marker Display."

Next Level Search

On the active trace waveform, the moving marker at the peak or bottom is set to the next peak (local maximum value) or bottom (local minimum value).

If such peak or bottom is not found, a warning appears.

WARNING 103 : No data in active trace

Next Search Right

On the active trace waveform, the moving marker at the peak or bottom is set to the peak (local maximum value) or bottom (local minimum value) on its right.

If such peak or bottom is not found, a warning appears.

WARNING 103 : No data in active trace

Next Search Left

On the active trace waveform, the moving marker at the peak or bottom is set to the peak (local maximum value) or bottom (local minimum value) on its left.

If such peak or bottom is not found, a warning appears.

WARNING 103 : No data in active trace

Set Marker Set

Sets a fixed marker with the assigned number at the moving marker position. The number can be assigned in the range of 001 to 1024. The default number is one greater than the highest fixed marker number among the currently set markers or 001 if no markers have been set.

If Marker Active is set to OFF, Set Marker is disabled.

Clear Marker Clear

Clears the specified fixed marker number. The marker value in the data area is also cleared.

The default fixed marker number to be cleared is the last assigned fixed marker number.

4

All Marker Clear

Clears all currently displayed moving markers and fixed markers.

Mode Diff

Sets the minimum peak/bottom difference (dB) serving as a basis for mode determination during mode detection.

The setting range is 0.01 to 50.00 dB (FINE: steps of 0.01, coarse: steps of 1). You set the value in a parameter input window. (Default value: 3.00 dB)

Search / Ana Marker L1-L2

When set to ON and wavelength line markers L1 and L2 are set, peak searching, bottom searching (PEAK SEARCH in the Main Menu window), and analysis function (ANALYSIS in the Main Menu window) calculations are only applied between line markers 1 and 2. The setting applies to MARKER, PEAK SEARCH, and Search / Ana Marker L1-L2 of ANALYSIS.

If wavelength line markers L1 and L2 are not set, the key is disabled even when Search / Ana Marker L1-L2 is set to ON. (Default value: OFF)

You can also set the parameter by tapping the $\frac{|\mathbf{x}|^2}{|\mathbf{x}|^2}$ shortcut key at the bottom of the screen. When set to on, the shortcut key is highlighted.

Note

- If both L1 and L2 are set, the functions are executed between line markers 1 and 2.
- If only L1 is set, the function is executed from line marker 1 to the right edge of the screen.
- If only L2 is set, the function is executed from the left edge of the screen to line marker 2.

Search / Ana Zoom Area

When set to ON, peak searching, bottom searching (PEAK SEARCH in the Main Menu window), and analysis function (ANALYSIS in the Main Menu window) are only applied to data in the ZOOM SPAN range.

The setting applies to MARKER, PEAK SEARCH, and Search / Ana Zoom Area of ANALYSIS.

When this key and the SEARCH/ANA L1-L2 key are set to ON, calculations are applied to data that are both within the ZOOM SPAN range and between line markers 1 and 2. (Default value: ON)

You can also set the parameter by tapping the $\frac{SRC}{20M}$ shortcut key at the bottom of the screen. When set to on, the shortcut key is highlighted.

Auto Search

The peak or bottom value is detected automatically every time a sweep is performed.

Auto Search

Turns on or off peak/bottom searching that is performed every sweep.

When set to ON, a peak/bottom search is performed automatically and a moving marker is set automatically after sweeping ends. (Default value: OFF)

You can also set the parameter by tapping the $\frac{AuT}{SRC}$ shortcut key at the bottom of the screen. When set to on, the shortcut key is highlighted.

4.14 Multi Search


Procedure

Selecting the Multi Search

- 1. Tap **= Menu**. The Main Menu window appears.
- 2. Tap PEAK SEARCH. A function menu appears for detecting peak values.
- 3. Tap More to display the More 2/2 function menu.
- 4. Tap Search Mode to select MULTI. In the default settings, SINGL (single search) is selected. When you select MULTI, a peak search or a bottom search is executed. Which search is executed depends on which key, Peak Search or Bottom Search, has been selected on the More 1/2 function menu.
- 5. Tap More to display the More 1/2 function menu.

Finding Multiple Peak Wavelengths/Levels

6. Tap **Peak Search**. Fixed markers are set on the multiple peaks of the waveform, and the marker values are displayed in the data area. The moving marker is set on the highest peak.



Finding Multiple Bottom Wavelengths/Levels

 Continuing from step 5, tap Bottom Search. Fixed markers are set on the multiple bottoms of the waveform, and the marker values are displayed in the data area. The moving marker is set on the lowest bottom.

Note _

- If the active trace is not set to DISP, you cannot use the moving marker. Set View @ DISP BLANK under TRACE to DISP.
- The moving marker is also displayed when you tap PEAK SEARCH in the Main Menu window.

Finding the Next Peak/Bottom Level

The procedure is the same as the procedure shown for the single search in the previous section.

Finding the Level Peak/Bottom to the Right of the Moving Marker

The procedure is the same as the procedure shown for the single search in the previous section.

Finding the Level Peak/Bottom to the Left of the Moving Marker

The procedure is the same as the procedure shown for the single search in the previous section.

Setting the Mode (Peak/Bottom) Detection Threshold and the Detection List Sort Order


- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap **PEAK SEARCH**. A function menu appears for detecting peak values.
- **3.** Tap **More** to display the More 2/2 function menu.
- **4.** Tap **Multi Search Setting**. A function menu appears for setting the mode (peak/ bottom) detection threshold and the marker number assignment order.

Setting the Mode (Peak/Bottom) Detection Threshold

- 5. Tap Threshold. A parameter input window appears.
- 6. Enter the mode detection threshold in the parameter input window.
- 7. Tap nm/ENT.

Setting the Detection List Sort Order

5. Tap Sort by. Each time you tap, the value switches between WL and LVL.



Explanation

The instrument detects multiple peaks (maximum level values) or bottoms (minimum level values) of the measured waveform at the same time.

Threshold

Set the threshold (detection range level) that is used when the multi search detects modes (peaks/bottoms).

For peak searches, the peak detection range is defined as being the levels from the measured waveform's maximum peak to the threshold value.

For bottom searches, the bottom detection range is defined as being the levels from the measured waveform's minimum bottom to the threshold value.

Sort by

The detected marker values are displayed as a list in the data area. This setting sets the sort order of the detection list.

- WL: Wavelengths are displayed in order starting from the shortest wavelength.
- LVL: For the peak search, levels are displayed in order starting from the highest level. For the bottom search, levels are displayed in order starting from the lowest level.

Peak Search

A peak search (a search for the maximum level values) is performed on the active trace waveform. Fixed markers are displayed on the peak points. The moving marker is displayed on the maximum peak (the maximum level value). The marker values are displayed in the data area. If the peak level is off the screen, its marker is displayed at the top or bottom edge of the screen. Even in this situation, the correct marker value is displayed.

For details on using the moving marker after executing a measurement, see section 4.9, "Marker Display."

If there are five or more data values, you can drag the data area to scroll.

Bottom Search

A bottom search (a search for the minimum level values) is performed on the active trace waveform. Fixed markers are displayed on the bottom points. The moving marker is displayed on the minimum bottom (the minimum level value). The marker values are displayed in the data area. If the bottom is off the screen, its marker is displayed at the top or bottom edge of the screen. Even in this situation, the correct marker value is displayed.

For details on using the moving marker after executing a measurement, see section 4.9, "Marker Display."

If there are five or more data values, you can drag the data area to scroll.

Other Keys

The following keys are also displayed on the PEAK SEARCH function menu. These keys have the same functions as the functions explained in the previous section on the single search. For details, see the explanation in the previous section.

Next Level Search Next Search Right Next Search Left Set Marker Set Clear Marker Clear All Marker Clear Mode Diff Search / Ana Marker L1-L2 Search / Ana Zoom Area Auto Search

Note -


The Mode Diff (mode judgment reference)—the peak/bottom difference—setting is shared between the multi search and single search.

5.1 Spectral Width Measurement

Procedure

Spectral width can be measured from the measured waveform.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap ANALYSIS. A function menu appears for analyzing measured waveforms.
- 3. Tap Spec Width. A menu appears for selecting the analysis algorithm.
- Tap THRESH, ENVELOPE, RMS, or PEAK RMS. Analysis is performed, and the results are displayed in the data area.



When changing the analysis parameters


- Continuing from step 4, tap Parameter Setting. An analysis parameter setting screen appears.
- 6. Tap within the frame of values, and set them.

If a parameter input window appears, enter the value in the window.

For check boxes, you can also use the arrow keys on the function menu to move the cursor and tap **Select**.

- Tap X to close the analysis parameter setting screen. You can also tap Close Window on the function menu. The function menu returns to the previous level.
- **8.** Tap **Analysis Execute**. Analysis is performed according to the changed parameters, and the results are displayed in the data area.

5.1 Spectral Width Measurement



Note -

You can also perform the currently set analyze by tapping Analysis Execute on the pop-up list. To display the pop-up list, tap or right-click the waveform display area showing the waveform. For details, see section 3.2, "Menu Operations" in IM AQ6360-02EN.



If you want to change just the threshold level, you can use Spec Width Thresh.

Changing the Threshold Value for Each Algorithm

- **5.** Continuing from step 4, tap **Spec Width Thresh**. A parameter input window appears.
- 6. Enter the value in the parameter input window.
- 7. Tap µm/ENT or nm/ENT.

Automatic Analysis on Each Sweep

 Continuing from step 4, tap Auto Analysis OFF ON to select ON. At the end of each sweep, the Spec Width, Analysis 1, or Analysis 2 function (whichever is selected) is executed automatically.

Note .

- If Auto Search under PEAK SEARCH is set to ON and Auto Analysis is set to ON, Auto Search will automatically be set to OFF.
- You can also set the parameter by tapping the ANA shortcut key at the bottom of the screen. When set to on, the shortcut key is highlighted.

Saving the Analysis Results

- **3.** Continuing from step 2, Tap **More** to display the More 2/2 function menu.
- 4. Tap Result Save. A file list appears.
- **5.** For the remaining procedure, see section 6.5, "Saving and Loading Analysis Results Data."

Explanation

Algorithms

Algorithms for Spectral Width Analysis


Algorithm	Description
THRESH	Determines spectral width from the width between points where the waveform crosses the threshold value.
ENVELOPE	Determines spectral width from waveform envelope.
RMS	Determines spectral width from waveform standard deviation.
PEAK RMS	Determines spectral width from waveform mode peak standard deviation.

Note _

- For details on the spectral width analysis algorithms and parameters, see appendix 2, "Data Calculation Algorithms for Spectral Widths."
- For information on NOTCH, see section 5.2, "Notch Width Measurement."

Result Display

Analysis results are displayed in the data area.



Spec Width Thresh

You can set threshold values for each spectral width analysis algorithm. After the value is set, analysis is executed and the display is updated.

The setting range is 0.01 to 50.00 dB. You can set it in steps of 0.01. When entering with the arrow keys when COARSE is selected, the value changes in steps of 1.00.

Each analysis algorithm has its own threshold value.

When Spec Width is set to OFF, this key is disabled.


The value set with this key is shared with the value set on the analysis parameter setting screen that appears when Parameter Setting is tapped.

5.2 Notch Width Measurement

Procedure

Notch width measurement measures the notch width (passband/notch width) from the measured waveform of a filter with U-shaped or V-shaped wavelength characteristics.


- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap ANALYSIS. A function menu appears for analyzing measured waveforms.
- 3. Tap Spec Width. A menu appears for selecting the analysis algorithm.
- **4.** Tap **NOTCH**. Analysis is performed, and the results are displayed in the data area.



Notch width measurement waveform (BOTTOM)

Notch width measurement waveform (PEAK)

									/	/ Da	ita a	rea		
	AWA +	TH ANALY	SIS: NOTCH	1>					_/-		A	018 Jan 1	/DSPI	≡ Menu
TH		K: 1.00)	 λC			743ni 721ni		/		S	:FIX :FIX :FIX :FIX	/BLK /BLK /BLK /BLK	Spec Width NOTCH
		PE: PEAK									F	:FIX :FIX	/BLK /BLK	Analysis 1
ST/	RT: 1529.	900 nm	STOP: 1		nm	c		···· <u>⊢</u>	530.400 n		N: 1.	0nm		DFB-LD
-41.6		1_nm	SENS: M	ID	-		AV	G:	1	SMF	NL: 50	01(A)	1 _	Analysis 2 WDM
													Ī	Analysis Execute
-42.6 d8m	REF							-				-	-	NOTCH
				\sim		edre		4			+		-	Spec Width Thresh 0.50dB
-43.6					<u>}</u>	- <u>+</u>	/						-	Parameter Setting
					H.						+			Switch
-44.6						d7								Display TRACE&TABLE
0.5 dB/D						¥							-	Auto Analysis
-45.6													-	OFF ON
													-	
-46.6													1	Analysis
1529	9.900 nm	LVL SH	F SHF MSH	SRC SF ZOM 1-	RC VA 2 W	C AL	0.400 II AU S AN		UT AUT AU SCL RE	0.10 n	<u> </u>	1530 RPT SG	.900 nm L STP	More 1/2




When changing the analysis parameters

- **5.** Continuing from step 4, tap **Parameter Setting**. A notch analysis parameter setting screen appears.
- 6. Tap within the frame of values, and set them.

If a parameter input window appears, enter the value in the window.

For check boxes, you can also use the arrow keys on the function menu to move the cursor and tap **Select**.

- Tap X to close the notch analysis parameter setting screen. You can also tap Close Window on the function menu. The function menu returns to the previous level.
- **8.** Tap **Analysis Execute**. Analysis is performed according to the changed parameters, and the results are displayed in the data area.



Note

You can also perform the currently set analyze by tapping Analysis Execute on the popup list. To display the pop-up list, tap or right-click the waveform display area showing the waveform. For details, see section 3.2, "Menu Operations" in IM AQ6360-02EN.




• For details on the notch width analysis algorithms and parameters, see appendix 2, "Data Calculation Algorithms for Spectral Widths."

5.3 SMSR Measurement

Procedure

SMSR can be measured from the measured waveform of a DFB-LD.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap ANALYSIS. A function menu appears for analyzing measured waveforms.
- 3. Tap Analysis 1. A menu appears for selecting the analysis function.
- 4. Tap SMSR. Analysis is performed, and the results are displayed in the data area.




When changing the analysis parameters

- Continuing from step 3, tap Parameter Setting. An SMSR measurement parameter setting screen appears.
- 6. Tap within the frame of values, and set them.

If a parameter input window appears, enter the value in the window.

For check boxes, you can also use the arrow keys on the function menu to move the cursor and tap **Select**.

- Tap X to close the SMSR measurement setting screen. You can also tap Close Window on the function menu. The function menu returns to the previous level.
- **8.** Tap **Analysis Execute**. Analysis is performed according to the changed parameters, and the results are displayed in the data area.



Note _

You can also perform the currently set analyze by tapping Analysis Execute on the pop-up list. To display the pop-up list, tap or right-click the waveform display area showing the waveform. For details, see section 3.2, "Menu Operations" in IM AQ6360-02EN.




Explanation

SMSR

SMSR stands for side-mode suppression ratio.

SMSR represents the difference between the mode peak and the side-mode level. It is one of the parameters used to evaluate the performance of DFB-LDs and the like.



Note.

For details on SMSR analysis algorithms, see appendix 3, "Details of Each Analysis Function."

Result Display

Analysis results are displayed in the data area.

<u>SMSR ANALYSIS></u> SMSR MODE: MODE	1 <u>SM</u> S	R MASK: ±0.00nm
ΔPK: 1549.3	- (0110	8.15dBm
Δ2nd PK: 1550.2	\ \ \	35.38dBm
ΔPK-Δ2nd PK: 0.9	600nm	43.52dB
Analysis results		Analysis parameter values

ablaPK: Mode peak wavelength, level value

 $\bigtriangledown \! \bigtriangledown \! 2 nd$ PK: Side mode wavelength, level value

MODE 1: Set the 2nd peak excluding the MASK AREA as the side mode.


SMSR MASK: Mask setting range

5.4 Power Measurement

Procedure


Optical power can be measured by integrating the measured waveform levels.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap ANALYSIS. A function menu appears for analyzing measured waveforms.
- 3. Tap Analysis 1. A menu appears for selecting the analysis function.
- **4.** Tap **POWER**. Analysis is performed, and the results are displayed in the data area.



When changing the analysis parameters

- **5.** Continuing from step 4, tap **Parameter Setting**. A power offset setting screen appears.
- 6. Tap the frame of the value, and enter the value in the parameter input window.
- 7. Tap X to close the power offset setting screen. You can also tap Close Window on the function menu. The function menu returns to the previous level.
- **8.** Tap **Analysis Execute**. Analysis is performed according to the changed parameters, and the results are displayed in the data area.





You can also perform the currently set analyze by tapping Analysis Execute on the popup list. To display the pop-up list, tap or right-click the waveform display area showing the waveform. For details, see section 3.2, "Menu Operations" in IM AQ6360-02EN.



 For details on power analysis algorithms, see appendix 3, "Details of Each Analysis Function."


5.5 DFB-LD, FP-LD, and LED Measurement

Procedure

Light source parameters can be analyzed from the measured waveform of each light source (DFB-LD, FP-LD, LED).

For instructions on how to acquire measured waveforms, see "Loading a Waveform for PMD Measurement" on page 5-14.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap ANALYSIS. A function menu appears for analyzing measured waveforms.
- 3. Tap Analysis 1. A menu appears for selecting the analysis function.
- **4.** Tap **DFB-LD**, **FP-LD**, **or LED** according to the type of light source to be analyzed. Analysis is performed, and the results are displayed in the data area.



Example of a measured waveform of an FP-LD

To end the DFB-LD analysis

5. Tap the waveform display area to display a pop-up list, and tap **Analysis Exit**. This procedure is not necessary for FP-LD or LED.

The analysis also ends when you select another function on the Main Menu window or tap a value in the measurement condition area or the like.

Note _

On the DFB-LD analysis result display, when you tap the waveform display area, you can select the following functions from the pop-up list.



- · Analysis Exit: Finish the analysis.
- · Parameter Setting: Display a parameter setting screen.
- · Scale: Display a operation tool window for waveform zooming.

When changing the analysis parameters

- **6.** Continuing from step 4, tap **Parameter Setting**. An measurement parameter setting screen appears for the selected type of light source.
- 7. Tap within the frame of values, and set them.

If a parameter input window appears, enter the value in the window.

For check boxes, you can also use the arrow keys on the function menu to move the cursor and tap **Select**.

- Tap X to close the measurement parameter setting screen. You can also tap Close Window on the function menu. The function menu returns to the previous level.
- **9.** Tap **Analysis Execute**. Analysis is performed according to the changed parameters, and the results are displayed in the data area.

Note _

• You can also perform the currently set analyze by tapping Analysis Execute on the popup list. To display the pop-up list, tap or right-click the waveform display area showing the waveform. For details, see section 3.2, "Menu Operations" in IM AQ6360-02EN.



• For details on the analysis algorithms for the DFB-LD, FP-LD, and LED light sources and related parameters, see appendix 3, "Details of Each Analysis Function."


5.6 PMD Measurement

Procedure

The polarization mode dispersion (PMD) can be determined from a measured waveform by using the instrument in combination with a wideband light source and polarizer, a polarization controller, and an analyzer.

For instructions on how to acquire measured waveforms, see "Loading a Waveform for PMD Measurement" on page 5-14.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap ANALYSIS. A function menu appears for analyzing measured waveforms.
- 3. Tap Analysis 1. A menu appears for selecting the analysis function.
- 4. Tap PMD. Analysis is performed, and the results are displayed in the data area.



When changing the analysis parameters

- Continuing from step 4, tap Parameter Setting. A threshold level setting screen appears.
- 6. Tap the frame of the value, and enter the value in the parameter input window.
- Tap X to close the threshold level setting screen. You can also tap Close
 Window on the function menu. The function menu returns to the previous level.
- **8.** Tap **Analysis Execute**. Analysis is performed according to the changed parameters, and the results are displayed in the data area.

Note ____

You can also perform the currently set analyze by tapping Analysis Execute on the popup list. To display the pop-up list, tap or right-click the waveform display area showing the waveform. For details, see section 3.2, "Menu Operations" in IM AQ6360-02EN.




- When PMD measurement is performed, waveform data at or below the threshold level from the peak is not used in analysis. The threshold level is set on the threshold level setting screen.
- The mode judgment threshold level used during PMD analysis execution is set with Mode Diff under PEAK SEARCH. On the waveform, a level difference exceeding the value set with Mode Diff is recognized as a mode.
- For a description of how to set the mode judgment threshold level, see section 4.13, "Single Search."
- For details on the PMD analysis algorithm and parameters, see appendix 3, "Details of Each Analysis Function."

Loading a Waveform for PMD Measurement

PMD measurement is performed after loading of the waveform used for PMD measurement.

The configuration for PMD measurement and the waveform acquisition procedure are explained below.



- **1.** Set the measurement conditions so that the entire wavelength range of the wideband light source can be measured. Set the resolution to about 0.2 nm.
- 2. Tap **Menu**. The Main Menu window appears.
- 3. Tap SWEEP. A function menu appears for sweeping.
- 4. Tap Repeat. Repeat sweeping will begin.
- **5.** While watching the waveform during repeat sweeping, adjust the polarization controller so as to maximize the waveform's peak/bottom difference (the level difference between the maximum and minimum values).
- **6.** Tap **Single** to perform a single sweep. Acquisition of measurement waveforms is complete.

5.7 WDM Transmission Signal Analysis

Procedure

The center wavelength, level, and SNR of each channel can be measured from the measured waveform of a WDM transmission signal.


- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap ANALYSIS. A function menu appears for analyzing measured waveforms.
- 3. Tap Analysis 2. A menu appears for selecting the analysis function.
- Tap WDM. Analysis is performed, and the results are displayed on the screen.
 Tapping Switch Display switches the analysis results display screen.
 Trace & Table: A waveform and table are displayed.

Trace: Only the waveform is displayed.

Table: Only the table is displayed.

To end the analysis, tap X in the upper right of the table, or tap the waveform display area to display a pop-up list, and tap Analysis Exit.

The analysis also ends when you select another function on the Main Menu window or tap a value in the measurement condition area or the like.



Note.

• If you select Trace & Table or Trace using Switch Display, when you tap the waveform display area, you can select the following functions from the pop-up list.




- · Analysis Exit: Finish the analysis.
- · Parameter Setting: Display a parameter setting screen.
- · Scale: Display a operation tool window for waveform zooming.
- If you select Trace & Table using Switch Display and you tap the analysis results list while the waveform is zoomed, the waveform of the tapped channel appears in the center of the waveform screen.

When changing the analysis parameters


- Continuing from step 4, tap Parameter Setting. A WDM analysis parameter setting screen appears. If a setting screen has multiple pages, tapping Next Page shows the next screen.
- 7. Tap within the frame of values, and set them.

If a parameter input window appears, enter the value in the window.

For check boxes, you can also use the arrow keys on the function menu to move the cursor and tap **Select**.



- Tap X to close the WDM parameter setting screen. You can also tap Close
 Window on the function menu. The function menu returns to the previous level.
- **9.** Tap **Analysis Execute**. Analysis is performed according to the changed parameters, and the results are displayed on the screen.



Note _


 You can also perform the currently set analyze by tapping Analysis Execute on the popup list. To display the pop-up list, tap or right-click the waveform display area showing the waveform. For details, see section 3.2, "Menu Operations" in IM AQ6360-02EN.



 For details on the WDM analysis algorithm and parameters, see appendix 4, "WDM Analysis Function."

Explanation

The following configuration is used to measure WDM transmission signals.



WDM signal light is measured, and the waveform is drawn in the active trace.

Setting Analysis Parameters

WDM analysis parameters are broadly divided into the following three categories. Change the parameter settings according to the analysis being performed.

- Channel detection parameters (CHANNEL DETECTION SETTING)
- Noise level measurement parameters (INTERPOLATION SETTING)
- Analysis result display parameters (DISPLAY SETTING) These are explained below.

For details on parameters, see appendix 4, "WDM Analysis Function."

Channel Detection Parameters

These parameters are used to set the threshold level and the like for WDM channel detection.

THRESH LEVEL

This parameter sets the threshold level for channel detection. This setting determines how far down in decibels from the peak level to detect a mode peak as a channel.

MODE DIFF

This parameter sets the minimum value for the peak/bottom difference during channel peak detection.


If the waveform peak/bottom difference equals or exceeds this value, it is detected as a mode peak.

DISPLAY MASK

This parameter sets the mask level value for channel masking. Channels at a level equal to or below this setting are masked.

Examples of Channel Detection Parameter Settings

THRESH LEVEL = 10.0 dB MODE DIFF = 15.0 dB



Wavelength

- In the above example, only (A) and (C) are detected as channels.
 - Because the peak powers of (A) and (C) are within the THRESH LEVEL range and the peak/bottom difference is greater than the MODE DIFF value, they are detected as channels.
 - (B) and (E) are not detected because their peak powers are outside the THRESH LEVEL range.
 - The peak power of (D) is within the THRESH LEVEL range but because the peak/bottom difference is less than the MODE DIFF value, it is not detected as a channel.
- If you want to mask a channel, set DISPLAY MASK. For example, setting DISPLAY MASK to -20.0 dBm masks (B) and (E) because their levels are less than this value.

Noise Level Measurement Parameters

These parameters are used to set the interpolation method and bandwidth for noise level measurement.

NOISE ALGO

Select one of the five algorithms shown below for measuring the noise level. If AUTO-FIX or AUTO-CTR is set, the measurement parameters at another noise level are set automatically. To set the values manually, select MANUAL-FIX or MANUAL-CTR.

- AUTO-FIX Automatic settings (FIX type)
- MANUAL-FIX Manual settings (FIX type)
- AUTO-CTR Automatic settings (CENTER type)
- MANUAL-CTR Manual settings (CENTER type)
- PIT Automatic settings (PIT type)

Note.

- If AUTO-FIX, AUTO-CTR, or PIT is selected, the NOISE AREA and MASK AREA parameters are set automatically according to the measured waveform. FITTING ALGO is set to LINEAR.
- For details on the WDM analysis algorithm and parameters, see appendix 4, "WDM Analysis Function."

NOISE AREA

This parameter is used to set the range of waveform data to be used in determining the noise level through interpolation.

This parameter is only set when NOISE ALGO is set to MANUAL-FIX.

MASK AREA

This parameter is used to set the range of signal light to be masked when determining the noise level through interpolation.

This parameter is only set when FITTING ALGO is not set to LINEAR.

FITTING ALGO

This parameter is used to select the interpolation algorithm for determining the noise level.

This parameter is only set when NOISE ALGO is set to MANUAL-FIX or MANUAL-CTR.

Interpolation Algorithms

Fitting Algorithm	Description
LINER	Linear interpolation
GAUSS	Normal distribution curve
LORENZ	Lorenz curve
3RD POLY	3rd order polynomial
4TH POLY	4th order polynomial
5TH POLY	5th order polynomial

Note .

If NOISE ALGO is AUTO-FIX or AUTO-CTR, then FITTING ALGO is automatically set to LINEAR and does not need to be set manually.

NOISE BW

This parameter is used to set the noise bandwidth.

DUAL TRACE

This parameter is used to turn the dual trace function on or off. When the dual trace function is used, the signal level and noise level during SNR measurement can each be determined from different traces.

Analysis Results Display Parameters

These parameters are used to set the format for displaying the analysis results on the screen.


DISPLAY TYPE

This parameter is used to select the analysis results display format.

DISPLAY TYPE	Description and Procedure			
ABSOLUTE	1. Set CH RELATION to OFFSET or SPACING.			
(absolute value	OFFSET: Displays a value relative to the reference channel.			
display)	SPACING: Displays the wavelength difference and level			
	difference from the adjacent channel.			
	2. If you select OFFSET, select the reference channel with REF CH.			
	When using the channel with the highest level as the reference			
	Select HIGHEST.			
	 When using a specific channel as the reference 			
	Set the reference channel number in "***CH".			
RELATIVE	There are no settings for this display type.			
(values relative to	(If you want to change the grid table, see appendix 1, "Grid Table for			
the grid)	WDM Wavelength.")			
DRIFT(MEAS)	The procedure varies depending on the reference.			
(drift display relative	To use the waveform data of the current active trace waveform			
to a past measured	as the reference			
wavelength)	Tap MAX/MIN RESET.			
	 To use the first measured waveform after changing the 			
	measurement conditions as the reference			
	Because the first measured waveform data is used as the			
	reference, there are no settings that need to be specified with			
	parameters.			
DRIFT(GRID)	The procedure varies depending on the reference.			
(drift display relative	To use the waveform data of the current active trace waveform			
to grid wavelength)	as the reference			
	Tap MAX/MIN RESET.			
	 To use the first measured waveform after changing the 			
	measurement conditions as the reference			
	Because the first measured waveform data is used as the			
	reference, there are no settings that need to be specified with			
	parameters.			
	(If you want to change the grid wavelength, see appendix 1,			
	"Grid Table for WDM Wavelength.")			


OUTPUT SLOPE

Displays the least square approximation line passing through the detected channel peak. The channel slope can be obtained as a numerical value.



POINT DISPLAY

This parameter is used to display the range of data used in interpolation for determining the noise level.



Other Parameters

SIGNAL POWER

This parameter sets the signal power calculation method.

INTEGRAL RANGE

This parameter sets the integral range for determining signal power.

5.8 Optical Amp Gain and NF Measurement

Procedure

Measurement can be performed of the optical amp gain and noise figure (NF) from the measured waveform of the signal light going into the optical amp, and the measured waveform of the output light leaving the optical amp.

For instructions on how to acquire measured waveforms, see "Acquiring the Waveform to Be Analyzed" on page 5-25.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap ANALYSIS. A function menu appears for analyzing measured waveforms.
- 3. Tap Analysis 2. A menu appears for selecting the analysis function.
- Tap EDFA-NF. Analysis is performed, and the results are displayed on the screen.
 Tapping Switch Display switches the analysis results display screen.

TRACE & TABLE: A waveform and table are displayed.

TRACE: Only the waveform is displayed.


TABLE: Only the table is displayed.

GRAPH & TABLE: A graph and table are displayed.

GRAPH: Only the graph is displayed.

5. To end the analysis, tap **X** in the upper right of the table or graph, or tap the waveform display area to display a pop-up list, and tap **Analysis Exit**.

The analysis also ends when you select another function on the Main Menu window or tap a value in the measurement condition area or the like.



Note _


• If you select Trace & Table or Trace using Switch Display, when you tap the waveform display area, you can select the following functions from the pop-up list.



- · Analysis Exit: Finish the analysis.
- Parameter Setting: Display a parameter setting screen.
- Scale: Display a operation tool window for waveform zooming.
- If you select Trace & Table using Switch Display and you tap the analysis results list while the waveform is zoomed, the waveform of the tapped channel appears in the center of the waveform screen.

Displaying the Gain (Gain) and Noise Factor (NF) Graphs

- **6.** For Switch Display, tap **Graph & Table** or **Graph**. A function menu appears for setting the graph display and markers.
- **7.** Tap Line Marker Y1. Marker Y1 appears on the graph, and a parameter input window appears.
- 8. Enter the value in the parameter input window.
- 9. Tap µm/ENT or nm/ENT.
- **10.** Tap Line Marker Y2. Marker Y2 appears on the graph, and a parameter input window appears.
- 11. Enter the value in the parameter input window.
- 12. Tap µm/ENT or nm/ENT.



Note

If both markers Y1 and Y2 are turned on, the difference between the markers are displayed in the marker information.


When changing the analysis parameters

- **6.** Continuing from step 4, tap **Parameter Setting**. A EDFA-NF analysis parameter setting screen appears.
- 7. Tap within the frame of values, and set them.

If a parameter input window appears, enter the value in the window.

For check boxes, you can also use the arrow keys on the function menu to move the cursor and tap **Select**.

- Tap X to close the EDFA-NF analysis parameter setting screen. You can also tap Close Window on the function menu. The function menu returns to the previous level.
- **9.** Tap **Analysis Execute**. Analysis is performed according to the changed parameters, and the results are displayed on the screen.



/ Analysis parameter setting screen

Note.

You can also perform the currently set analyze by tapping Analysis Execute on the popup list. To display the pop-up list, tap or right-click the waveform display area showing the waveform. For details, see section 3.2, "Menu Operations" in IM AQ6360-02EN.




• For details on the optical amp analysis algorithm and parameters, see appendix 5, "Optical Amp Analysis Function."

Acquiring the Waveform to Be Analyzed


Analysis of optical amp gain and NF is performed after measuring the signal light going into the optical amp and the output light leaving the optical amp.

The following configuration and general procedure is used to measure optical amp gain and NF.

Signal light measurement configuration



Output light measurement configuration



Writing to Trace A the Waveform of the Signal Light Input to the Optical Amp

- **1.** Input the signal light sent to the optical amp into the instrument.
- 2. Tap **Menu**. The Main Menu window appears.
- 3. Tap TRACE. A function menu appears for traces.
- 4. Tap Active Trace to select A.
- 5. Tap View A to select DISP.
- 6. Tap Write A. Trace A is set to write mode.
- Measure the signal light waveform according to measurement conditions for the signal light waveform.

(For details on the measuring procedure, see chapter 3, "Measurement.")

8. Tap Fix A under TRACE. Trace A is set to fix mode.

Note .

If all traces from trace A to trace G have been set to fix mode (FIX) as a result of step 8, a warning is displayed. However, this does not pose a problem because trace B is set to write mode in the next step.

Writing to Trace B the Waveform of the Output Light from the Optical Amp

- 9. Input the light output from the optical amp into the instrument.
- 10. Display the Main Menu window, and tap TRACE.
- 11. Tap Active Trace on the function menu to select B.
- 12. Tap View B to select DISP.
- 13. Tap Write B. Trace B is set to write mode.
- **14.** Measure the waveform of the output light with the same measurement conditions used for measuring the signal light waveform.

YOKOGAWA 🔶 **≡** Menu Δ-Δn: Δ Δ0001 Δ0002 Δ0003 Δ0004 Δ0005 Auto /DSP /BLK /BLK /BLK /BLK /BLK 4eas. Conditions> START: 1546.291 r SPEED: SPAN: 1x 10.0 nm 1001(M) STOP: 1556.291 nm CENTER: 1551.291 nm RES: -10.0 dBm -30 weep arker L1-L2 <u>OFF</u> Of -50. 10.0 dB/D Sweep Interval -70. ₩ 鞩 -90.0 1546. LVL WL NOI SEC SEC VAC AUT AUT AUT AUT AUT AUT SWR SMG RPT SGL STP

Examples of signal and output light waveforms

5.8 Optical Amp Gain and NF Measurement

Setting EDFA-NF Analysis Parameters

EDFA-NF analysis parameters are broadly divided into the following two categories. Change the parameter settings according to the analysis being performed.

- Channel detection parameters (CHANNEL DETECTION SETTING)
- ASE level measurement parameters (INTERPOLATION SETTING)
- These are explained below.

For details on parameters, see appendix 3, "Details of Each Analysis Function."

Channel Detection Parameters

These parameters are used to set the threshold level and the like for WDM channel detection.

THRESH LEVEL

This parameter sets the threshold level for channel detection. This setting determines how far down in decibels from the peak level to detect a mode peak as a channel.

MODE DIFF

This parameter sets the minimum value for the peak/bottom difference during channel peak detection.

If the waveform peak/bottom difference equals or exceeds this value, it is detected as a mode peak.

Note.

For details on setting parameters for channel detection, see "Channel Detection Parameters" in section 5.7, "WDM Transmission Signal Analysis."

ASE Level Measurement Parameters

These parameters are used to set the waveform level, offset, and interpolation method for ASE level measurement.

OFFSET(IN)

A level offset can be set on a signal light waveform (trace A). Specify "0.00" if a level offset is not needed.

OFFSET(OUT)

A level offset can be set on an output light waveform (trace B). Specify "0.00" if a level offset is not needed.

ASE ALGO

Select one of the five algorithms shown below for measuring the ASE level. If AUTO-FIX or AUTO-CTR is set, the measurement parameters at another ASE level are set automatically. To set the values manually, select MANUAL-FIX or MANUAL-CTR.

- AUTO-FIX Automatic settings (FIX type)
- MANUAL-FIX Manual settings (FIX type)
- AUTO-CTR Automatic settings (CENTER type)
- MANUAL-CTR Manual settings (CENTER type)

Note .

- If AUTO-FIX or AUTO-CTR is selected, the FITTING AREA and MASK AREA parameters are set automatically according to the measured waveform. FITTING ALGO is set to LINEAR.
- For details on parameters, see appendix 5, "Optical Amp Analysis Function."

FITTING AREA

This parameter is used to set the range of waveform data to be used in determining the ASE level through interpolation.

This parameter is only set when ASE ALGO is set to MANUAL-FIX.

MASK AREA

This parameter is used to set the range of signal light to be masked when determining the ASE level through interpolation.

This parameter is only set when FITTING ALGO is not set to LINEAR.

FITTING ALGO

This parameter is used to select the interpolation algorithm for determining the ASE level. This parameter is only set when ASE ALGO is set to MANUAL-FIX or MANUAL-CTR.

Interpolation Algorithms


Fitting Algorithm	Description
LINER	Linear interpolation
GAUSS	Normal distribution curve
LORENZ	Lorenz curve
3RD POLY	3rd order polynomial
4TH POLY	4th order polynomial
5TH POLY	5th order polynomial

Note -

If ASE ALGO is AUTO-FIX or AUTO-CTR, then FITTING ALGO is automatically set to LINEAR and does not need to be set manually.

POINT DISPLAY

This parameter is used to display the range of data used in interpolation for determining the ASE level.



NF Calculation Parameters

RES BW

This parameter sets the method for calculating the measurement resolution RBi of each channel used in computing the NF value.

The default is MEASURED.

If the measuring resolution varies greatly from channel to channel, or in other such cases, select CAL DATA.

MEASURED:

The value of the THRESH 3dB width for each channel is determined from the TRACE B waveform and assigned to RBi.

CAL DATA:

determined from the TRACE B waveform and assigned to RBi. The actual resolution value stored in the instrument is assigned to RBi.

SHOT NOISE

This parameter sets whether the Shot Noise component is included in computation of the NF value.

The default is ON.

- ON: Shot Noise component is included in computation of the NF value.
- OFF: Shot Noise component is not included in computation of the NF value.

5.9 Optical Filter Characteristics Measurement

Procedure

Optical filter characteristics can be measured from the measured waveform of the light input to the optical filter from the light source, as well as from the measured waveform light output from the optical filter.


For instructions on how to acquire measured waveforms, see "Acquiring the Waveform to Be Analyzed" on page 5-36.

Filter Measurement (Single Channel)

You can analyze a waveform whose number of modes is 1.

Filter Peak Analysis

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap ANALYSIS. A function menu appears for analyzing measured waveforms.
- 3. Tap Analysis 2. A menu appears for selecting the analysis function.
- **4.** Tap **FILTER-PK**. Analysis is performed, and the results are displayed in the data area.



When changing the analysis parameters


- Continuing from step 4, tap Parameter Setting. A FILTER-PK analysis parameter setting screen appears. If a setting screen has multiple pages, tapping Next Page shows the next screen.
- 6. Tap within the frame of values, and set them.

If a parameter input window appears, enter the value in the window.

For check boxes, you can also use the arrow keys on the function menu to move the cursor and tap **Select**.

- **7.** Tap **X** to close the FILTER-PK parameter setting screen. You can also tap **Close Window** on the function menu. The function menu returns to the previous level.
- **8.** Tap **Analysis Execute**. Analysis is performed according to the changed parameters, and the results are displayed in the data area.

5.9 Optical Filter Characteristics Measurement



Note _

You can also perform the currently set analyze by tapping Analysis Execute on the popup list. To display the pop-up list, tap or right-click the waveform display area showing the waveform. For details, see section 3.2, "Menu Operations" in IM AQ6360-02EN.



• For details on the optical filter analysis algorithm and parameters, see appendix 6, "Optical Filter Analysis Function."

Filter Bottom Analysis

This is used if the optical filter is of a notch type rather than a pass band type.

- 1. Tap **= Menu**. The Main Menu window appears.
- 2. Tap ANALYSIS. A function menu appears for analyzing measured waveforms.
- 3. Tap Analysis 2. A menu appears for selecting the analysis function.
- **4.** Tap **FILTER-BTM**. Analysis is performed, and the results are displayed in the data area.

When changing the analysis parameters

- Continuing from step 4, tap Parameter Setting. A FILTER-BTM analysis parameter setting screen appears. If a setting screen has multiple pages, tapping Next Page shows the next screen.
- 6. Tap within the frame of values, and set them.

If a parameter input window appears, enter the value in the window.

For check boxes, you can also use the arrow keys on the function menu to move the cursor and tap **Select**.

- Tap X to close the FILTER-BTM parameter setting screen. You can also tap Close Window on the function menu. The function menu returns to the previous level.
- **8.** Tap **Analysis Execute**. Analysis is performed according to the changed parameters, and the results are displayed in the data area.

Note.

• You can also perform the currently set analyze by tapping Analysis Execute on the popup list. To display the pop-up list, tap or right-click the waveform display area showing the waveform. For details, see section 3.2, "Menu Operations" in IM AQ6360-02EN.



• For details on the optical filter analysis algorithm and parameters, see appendix 6, "Optical Filter Analysis Function."

Filter Measurement for WDM (Multi Channel)

You can analyze multi-mode waveforms.

WDM Filter Peak Analysis

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap ANALYSIS. A function menu appears for analyzing measured waveforms.
- 3. Tap Analysis 2. A menu appears for selecting the analysis function.
- Tap WDM FIL-PK. Analysis is performed, and the results are displayed on the screen. Tapping Switch Display switches the analysis results display screen.


TRACE & TABLE: A waveform and table are displayed.

TRACE: Only the waveform is displayed.

TABLE: Only the table is displayed.

To end the analysis, tap X in the upper right of the table, or tap the waveform display area to display a pop-up list, and tap Analysis Exit.

The analysis also ends when you select another function on the Main Menu window or tap a value in the measurement condition area or the like.



Note

If you select Trace & Table or Trace using Switch Display, when you tap the waveform display area, you can select the following functions from the pop-up list.



- · Analysis Exit: Finish the analysis.
- Parameter Setting: Display a parameter setting screen.
- Scale: Display a operation tool window for waveform zooming.
- If you select Trace & Table using Switch Display and you tap the analysis results list while the waveform is zoomed, the waveform of the tapped channel appears in the center of the waveform screen.


When changing the analysis parameters

- Continuing from step 4, tap Parameter Setting. A WDM FIL-PK analysis parameter setting screen appears. If a setting screen has multiple pages, tapping Next Page shows the next screen.
- 7. Tap within the frame of values, and set them.

If a parameter input window appears, enter the value in the window.

For check boxes, you can also use the arrow keys on the function menu to move the cursor and tap **Select**.

- Tap X to close the WDM FIL-PK parameter setting screen. You can also tap Close Window on the function menu. The function menu returns to the previous level.
- **9.** Tap **Analysis Execute**. Analysis is performed according to the changed parameters, and the results are displayed on the screen.



Note

You can also perform the currently set analyze by tapping Analysis Execute on the popup list. To display the pop-up list, tap or right-click the waveform display area showing the waveform. For details, see section 3.2, "Menu Operations" in IM AQ6360-02EN.



• For details on the optical filter analysis algorithm and parameters, see appendix 6, "Optical Filter Analysis Function."

WDM Filter Bottom Analysis

This is used if the optical filter is of a notch type rather than a pass band type.

- 1. Tap **= Menu**. The Main Menu window appears.
- 2. Tap ANALYSIS. A function menu appears for analyzing measured waveforms.
- 3. Tap Analysis 2. A menu appears for selecting the analysis function.
- Tap WDM FIL-BTM. Analysis is performed, and the results are displayed on the screen. Tapping Switch Display switches the analysis results display screen. TRACE & TABLE: A waveform and table are displayed.
 TRACE: Only the waveform is displayed.
 TABLE: Only the table is displayed.
- To end the analysis, tap X in the upper right of the table, or tap the waveform display area to display a pop-up list, and tap Analysis Exit.

The analysis also ends when you select another function on the Main Menu window or tap a value in the measurement condition area or the like.

Note.

• If you select Trace & Table or Trace using Switch Display, when you tap the waveform display area, you can select the following functions from the pop-up list.

Parameter Setting

Scale

- · Analysis Exit: Finish the analysis.
- Parameter Setting: Display a parameter setting screen.
- · Scale: Display a operation tool window for waveform zooming.
- If you select Trace & Table using Switch Display and you tap the analysis results list while the waveform is zoomed, the waveform of the tapped channel appears in the center of the waveform screen.

When changing the analysis parameters

- Continuing from step 4, tap Parameter Setting. A WDM FIL-BTM analysis parameter setting screen appears. If a setting screen has multiple pages, tapping Next Page shows the next screen.
- 7. Tap within the frame of values, and set them.

If a parameter input window appears, enter the value in the window.

For check boxes, you can also use the arrow keys on the function menu to move the cursor and tap **Select**.

- Tap X to close the WDM FIL-BTM parameter setting screen. You can also tap Close Window on the function menu. The function menu returns to the previous level.
- **9.** Tap **Analysis Execute**. Analysis is performed according to the changed parameters, and the results are displayed on the screen.

Note_

You can also perform the currently set analyze by tapping Analysis Execute on the popup list. To display the pop-up list, tap or right-click the waveform display area showing the waveform. For details, see section 3.2, "Menu Operations" in IM AQ6360-02EN.




• For details on the optical filter analysis algorithm and parameters, see appendix 6, "Optical Filter Analysis Function."

Acquiring the Waveform to Be Analyzed


First measure the waveform of the wideband light source as a reference waveform, then subtract the optical filter's output waveform from the reference waveform to measure the characteristics of the optical filter.

The following configuration and general procedure is used to measure optical filter characteristics.

A pass band type optical filter is used as an example.



Spectrum measurement after passing through the filter



Writing to Trace A the Waveform of the Light Source Input to the Optical Filter

- **1.** Input the emitted light from the light source that is input to the optical filter into the instrument.
- 2. Tap **Menu**. The Main Menu window appears.
- 3. Tap TRACE. A function menu appears for traces.
- 4. Tap Active Trace to select A.
- 5. Tap View A to select DISP.
- 6. Tap Write A. Trace A is set to write mode.
- 7. Measure the light source waveform according to measurement conditions for the light source waveform.

(For details on the measuring procedure, see chapter 3, "Measurement.")

8. Tap Fix A under TRACE. Trace A is set to fix mode.

Note -

If all traces from trace A to trace G have been set to fix mode (FIX) as a result of step 8, a warning is displayed. However, this does not pose a problem because trace B is set to write mode in the next step.

Writing to Trace B the Waveform of the Output Light from the Optical Filter

- **9.** Input the emitted light from the light source to the optical filter, then input the light that is output from the optical filter into the instrument.
- 10. Display the Main Menu window, and tap TRACE.
- 11. Tap Active Trace on the function menu to select B.
- 12. Tap View B to select DISP.
- 13. Tap Write B. Trace B is set to write mode.
- **14.** Measure the waveform of the output light with the same measurement conditions used for measuring the light source waveform.

Writing to Trace C the Difference between Traces

- 15. Display the Main Menu window, and tap TRACE.
- 16. Tap Active Trace on the function menu to select C.
- 17. Tap View C to select DISP.
- 18. Tap Calculate C.
- 19. Tap Log Math. A menu appears for selecting the equation.
- 20. Tap C=A-B(LOG). The waveform which is obtained by subtracting the trace B waveform from the trace A waveform is displayed in trace C.

Explanation

Setting WDM Filter Analysis Parameters

WDM FIL-PK analysis parameters are broadly divided into the following three categories. Change the parameter settings according to the analysis being performed.

- Channel detection parameters
- · Parameter settings for each analysis item
- These are explained below.

For details on parameters, see appendix 6, "Optical Filter Analysis Function."

Channel Detection Parameters

These parameters are used to set the algorithm and threshold level for WDM channel detection.

ALGO

Select one of the four algorithms shown below for detecting the WDM channel and analyzing the reference wavelength of each channel.


- PEAK
- MEAN
- GRID FIT
- GRID

The channel detection and reference wavelength analysis results for each channel vary depending on the algorithm selected.

• When PEAK is selected

Each mode peak is detected as a channel.


The peak wavelength of each channel is the reference wavelength.



When MEAN is selected

Each mode peak is detected as a channel.

The 3 dB center wavelength of each channel is the reference wavelength.




• When GRID FIT is selected

The mode peak detected within grid wavelength \pm (test band/2) is set as the channel. The grid wavelength nearest to each channel is the reference wavelength.

YOKOGAWA 🔶						8 Feb 16 18:27	≡ M enu
TR A Δ0002:	1546.1230nm -28	0.36dBm			B:FI C:FI D:FI	X /BLK X /BLK	Spec Width
TR A Δ0004:	1549.3230nm -25	7.27dBm 5.90dBm 1.70dBm		-	E:FI F:FI G:FI	X /BLK	THRESH
< Meas, Condi	ions>	1111	1110	SPE			Analysis 1
START: 154		560.002mm	NTER: 1550.	~ ~ ~	AN: 20.0 r		DFB-LD
RES:				1			Analysis 2
-0.7			-10.			<u> </u>	
····•	····		* *	in in		···+···	WDM FIL-P
-20.7 REF		X X X	A A	ž.	Å		Analysis
-40.7		1	. <u>()</u>				Execute
		₿@ł@ł.÷					WDM FIL-P
-60.7		아누~~~ 수많을~~~ 수입수 수	생산물		4+		Spec Width
		반서~~~서 많습~~~서 많네 순	ゴニーゴー	1-	ii ii ii		(Thresh
10.0 dB/D 001.44	MANYA/N S MY	- W - Y			nr-1,	- Sectores	L
-100.7				5			Parameter
1540.003 nr	n	1550	.003 nm	2.00 r	nm/D	1560.003 nm	Setting
<wdm filte<="" td=""><td>R(PEAK) ANALYSIS></td><td></td><td>[P</td><td>ASS BAND1 T</td><td>EST BAND:0.</td><td>20nm ×</td><td></td></wdm>	R(PEAK) ANALYSIS>		[P	ASS BAND1 T	EST BAND:0.	20nm ×	
	CTION] ALGO:GRID F		MODE DIFF:3		EST BAND:0.		Switch Display
[RIPPLE NO. NOM	TEST BAND:0.20nm	[CROSS TALK]	SPACING:0.8	Onm T 3.0dB PB	EST BAND:0. RIPPLE	20nm CROSS TK(L)	TRACE&TABL
	nm] PK LVL[dBm]	CTR WL[nm]	SB[nm]	5.000 PB [nm]	[dB]	[dB] (R)	
1 1544.	5258 1544.5430	0.1920	0.0000	0.2946	4.105	47.277	Auto Analysis
	-30.358	1544.5350				46.646	OFF O
2 1546.		0.1948	0.0000	0.2903	3.710	48.554	
	-28.845	1546.1310				48.332	
3 1547.		0.1957	0.0000	0.2827	3.240	50.373	
	-27.274	1547.7245				49.744	Analysis
4 1549.		0.1958	0.0000	0.2842	3.266	51.097	
t	-25.895	1549.3251				51.488	More 1/2
	LVL WL NO SHF SHF MS	I SRC SRC VAC AU ZOM 1-2 WL OFS	AUT AUT A ANA SRC S	UT AUT AUT CL REF CTR	SWP SMO 1-2 OTH	RPT SGL STP	

• When GRID is selected

The wavelengths registered in the grid table wavelength are recognized as channels. Grid wavelength is set as the reference wavelength.



Grid wavelengths are detected as channels.

THRESH LEVEL

This parameter sets the threshold level for channel detection.

MODE DIFF

This parameter sets the minimum value for the peak/bottom difference during channel peak detection.

Note

For details on setting parameters for channel detection, see "Channel Detection Parameters" in section 5.7, "WDM Transmission Signal Analysis."

TEST BAND

This parameter sets the bandwidth for reference wavelength analysis.

Parameter Settings for Each Analysis Item

Set the parameters of each WDM optical filter analysis item. An analysis parameter setting screen appears.

Note.

For details on the optical filter analysis algorithm and parameters, see appendix 6, "Optical Filter Analysis Function."

5.10 Editing the Grid Table

Procedure

Editing a Standard Grid Table


- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SYSTEM.
- 3. Tap Grid Editor. A grid table edit screen appears.

Setting the Frequency Spacing

4. Tap any of the keys from 200GHz Spacing to 12.5GHz Spacing. Depending on the selected key, a frequency spacing table of 200 GHz, 100 GHz, 50 GHz, 25 GHz, or 12.5 GHz can be used.

Setting the Reference Wavelength

- 5. Tap Reference Wavelength. A parameter input window appears.
- 6. Enter the reference wavelength in the parameter input window, and tap nm/ENT.



Editing a Custom Grid Table


- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SYSTEM.
- 3. Tap Grid Editor. A grid table edit screen appears.
- 4. Tap Custom. A custom grid table edit screen appears.

Setting the Start and Stop Wavelengths

- 5. Tap Start Wavelength or Stop Wavelength. A parameter input window appears.
- Enter the start or stop wavelength in the parameter input window, and tap nm/ ENT.

Setting the Frequency Spacing

- 7. Tap Spacing. A parameter input window appears.
- 8. Enter the frequency spacing in the parameter input window, and tap nm/ENT.
- **9.** Tap **Execute**. The settings entered up to this point are finalized, and the previous menu is displayed allowing setting of the reference wavelength.



Setting the Reference Wavelength


- 10. Tap Reference Wavelength. A parameter input window appears.
- 11. Enter the reference wavelength in the parameter input window, and tap nm/ENT.

Note _

- If you edit a custom grid table and tap Cancel without tapping Execute, the edits that have been made will be canceled.
- Tapping Execute applies the custom grid table to the analysis function.

Setting Channel Point Wavelength

- **5.** Continuing from step 4, tap the number of the channel point you want to change on the custom grid table edit screen. The cursor moves to the number that you tapped.
- 6. Tap Value Edit. A parameter input window appears.
- 7. Enter the wavelength in the parameter input window, and tap nm/ENT.



Inserting Channel Points

- **5.** Continuing from step 4, tap the number of the channel point you want to insert into on the custom grid table edit screen. The cursor moves to the number that you tapped.
- **6.** Tap **Insert**. A channel point is inserted with the same wavelength as the selected channel point. Subsequent channel points are shifted down by one point.

Deleting Channel Points

- **5.** Continuing from step 4, tap the number of the channel point you want to delete on the custom grid table edit screen. The cursor moves to the number that you tapped.
- **6.** Tap **Delete**. The selected channel point is deleted. Subsequent channel points are shifted up by one point.

Switching the Unit of the Wavelength Axis on the Grid Table to Frequency

- 1. Tap = Menu. The Main Menu window appears.
- 2. Tap MARKER.
- 3. Tap More to display the More 3/3 function menu.
- Tap Marker Unit nm THz. Each time you tap, the value switches between nm and THz.

Note .

For a description of the operation screen of the marker function menu, see section 4.9, "Marker Display."

Explanation

Grid Table

A grid table lists wavelengths (frequencies) that are referenced by part of the analysis function when it is executed. There is a standard grid table and a custom grid table.

Standard Grid Table

This grid table is created with pre-defined wavelength (frequency) ranges. It can be created by setting the reference wavelength (frequency) and frequency spacing.

200 GHz Spacing to 12.5 GHz Spacing

Creates a grid table with 200 GHz to 12.5 GHz grid spacing.

Reference Wavelength

Sets the grid table reference wavelength. You can set the value between 1200.0000 and 1650.0000 nm.

Custom Grid Table

This is a grid table that users can edit as they like. It is created automatically by setting the start/stop wavelength (frequency), reference wavelength (frequency), and frequency spacing. Users can add or delete an arbitrary channel to/from the created grid table or edit wavelength (frequency) values for each channel there.

Start Wavelength

Sets the start wavelength.

Stop Wavelength Sets the stop wavelength.

.

Spacing Sets the frequency spacing.

Reference Wavelength

Sets the grid table reference wavelength. You can set the value between 1200.0000 and 1650.0000 nm.

Value Edit

You can edit channel points.

Note .

For details on the grid table, see appendix 1, "Grid Table for WDM Wavelength."

5.11 Measurement of Level Fluctuations in Single-Wavelength Light (0 nm Sweeping)

Procedure

This function measures changes over time in the level of a specific wavelength level. It is useful for purposes such as optical axis alignment when connecting an optical fiber to a light source. The following discussion pertains to an example in which the spatial light of an He-Ne gas laser (1523.488 nm) is input to an optical fiber.

Setting the Center Wavelength to 1523.488 nm

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap CENTER. A function menu appears for setting the center wavelength.
- 3. Tap Center Wavelength. A parameter input window appears.
- 4. Enter the center wavelength 1523.488 nm in the parameter input window.
- 5. Tap nm/ENT.

Setting the Resolution to 2 nm

- **6.** Display the Main Menu window, and tap **SETUP**. A function menu appears for setting measurement conditions.
- 7. Tap Resolution. A menu appears for selecting the resolution.
- 8. Tap 2nm.

Note -

On the AQ6360, the resolution bandwidth during 0 nm sweeping is approximately 0.1 nm (varies depends on the wavelength), regardless of the resolution setting. As such, the measured power will not be affected even if you change the resolution value.

Setting the Sweep Width to 0 nm

- Display the Main Menu window, and tap SPAN. A function menu appears for setting the sweep span.
- 10. Tap Span Wavelength. A parameter input window appears.
- 11. Enter the sweep span 0 nm in the parameter input window.
- 12. Tap nm/ENT. The sweep span is set to 0 nm. The measurement start wavelength, measurement center wavelength, and measurement stop wavelength are all set to 1523.488 nm.

Note.


When you tap a value in the measurement condition area of the screen, the function menu automatically changes accordingly, and you can set the value directly. For details, see section 3.2, "Menu Operations" in IM AQ6360-02EN.

<meas. conditions=""> NEW</meas.>			SPEED: 1x	٦
START: 1523.488 nm	STOP: 1523.488 nm	CENTER: 1523.488 nm	SPAN: 0.0 nm	
RES: 2 nm	SENS: MID	AVG: 1	SMPL: 501(A)	

Measurement condition area

Setting the Sweep Time

- 13. Tap 0nm Sweep Time. A parameter input window appears.
- 14. Enter a sweep time in the parameter input window, and tap nm/ENT.
- 15. Display the Main Menu window, and tap SWEEP.
- 16. Tap Repeat. Sweeping will begin.




Note

- When the sweep range is set to 0 nm, the horizontal scale changes to time.
- The sweeping time varies depending on the measurement sensitivity (Sensitivity under SETUP). If the 0nm Sweep Time value is less than the sweeping time for each sensitivity, the setting for the key is invalid and the MINIMUM setting is used.

Explanation

The following figure shows the configuration for applying the spatial light of an He-Ne gas laser (1523.488 nm) into an optical fiber.



The sweep width is set to 0 nm, the center wavelength is fixed, and the level of a single wavelength of light is measured.

The optical fiber plug is adjusted while observing the displayed waveform so as to set the light source input level to the peak.

0nm Sweep Time

When the sweep width is 0 nm, the horizontal scale is time.

Set the time required to measure from the left edge to the right edge of the screen.

You can set the value in the range of 1 to 50 s or to MINIMUM. You can set it in steps of 1 s. When entering with the arrow keys when COARSE is selected, the value changes in steps of 1-2-5.

If 0 is entered, MINIMUM is shown on the display.

The sweeping time varies depending on the measurement sensitivity (Sensitivity under SETUP). If the 0nm Sweep Time value is less than the sweeping time for each sensitivity, the setting for the key is invalid and the MINIMUM setting is used.

The sampling points are automatically set to 1001.

5.12 Specifying an Analysis Range


Analysis between Line Markers

You can specify the range to be analyzed using line markers. The range between the two line markers is analyzed.

Power Measurement between Line Markers

The integrated power can be determined for the area between wavelength line marker 1 and wavelength line marker 2.

- **1.** Set wavelength line marker 1 and wavelength line marker 2 at either end of the range where you want to measure the integrated power.
- 2. Tap **Menu**. The Main Menu window appears.
- 3. Tap MARKER. A function menu appears for setting the marker.
- 4. Tap More to display the More 3/3 function menu.
- 5. Tap Search / Ana Marker L1- L2 to select ON.
- **6.** Display the Main Menu window, and tap **ANALYSIS**. A function menu appears for analyzing measured waveforms.
- 7. Tap Analysis 1. A menu appears for selecting the analysis function.
- **8.** Tap **POWER**. Analysis is performed between the line markers, and the results are displayed in the data area.
- **9.** To cancel, tap **Search / Ana Marker L1- L2** to select OFF. Analysis will be performed over the entire screen.



Note

- If both L1 and L2 are set, measurement is performed between line markers 1 and 2.
- If only L1 is set, the measurement is performed from line marker 1 to the right edge of the screen.
- If only L2 is set, measurement is performed from the left edge of the screen to line marker 2.
- If neither L1 or L2 is set, measurement is performed from the specified start wavelength to the stop wavelength.
- You can also set the parameter by tapping the ^{|src|}/₁₋₂ shortcut key at the bottom of the screen. When set to on, the shortcut key is highlighted.

Analysis in the Zoom Area


You can specify the zoomed area as the analysis range.

For example, the power in the zoom area can be measured. This function calculates the integrated power between display scales. It is a useful function for the ASE evaluation of optical amplifiers and the like.


Power Measurement in the Zoom Area

Optical power can be measured by integrating the measured waveform levels in the zoom area.

- Zoom the measured waveform. Set the display scale to the range you want to measure. For the procedure to zoom the waveform, see section 4.1, "Zooming a Waveform."
- 2. Tap **Menu**. The Main Menu window appears.
- 3. Tap MARKER. A function menu appears for markers.
- 4. Tap More to display the More 3/3 function menu.
- 5. Tap Search / Ana Zoom Area to select ON.



- 6. Display the Main Menu window, and tap **ANALYSIS**. A function menu appears for analyzing measured waveforms.
- 7. Tap Analysis 1. A menu appears for selecting the analysis function.
- **8.** Tap **POWER**. Analysis is performed between the display scales, and the results are displayed in the data area.



5.12 Specifying an Analysis Range

Note_

- You can also set the parameter by tapping the bottom of the screen. When set to on, the shortcut key is highlighted.
- If Search / Ana Zoom Area is set to OFF, analysis is performed over the entire range of the measurement scale.
- For details on the power analysis function, see appendix 3, "Details of Each Analysis Function."

Explanation

When the line marker search function and zoom area search functions are enabled at the same time, the intersection of the two ranges is the range for analysis.

The following figure shows the analysis range of a power measurement when both Search / Ana Marker L1- L2 and Search / Ana Zoom Area are set to ON. Because both settings are ON, the $\frac{SRC}{1+2}$ and $\frac{SRC}{2OM}$ shortcut keys at the bottom of the screen are highlighted.


YOKOGAWA	2018 Jan 16 17:4	
POWER: -21.38dBm (7.274µW)	B:FIX /BL C:FIX /BL	K Spec Width
OFFSET: 0.00dB	D:FIX /BL E:FIX /BL	K THRESH
	F:FIX /BL G:FIX /BL	Analysis 1
<meas. conditions=""> SPEED: START: 1543.200 nm STOP: 1563.200 nm CENTER: 1553.200 nm SPAN:</meas.>	1x 20.0 nm	POWER
	1001(M)	Analysis 2
10.0 L1:1551.6307nm L2:1553.4010nm		WDM
-10.0 REF. L2-11: 1,2703nm		Analysis Execute POWER
Range where the area between the		Spec Width Thresh
line markers and zoom area overlap	- 1 A T	
		Parameter Setting
		Switch Display
-50.0		TRACE&TABLE
	<u> </u>	Auto Analysis
-70.0		OFF ON
A = 1 = 1 = 1 = 1 = 1 = 1 = 1 = 1 = 1 =	LINN I I -	_
الألب المراجع المرجع المراجع الممراجع المراجع المراجع المراجع المراجع المراجع المراجع	www	Analysis
1548.184 nm ZOOMING 1552.884 nm 0.94 nm/D	1557.584 nr	m More 1/2
LVL WL NOI SRC SRC VL AUT AUT AUT AUT AUT AUT SWP	SMO RPT SGL ST	

5.13 Correcting the Displayed Values

Procedure


Set the amount of wavelength shift.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SYSTEM.
- 3. Tap Wavelength Shift. A parameter input window appears.
- 4. Enter the amount of wavelength shift in the parameter input window.
- 5. Tap µm/ENT or nm/ENT.



Setting the Amount of Level Shift

- 1. Tap **Menu**. The Main Menu window appears.
 - 2. Tap SYSTEM.
 - 3. Tap Level Shift. A parameter input window appears.
 - 4. Enter the amount of level shift in the parameter input window.
 - 5. Tap µm/ENT or nm/ENT.



Note

After you enter the amount of wavelength or level shift, it is applied to the displayed values when the next measurement is performed.

Determining the Amount of Level Shift

Even when the NA of the optical fiber in use is unknown, the amount of level shift is determined so that correct level measurements can be performed.


- **1.** Set up a light source such as a DFB-LD with a spectrum width that is narrower than the instrument's resolution (with a wavelength of 1310 nm or 1550 nm).
- **2.** Connect the light source and the instrument using an optical fiber cord and set the instrument's resolution to 2.000 nm.
- 3. Perform a measurement to determine the peak level.
- **4.** Disconnect the optical fiber cord from the instrument and connect it to a light power meter to measure the light power.
- **5.** Calculate the difference between the peak level value obtained from the instrument and the power value obtained from the light power meter, and set this amount as the instrument's level shift.

Explanation

Numerical Aperture (NA) of Input Optical Fibers and Level Measurements

The level measurement errors of this instrument varies depending on the numerical aperture (NA) of the optical fiber connected to the input connector section. The absolute level of this instrument is calibrated with a $9.5/125 \,\mu$ m single mode optical fiber (SSMA type in JIS C6835, PC polishing, mode field diameter: $9.5 \,\mu$ m, NA: 0.104 to 0.107). If the NA value is not within this range even for single mode optical fibers, the level accuracy is not guaranteed.

Numerical aperture of input optical fibers and level errors (representative characteristics)



Absolute Level Accuracy

The absolute level of this instrument is calibrated with a $9.5/125 \ \mu m$ single mode optical fiber (SSMA type in JIS C6835, PC polishing, mode field diameter: $9.5 \ \mu m$, NA: 0.104 to 0.107). The level accuracy when other optical fibers are used is not guaranteed. For multi-mode (GI) fibers, a relatively accurate spectrum is indicated for low-coherence light, such as white light, natural light, and LEDs.

For high-coherence light, such as a laser beam, interference occurs within the optical fiber, and the intensity distribution of light reflected from the end of the fiber varies depending on the fiber form. As such, moving the fiber may change the spectrum (measurement level).

Wavelength Shift **.**nm

Sets the amount of wavelength shift.

When the wavelength shift is changed, the specified value is added to the display value on the wavelength axis. This key is used for purposes such as correcting differences in wavelength display values among different measurement instruments.

The setting range is -5.000 to 5.000 nm. You can set it in steps of 0.001 nm. When entering with the arrow keys when COARSE is selected, the value changes in steps of 0.1 nm.

You can also set the parameter by tapping the $\frac{WL}{SHF}$ shortcut key at the bottom of the screen. When you set the amount of wavelength shift, the shortcut key is highlighted.

Level Shift ***.***dB

Sets the amount of level shift.

When the level shift is changed, the specified value is added to the display value on the level axis.

This key is used for purposes such as correcting level errors due to differences in the NA values of $9.5/125 \ \mu m$ SM optical fibers connected to the instrument, and correcting loss on externally connected isolators, filters and the like.

The setting range is -60.00 to 60.00 dB. You can set it in steps of 0.01 dB. When entering with the arrow keys when COARSE is selected, the value changes in steps of 0.1 dB.

You can also set the parameter by tapping the $\frac{|V|}{|SHF|}$ shortcut key at the bottom of the screen. When you set the amount of level shift, the shortcut key is highlighted.

6.1 USB Storage Device

Compatible USB Storage Devices

The instrument supports USB memory devices and hard drives compliant with USB 1.0 or USB 2.0.

For more details, contact your nearest YOKOGAWA dealer.

Removing a USB Storage Device

Be sure to follow the procedure below to remove a USB storage device.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap FILE. A function menu appears for saving and loading data.
 - Check whether the Remove USB Storage key is disabled (dimmed). If it is, the USB storage device can be removed.
- **3.** If the Remove USB Storage key is enabled, Tap **Remove USB Storage**. The Remove USB Storage key is disabled (dimmed), and the USB storage device can be safely removed.



Note -

- If there are multiple connected USB storage devices, the instrument detects only the one connected first.
- If you restart the instrument, the devices connected afterward will also be detected.
- For other notes, see the instruction manual supplied with the USB memory device.

6.2 Saving and Loading Waveform Data

Procedure

You can save waveforms displayed on the instrument to a USB storage device or internal memory and load data from a USB storage device.



CAUTION

Do not remove the USB storage medium or turn the power OFF while the USB storage medium access indicator is blinking. This can damage the data on the medium or the device itself. Also, always place a USB storage medium in the removable state (following the procedure in section 6.1) before removing it.

French



ATTENTION

Ne retirez pas le dispositif de stockage USB et ne coupez pas l'alimentation lorsque le voyant d'accès au dispositif de stockage USB clignote.

Cela risquerait d'endommager le dispositif ou les données se trouvant sur ce dernier. De plus, toujours faire passer un support de stockage USB à l'état de retrait en toute sécurité (en suivant la procédure figurant à la section 6.1) avant de le retirer.

Saving Trace Data


Selecting the Method of Automatically Setting the File Name

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap FILE. A function menu appears for saving and loading data.
- 3. Tap Auto File Name to select NUM (serial number) or DATE.

Setting the Type of File to Save to TRACE

- 4. Tap Item Select. A menu appears for selecting the type of file to save or load.
- 5. Tap Trace. Trace is selected, and the menu returns to the previous level.
- 6. Tap Write. A trace list and a file list are displayed on the screen.

6.2 Saving and Loading Waveform Data



Selecting the Save Destination and Data Format


- 7. Tap Memory to select INT (internal memory) or EXT (USB storage device).
- 8. Tap File Type to set the data format to BIN (binary format) or CSV (ASCII format).




6

Selecting a Trace to Save

9. Tap **Trace** @→**File** (where @ is the currently selected trace number). Traces A through G are displayed in a function menu.





Note.

Instead of tapping Trace @—File, you can also tap the appropriate line on the trace list to select the trace to save.

Entering a File Name (When Saving to a Specific File Name)


If you do not set a file name, the file will automatically be assigned a name using a serial number or date.

For instructions on how to create directories and sort the file list, see the next page.

- 11. Tap the line displaying "NEW FILE" to move the cursor to it.
- 12. Tap File Name. A keyboard appears.
- 13. Use the keyboard to input the new file name.

For instructions on how to enter text, see section 3.3, "Entering Numerical Values and Strings," in IM AQ6360-02EN.

14. Tap **Done**. The file name is confirmed, and the screen returns to the previous level.



Saving the File

- **15.** To overwrite an existing file, move the cursor to the name of the file you want to overwrite.
- 16. Tap Execute. The file is saved.

If you tap **Return**, the data will not be saved. The menu will return to the previous level.

17. When overwriting a file, a confirmation message appears. Tap YES.

To cancel saving, tap NO.


										1	Menu	
			WRI	E : TRACE	B TO FILI						Memory	
				TRACE I						1	INT EXT	
TR	CENTER	SPAN [/DIV]	REF LVL	[/DIV]	RESLN	AVG	SAMPL	SENS	ATTR		File Name	
	1539.720nm	1.00nm	1.4dBm	10.0dB		1		MID	MEAS	1	File Name	
	1425.000nm	45.00nm	1.4dBm	10.0dB		1		NORM/AUT	MEAS			
	1425.000nm 1425.000nm	45.00nm 45.00nm	1.4dBm 1.4dBm	10.0dB 10.0dB		1		NORM/AUT NORM/AUT	MEAS		Trace B	
	1425.000nm	45.00nm	1.4dBm	10.0dB		1		NORM/AUT	MEAS		-> File	
	1425.000nm	45.00nm	1.4dBm	10.0dB		ī		NORM/AUT	MEAS			
G	1539.000nm	0.20nm	1.4dBm	10.0dB	0.1nm	1	501	MID	PKCVFIT A		File Type	
				v							The type 1	File nam
CI	E NAME> INT	:\w0008.wv/								Y	BIN CSV	
- 11		. (100001117)										
	FILE	NAME		DATE &	TIME		LABEL/F	ROGRAM NA	ME			
W	0008.WVA			<new f<="" th=""><th>ILE></th><th></th><th></th><th></th><th></th><th></th><th></th><th></th></new>	ILE>							
DF	B-LD		201	8/02/28	14:58:20		<d3< th=""><th>RECTORY></th><th></th><th></th><th>Make Directory</th><th></th></d3<>	RECTORY>			Make Directory	
w	0000.WVA		201	8/02/28	14:56:07						Directory	
w	0001.WVA				14:56:31						P	
	0002. WVA										File Sort	
					14:56:45						ETLE NAME	
W	0003.WVA		201	.8/02/28	14:57:01					1	Execute	
W	0004.WVA		201	8/02/28	14:57:19						Execute	
w	0005.WVA		201	8/02/28	14:57:28					I		
w	0006.WVA		201	8/02/28	14:57:56					N		
w	007. WVA		201	8/07/78	14:57:57						-	
			203	.0/02/20	1413/13/						Write	
	TAL: 10 FILE	S				FF	REE:	584 336	9,456 BYTES	1	Return	

Creating a Directory and Sorting Files

Perform the following procedure if needed.

18. Tap Make Directory.

- **19.** Tap **Directory Name**. A keyboard appears. Enter a directory name in the same manner as when entering a file name.
- Tap Execute. A directory will be created. Tap Cancel if you do not want to create the directory.
- 21. Tap File Sort. A menu appears for selecting the item to sort by.
- **22.** Tap the item you want to sort by. The files are sorted in ascending order by the selected item.




6

Loading Trace Data

Setting the Type of File to Load to TRACE

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap FILE. A function menu appears for saving and loading data.
- 3. Tap Item Select. A menu appears for selecting the type of file to save or load.
- 4. Tap Trace. Trace is selected, and the menu returns to the previous level.
- 5. Tap Read. A file list and a trace list appear on the screen.




Selecting the File to Load

- **6.** Tap **Memory** to select INT (internal memory) or EXT (USB storage device). The file list of the selected device appears.
- Tap a line in the file list to move the cursor to the file you want to load.
 Tapping View changes the display between list and thumbnail. To sort the files, see page 6-5.

Kogawa 🔶		2018	3 Feb 28 15:00	= Monu	Thumbna	ii uispi	ay					
	READ : FILE TO TRACE A		M	lemory			READ	: FILE TO	TRACE A			
FILE NAME> INT:\DFB-LD				INT EXT	FILE NAME> INT	:\DFB-LD						
FILE NAME	DATE & TIME	LABEL/PROGRAM NA	ME									
DFB-LD	2018/02/28 14:58:20	<directory></directory>										
w0000.wva	2018/02/28 14:56:07		Fi Fi	ile > Trace A					111	t i alla	1 0	- /ILI
w0001.wvA	2018/02/28 14:56:31		*	> Hace A	DIRECTORY	r		1 11	L) I A A	MAL		
w0002.wvA	2018/02/28 14:56:45			P					00000	poor		~
v0003.wvA	2018/02/28 14:57:01											
w0004.wvA	2018/02/28 14:57:19				DFB-LD	le le	0000.WVA		W0001.W	VA	W0002.W	VA
v0005. wvA	2018/02/28 14:57:28		Vi	iew								
v0006, wvA	2018/02/28 14:57:56			LIST THUMB			А					
W0007.WVA	2018/02/28 14:57:57						\sim				.	
									<i>ä</i>		Imme	m
								ᆜᄕ				
			Fi	ile Sort	W0003.WV/	. Iv	0004.WVA		W0005.W	VA	W0006.W	VA
TOTAL: 9FILES		FREE: 582,88	9,472 BYTES	FILE NAME	TOTAL: 9FILE	S				FREE	: 582,8	889,472 B
	TRACE LIST		E	xecute				TRACE L	IST			
R CENTER SPAN [/DIV]		AVG SAMPL SENS	ATTR		TR CENTER	SPAN [/DIV]	REF LVL	LVL SCL		AVG S/	AMPL SENS	ATT
1539.720nm 1.00nm	1.4dBm 10.0dB 0.1nm	1 501 MID	MEAS		A 1539.720nm	1.00nm	1.4dBm	10.0dB	0.1nm	1	501 MID	MEAS
8 1425.000nm 45.00nm	1.4dBm 10.0dB 1nm	1 2251 NORM/AUT		-	B 1425.000nm C 1425.000nm	45.00nm	1.4dBm	10.0dB 10.0dB			2251 NORM/AU	
1425.000nm 45.00nm 1425.000nm 45.00nm	1.4dBm 10.0dB 1nm 1.4dBm 10.0dB 1nm	1 2251 NORM/AUT 1 2251 NORM/AUT		Read	C 1425.000nm D 1425.000nm	45.00nm 45.00nm	1.4dBm 1.4dBm	10.0dB 10.0dB			2251 NORM/AU 2251 NORM/AU	
1425.000nm 45.00nm	1.4dBm 10.0dB 1nm	1 2251 NORM/AUT			E 1425.000nm	45.00nm	1.4dBm	10.0dB	1nm	1	2251 NORM/AU	T MEAS
1425.000nm 45.00nm	1.4dBm 10.0dB 1nm	1 2251 NORM/AUT	MEAS		F 1425.000nm	45.00nm	1.4dBm	10.0dB		1	2251 NORM/AU	T MEAS
3 1539.000nm 0.20nm	1.4dBm 10.0dB 0.1nm	1 501 MID	PKCVFIT A R	eturn	G 1539.000nm	0.20nm	1.4dBm	10.0dB	0.1nm	1	501 MID	PKCVFI

Selecting the Trace to Assign the Loaded Data To

- **8.** Tap **File**→**Trace** @ (where @ is the currently selected trace number). Traces A through G are displayed in a function menu.
- **9.** Tap the trace you want to assign.



Note_

Instead of tapping File \rightarrow Trace @, you can also tap the appropriate line on the trace list to select the trace to assign.

Loading the File

10. Tap Execute. The file is loaded.

If you tap **Return**, the file will not be loaded. The menu will return to the previous level.

11. Tap **Return**. The file list and trace list disappear, and the waveform is displayed in the assigned trace.

KO	gawa 🔶							2018	Feb 28 15:01	≡ M enu
			REAL	D : FILE T	O TRACE B					Memory
FI	LE NAME>	NT:\W0000.WV	'A							INT EX
	F	TILE NAME		DATE &	TIME		LABEL/P	ROGRAM NAM	ME	
D	FB-LD		201	18/02/28	14:58:20		<d1< td=""><td>RECTORY></td><td></td><td></td></d1<>	RECTORY>		
W	0000.WVA		201	18/02/28	14:56:07					File
w	0001.WVA		201	L8/02/28	14:56:31					-> mace b
w	0002.WVA		201	18/02/28	14:56:45					
w	0003.WVA		201	18/02/28	14:57:01					
w	0004.WVA		201	18/02/28	14:57:19					
w	0005. WVA		201	18/02/28	14:57:28					View
w	0006.WVA		201	L8/02/28	14:57:56					LIST THUN
w	0007.WVA		201	L8/02/28	14:57:57					
										File Sort
TC	TAL: 9F	ILES				F	REE:	582 880	9.472 BYTES	FTI F NAM
10	17AL. 91.	1115					NLL.	502,005	, HIZDITES	Execute
				TRACE I						Execute
R	CENTER	SPAN [/DIV]	REF LVL	LVL SCL	RESLN	AVG	SAMPL	SENS	ATTR	
١	1539.720nm	1.00nm	1.4dBm	10.0dB		1	501	MID	MEAS	
	1425.000nm		1.4dBm	10.0dB		1		NORM/AUT	MEAS	
	1425.000nm		1.4dBm	10.0dB		1		NORM/AUT	MEAS	Read
	1425.000nm		1.4dBm	10.0dB		1		NORM/AUT	MEAS	Read
-	1425.000nm		1.4dBm	10.0dB		1		NORM/AUT	MEAS	
	1425.000nm		1.4dBm 1.4dBm	10.0dB	1nm 0.1nm	1		NORM/AUT MID	MEAS PKCVFIT A	Return
	1539.000nm									

6

Explanation

You can save data from traces A to G to internal memory or a USB storage device or assign previously saved data to trace A to G and display it.

Extensions

The file name extensions for saving data are shown below. BIN (binary format): .WVA CSV (ASCII format): .CSV

File Name

You can save files by assigning their names automatically or with specific names. If you do not specify a file name, the following file name will be assigned automatically according to the Auto File Name setting.

When Auto File Name is set to NUM

File name: WXXXX.CSV (or .WVA)

XXXX is a serial number from 0000 to 9999.

When Auto File Name is set to DATE

File name: Wyyyymmdd_hhmmss.CSV (or .WVA)

yyyymmdd:		Yea	r (Gregori	an) m	ionth day
hhmmss:		Hou	r (24 hour	s)	mi	nute second
(D 1 //)		~ 1				15

(Date/time when the file list was updated)

Note -

• The date/time used when file names are assigned based on the date through remote commands or program commands is the date/time when the file is created.

When assigning a file name manually, use characters that are allowed by MS-DOS. The maximum number of characters that you can use for a file name is 56 (including the extension).
 The characters that you can use are shown below.
 !#\$%&'() 0123456789@
 ABCDEFGHIJKLMNOPQRSTUVWXYZ^

abcdefghijklmnopqrstuvwxyz{}

Data Format

Data can be saved in the following two formats.

BIN

Data is saved in binary format.

You cannot view the waveform data directly using an external application. The file size will be smaller than that of ASCII format.

CSV

Data is saved in comma-separated (CSV) ASCII format.

You can view the waveform data directly using an external application. The file size will be larger than that of binary format.

File Size

The file size varies depending on the data that you are saving. Check that there is sufficient free space at the storage destination before saving the data.

Sorting Files

You can sort the file list in ascending order by file name, file type, date, or label.

CSV Data Format

CSV data is saved in the following format.

60CSV	Header Measurement condition parameters
"MEASWL",1 "SWPSPD",0 "MODELNAME","AQ6360" "NEBWCAL0",0 "NEBWCAL1",0 "NEBWCALVL",0 "RESPARM",0 "FREQPARM",0	
"CHGPT",0 "RESCAL0_0",10000 "RESCAL0_1",0 "RESCAL0_2",0	
"[TRACE DATA]" 1546.8000, -53.419 1546.8100, -53.370 : :	Waveform data
1551.8000, -51.535	
Header	
60CSV File header	
// AQ6360 OPTICAL SPECTRUM ANALY	ZER // Label (57 characters)
35 Number of lines to TRA	

Measurement condition parameters

"CTRWL",1549.300000	Center wavelength
"SPAN", 5.000000	Span
"START WL",1546.800000	Measurement start wavelength
"STOP WL",1551.800000	Measurement stop wavelength
"WLFREQ", 0	Horizontal scale mode
	(0: wavelength mode, 1: frequency mode)
"REFL",+8.2	Reference level
"LSCL",10.0	Main level scale
"RESLN",0.100	Measurement resolution
"AVG",1	Average times
"SMPLAUTO",1	Sample points setting mode
	(0: MANUAL, 1: AUTO, 2: SMPL INTVL)
"SMPL", 501	Number of measured sampling points
"SMPLINTVL",0.0100	Measurement sampling interval
"MID"	Measurement sensitivity
"MEAS"	Measurement type
"LSUNT",0	Vertical scale mode (0: dBm, 1: dBm/nm)
"NMSKH","OFF"	Noise mask setting
	(NMSKV: VERTICAL, NMSKH: HOLIZONTAL)
"RESCOR",1	Resolution correction setting (0: OFF, 1: ON)
"SMOOTH",0	Smoothing setting (0: OFF, 1: ON)
"FIBERTYPE",0	Fiber connector setting (0: NORM, 1: ANGLED)
"MEASWL",1	Wavelength in air or vacuum (0: AIR, 1: VACUUM)
"SWPSPD",0	Sweep speed (0: 1x, 1: 2x)
"MODELNAME","AQ6360"	Model name
"NEBWCAL0",0	Resolution calibration coefficient
"NEBWCAL1",0	Resolution calibration coefficient
"NEBWCALWL",0	Resolution calibration wavelength
"RESPARM",0	RMS wavelength resolution coefficient
"FREQPARM",0	RMS frequency resolution coefficient
"CHGPT",0	Diffraction order parameter (fixed to 0)
"RESCAL0_0",10000	RMS resolution correction coefficient
"RESCAL0_1",0	RMS resolution correction coefficient
"RESCAL0_2",0	RMS resolution correction coefficient

The reference level and main level scale are saved to one of the following depending on the vertical scale.

N / - :	1	
iviain	ievei	scale

Vertical Axis Scale	Save Format	Description	
LOG	"REFL",***.*	Reference level	
	"LSCL",***.*	Level scale	
Linear"REFL",***.*	Reference level		
	"LSCL",***.*	Level scale	
	"BASEL",****.**	Base level	

Sub lev	el scale		
Vertical	Axis Scale	Save Format	Description
LOG		"REFL",***.*	Reference level
		"SSCLLOG",***.*	Level scale
		"LOFST",***.*	Level offset
Linear"F	REFL",***.*	Reference level	
		"SSCLN",***.*	Level scale
		"SMIN",****.**	Base level
DB/km	"REFL",***.*	Reference level	
	"SSKM",**.*	Level scale	
	"OFSKM",***.*	Offset level	
	"LENG",**.***	Optical fiber length	
%	"REFL",***.*	Reference level	
	"SSPS",***.*	Level scale	
	"SMINP",***.*	Base level	

Measurement Sensitivity

The data below is saved as measurement sensitivity depending on the measurement sensitivity type.

Format (during gate sampling measurement)	Measurement Sensitivity Type
"G-NORM-HOLD",****.*	NORM/HOLD
"G-NORM-AUTO",****.*	NORM/AUTO
"G-NORMAL",****.*	NORMAL
"G-MID",****.*	MID
"G-HIGH 1",**** *	HIGH 1
"G-HIGH 2",**** *	HIGH 2
	"G-NORM-HOLD",****.* "G-NORM-AUTO",****.* "G-NORMAL",****.* "G-MID",****.* "G-HIGH 1",****.*

HIGH 1 and HIGH 2 are available only on the standard model (-10).

Measurement Identifier

The data below is saved as a waveform identifier depending on the waveform type.

Format	Waveform Type	Format	Waveform Type	Format	Waveform Type
"MEAS"	WRITE	"E-D"	E-D(LOG)	"C+FL"	C+F(LIN)
"MAXH"	MAX HOLD	"C+D"	C+D(LOG)	"C-FL"	C-F(LIN)
"MINH"	MIN HOLD	"D+E"	D+E(LOG)	"F-CL"	F-C(LIN)
"RAVG"	ROLL AVG	"C+DL"	C+D(LIN)	"E+FL"	E+F(LIN)
"A-B"	A-B(LOG)	"C-DL"	C-D(LIN)	"E-FL"	E-F(LIN)
"B-A"	B-A(LOG)	"D-CL"	D-C(LIN)	"F-EL"	F-E(LIN)
"A+B"	A+B(LOG)	"D+EL"	D+E(LIN)	"NORM A"	NORMALIZE A
"A-BL"	A-B(LIN)	"D-EL"	D-E(LIN)	"NORM B"	NORMALIZE B
"B-AL"	B-A(LIN)	"E-DL"	E-D(LIN)	"NORM C"	NORMALIZE C
"A+BL"	A+B(LIN)	"C-F"	C-F(LOG)	"CVFT A",**	CURVE FIT A
"1-K(A/B)",*****.***	1-k(A/B)	"F-C"	F-C(LOG)	"CVFT B",**	CURVE FIT B
"1-K(B/A)",*****.***	1-k(B/A)	"E-F"	E-F(LOG)	"CVFT C",**	CURVE FIT C
"C-D"	C-D(LOG)	"F-E"	F-E(LOG)	"CVFTPK A",**	PK CURVE FIT A
"D-C"	D-C(LOG)	"C+F"	C+F(LOG)	"CVFTPK B",**	PK CURVE FIT B
"D-E"	D-E(LOG)	"E+F"	E+F(LOG)	"CVFTPK C",**	PK CURVE FIT C

Waveform Data

The measured waveform data is stored as sets of wavelength (in nm) and level. The number of sets equals the number of measurement samples. Waveforms measured in frequency mode are stored using their frequencies (THz).

Level values are stored as log values if the vertical scale is LOG, and as linear values if the vertical scale is linear.

(For LOG scale)	
[TRACE DATA]	Header indicating the start of the trace data
****.****, ±***.***(CR)(LF)	Wavelength value, level value (LOG) of the first point
*****.****, ±****.***(CR)(LF)	Wavelength value, level value (LOG) of the second point
****.****, ±***.***(CR)(LF)	Wavelength value, level value (LOG) of the last point
(For linear scale)	
[TRACE DATA]	Header indicating the start of the trace data
(Header indicating the start of the trace data Wavelength value, level value (linear) of the first point
[TRACE DATA]	5
[TRACE DATA] ****.****,*.***E±***(CR)(LF)	Wavelength value, level value (linear) of the first point

6.3 Saving and Loading Waveform Data (All Trace)

Procedure

You can save waveform data (all measured trace data) displayed on the instrument to a USB storage device and load data from a USB storage device.



CAUTION

Do not remove the USB storage medium or turn the power OFF while the USB storage medium access indicator is blinking. This can damage the data on the medium or the device itself. Also, always place a USB storage medium in the removable state (following the procedure in section 6.1) before removing it.

French



ATTENTION

Ne retirez pas le dispositif de stockage USB et ne coupez pas l'alimentation lorsque le voyant d'accès au dispositif de stockage USB clignote.

Cela risquerait d'endommager le dispositif ou les données se trouvant sur ce dernier. De plus, toujours faire passer un support de stockage USB à l'état de retrait en toute sécurité (en suivant la procédure figurant à la section 6.1) avant de le retirer.

Saving All Trace Data


Selecting the Method of Automatically Setting the File Name

Select the method of automatically setting the file name by referring to page 6-2.

Setting the Type of File to Save to ALL TRACE

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap FILE. A function menu appears for saving and loading data.
- 3. Tap Item Select. A menu appears for selecting the type of file to save or load.
- 4. Tap All Trace. All Trace is selected, and the menu returns to the previous level.
- 5. Tap Write. A trace list and a file list are displayed on the screen.

6.3 Saving and Loading Waveform Data (All Trace)



Selecting the Save Destination

5. Tap Memory to select INT (internal memory) or EXT (USB storage device).




Entering a File Name (When Saving to a Specific File Name)

If you do not set a file name, the file will automatically be assigned a name using a serial number or date.

- 6. Tap the line displaying "NEW FILE" to move the cursor to it.
- 7. Tap File Name. A keyboard appears.
- 8. Use the keyboard to input the new file name.

For instructions on how to enter text, see section 3.3, "Entering Numerical Values and Strings," in IM AQ6360-02EN.

9. Tap **Done**. The file name is confirmed, and the screen returns to the previous level.




Saving the File

- **10.** To overwrite an existing file, move the cursor to the name of the file you want to overwrite.
- 11. Tap Execute. The file is saved.

If you tap **Return**, the data will not be saved. The menu will return to the previous level.

12. When overwriting a file, a confirmation message appears. Tap YES.


To cancel saving, tap NO.



Loading All Trace Data

Setting the Type of File to Load to ALL TRACE

- 1. Tap **E Menu**. The Main Menu window appears.
- 2. Tap FILE. A function menu appears for saving and loading data.
- 3. Tap Item Select. A menu appears for selecting the type of file to save or load.
- 4. Tap All Trace. All Trace is selected, and the menu returns to the previous level.
- 5. Tap Read. A file list and a trace list appear on the screen.



Selecting the File to Load

6-5.

- **5.** Tap **Memory** to select INT (internal memory) or EXT (USB storage device). The file list of the selected device appears.
- Tap a line in the file list to move the cursor to the file you want to load.
 You can sort the files tapping File Sort. For the operating procedure, see page

Kogawa 🔶							2018	Feb 28 15:02	2 <u>— Manu</u>	
		READ	: FILE TO	ALL TRAC	E				Memory	
FILE NAME> INT	:\A0001.C5	/							INT EXT	
FIL	E NAME		DATE &	TIME		LABEL/F	ROGRAM NA	ME		Í
DFB-LD		201	8/02/28	14:58:20		<d.< td=""><td>ERECTORY></td><td></td><td></td><td></td></d.<>	ERECTORY>			
A0000.CSV		201	8/02/28	15:02:00						
A0001.CSV		201	8/02/28	15:02:01						
A0002.CSV		201	8/02/28	15:02:01						
A0003.CSV		201	8/02/28	15:02:01						
A0004.CSV		201	8/02/28	15:02:03						
A0005.CSV		201	8/02/28	15:02:04						
A0006.CSV		201	8/02/28	15:02:04						
A0007.CSV		201	8/02/28	15:02:05						
A0008.C5V		201	8/02/28	15:02:05						
A0009.CSV		201	8/02/28	15:02:06					File Sort	
A0010.CSV		201	8/02/28	15:02:07						Sorts files
TOTAL: 12 FILI	ES				F	REE:	580,022	2,272 BYTES	FILE NAME	
			TRACE	ICT					Execute	
CENTER	SPAN [/DIV]	REF LVL	LVL SCL	RESLN	AVG	SAMPL	SENS	ATTR		
A 1539.720nm	1.00nm	1.4dBm	10.0dB		1	501	MID	MEAS		
B 1425.000nm	45.00nm	1.4dBm	10.0dB		1		NORM/AUT	MEAS		
C 1425.000nm	45.00nm	1.4dBm	10.0dB		1		NORM/AUT	MEAS	Read	
D 1425.000nm	45.00nm	1.4dBm	10.0dB		1		NORM/AUT	MEAS		
E 1425.000nm	45.00nm 45.00nm	1.4dBm 1.4dBm	10.0dB 10.0dB		1		NORM/AUT NORM/AUT	MEAS MEAS		
3 1539.000nm	45.00nm 0.20nm	1.4dBm 1.4dBm	10.0dB		1		MID	PKCVFIT A	Return	

Loading the File

7. Tap Execute. The file is loaded.

If you tap **Return**, the file will not be loaded. The menu will return to the previous level.

8. Tap **Return**. The file list and trace list disappear, and the waveforms loaded from the file is displayed.

									LOXO	Feb 28 15:02	🗮 Menu
				READ	: FILE TO	ALL TRAC	Е				Memory
FI	e name>	INT	\A0001.CS	/							INT E
Г		FILE	NAME		DATE &	TIME		LABEL/P	ROGRAM NAM	1E	
D	B-LD			201	8/02/28	14:58:20		<d1< td=""><td>RECTORY></td><td></td><td></td></d1<>	RECTORY>		
A	0000.csv			201	8/02/28	15:02:00					
A	001.csv			201	8/02/28	15:02:01					
A	0002.csv			201	8/02/28	15:02:01					
A	0003.csv			201	8/02/28	15:02:01					
A	0004.csv			201	8/02/28	15:02:03					
A	0005.csv			201	8/02/28	15:02:04					
A	0006.CSV			201	8/02/28	15:02:04					
A	0007.CSV			201	8/02/28	15:02:05					
A	0008.CSV			201	8/02/28	15:02:05					
A	0009.CSV			201	8/02/28	15:02:06					File Sort
A	0010.CSV			201	8/02/28	15:02:07					
тс	TAL: 12	FILE	S				F	REE:	580,022	,272 BYTES	ETLE NAM
_					TRACE	IST					Execute
TR	CENTER		SPAN [/DIV]	REF LVL	LVL SCL		AVG	SAMPL	SENS	ATTR	
	1539.720r		1.00nm	1.4dBm	10.0dB	0.1nm	1		MID	MEAS	<u> </u>
	1425.000r		45.00nm	1.4dBm		1nm	1		NORM/AUT	MEAS	-
	1425.000r 1425.000r		45.00nm 45.00nm	1.4dBm 1.4dBm	10.0dB 10.0dB		1		NORM/AUT NORM/AUT	MEAS MEAS	Read
	1425.000r		45.00nm	1.4dBm	10.0dB		1		NORM/AUT	MEAS	
Ē	1425.000r		45.00nm	1.4dBm		1nm	î		NORM/AUT	MEAS	
G	1539.000r	m	0.20nm	1.4dBm	10.0dB	0.1nm	1		MID	PKCVFIT A	Return

Explanation

You can save measured waveform data in a single file in the internal memory or a USB storage device and load previously saved data into traces A and G and display it.

Extension

Data is saved to a file with .CSV extension.

File Name

You can save files by assigning their names automatically or with specific names. If you do not specify a file name, the following file name will be assigned automatically according to the AUTO FILE NAME setting. When AUTO FILE NAME is set to NUM

File name: AXXXX.CSV

XXXX is a serial number from 0000 to 9999.

When AUTO FILE NAME is set to DATE

File name: Ayyyymmdd_hhmmss.CSV

yyyymmdd :Year (Gregorian) month dayhhmmss:Hour (24 hours) minute second(Date/time when the file list was updated)

Note .

- The date/time used when file names are assigned based on the date through remote commands or program commands is the date/time when the file is created.
- When assigning a file name manually, use characters that are allowed by MS-DOS. The maximum number of characters that you can use for a file name is 56 (including the extension).
 The characters that you can use are shown below.
 !#\$%&'() 0123456789@

ABCDEFGHIJKLMNOPQRSTUVWXYZ^

abcdefghijklmnopqrstuvwxyz{}

File Size


The file size varies depending on the data that you are saving. Check that there is sufficient free space at the storage destination before saving the data.

Sorting Files

You can sort the file list in ascending order by file name, date, or label.

CSV Data Format

CSV data is saved in the following format.



Header

60CSVG	File header
// AQ6360 OPTICAL SPECTRUM ANALYZER //	Label (57 characters)

Measurement condition parameters

Measurement conditions of each trace, measurement conditions when files were saved, and trace settings are saved.

[MEAS SETTING] section:	Measurement settings when files were saved
[TRACE SETTING] section:	Trace settings
	(active trace information, each trace's settings,
	presence/absence of measured data)
[TRACE A] to [TRACE G]:	Measurement conditions for each trace
The waveform condition format is	the same as that of the waveform file.

See section 6.2, "Saving and Loading Waveform Data."

Measured Data

The measured waveform data of traces A through G are saved as wavelength and level vales of the measured number of samples.

Unmeasured trace data is not saved.

Waveforms measured in Frequency mode are also saved as wavelength values.

6.4 Saving and Loading Setting Data

Procedure

You can save the instrument's measurement conditions and function menu states to a file in binary format.



CAUTION

Do not remove the USB storage medium or turn the power OFF while the USB storage medium access indicator is blinking. This can damage the data on the medium or the device itself. Also, always place a USB storage medium in the removable state (following the procedure in section 6.1) before removing it.

French



ATTENTION

Ne retirez pas le dispositif de stockage USB et ne coupez pas l'alimentation lorsque le voyant d'accès au dispositif de stockage USB clignote.


Cela risquerait d'endommager le dispositif ou les données se trouvant sur ce dernier. De plus, toujours faire passer un support de stockage USB à l'état de retrait en toute sécurité (en suivant la procédure figurant à la section 6.1) avant de le retirer.

Selecting the Method of Automatically Setting the File Name

Select the method of automatically setting the file name by referring to page 6-2.

Setting the Type of File to Save to SETTING

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap FILE. A function menu appears for saving and loading data.
- 3. Tap Item Select. A menu appears for selecting the type of file to save or load.
- 4. Tap Setting. Setting is selected, and the menu returns to the previous level.
- 5. Tap Write. A file list appears.



Selecting the Storage Device

6. Tap Memory to select INT (internal memory) or EXT (USB storage device).



Entering the Name of a File to Save


If you do not set a file name, the file will automatically be assigned a name using a serial number or date.

For instructions on how to create directories and sort the file list, see page 6-5.

- 7. Tap the line displaying "NEW FILE" to move the cursor to it.
- 8. Tap File Name. A keyboard appears.
- **9.** Use the keyboard to input the new file name.

For instructions on how to enter text, see section 3.3, "Entering Numerical Values and Strings," in IM AQ6360-02EN.

10. Tap **Done**. The file name is confirmed, and the screen returns to the previous level.



6


Saving the File

- **11.** To overwrite an existing file, move the cursor to the name of the file you want to overwrite.
- 12. Tap Execute. The file is saved.

If you tap **Return**, the data will not be saved. The menu will return to the previous level.

13. When overwriting a file, a confirmation message appears. Tap YES.


To cancel saving, tap NO.



Loading Setting Data

Setting the Type of File to Load to SETTING


- **1.** Tap **Menu**. The Main Menu window appears.
- 2. Tap FILE. A function menu appears for saving and loading data.
- 3. Tap Item Select. A menu appears for selecting the type of file to save or load.
- 4. Tap Setting. Setting is selected, and the menu returns to the previous level.
- 5. Tap Read. A file list appears.



Selecting the File to Load


- **6.** Tap **Memory** to select INT (internal memory) or EXT (USB storage device). The file list of the selected device appears.
- 7. Tap a line in the file list to move the cursor to the file you want to load.

You can sort the files tapping **File Sort**. For the operating procedure, see page 6-5.



Loading the File

- Tap Execute. The file is loaded, and the instrument settings change.
 If you tap Return, the file will not be loaded. The menu will return to the previous level.
- 9. Tap Return. The file list disappears.



6

Explanation

You can save setting data to the internal memory or USB storage device and also load setting data saved previously and change the instrument settings.

Extension

Data is saved to a file with .STA extension.

File Name

You can save files by assigning their names automatically or with specific names. If you do not specify a file name, the following file name will be assigned automatically according to the AUTO FILE NAME setting.

When AUTO FILE NAME is set to NUM

File name: SXXXX.STA

XXXX is a serial number from 0000 to 9999.

When AUTO FILE NAME is set to DATE

File name: Syyyymmdd_hhmmss.STA

yyyymmdd:Year (Gregorian) month dayhhmmss:Hour (24 hours) minute second(Date/time when the file list was updated)

Note -

- The date/time used when file names are assigned based on the date through remote commands or program commands is the date/time when the file is created.
- When assigning a file name manually, use characters that are allowed by MS-DOS. The
 maximum number of characters that you can use for a file name is 56 (including the
 extension).
 The characters that you can use are shown below.

!#\$%&'()-

0123456789@

ABCDEFGHIJKLMNOPQRSTUVWXYZ^

abcdefghijklmnopqrstuvwxyz{}

File Size

The file size is about 74 KB.

Sorting Files

You can sort the file list in ascending order by file name, file type, date, or label.

6.5 Saving and Loading Analysis Results Data

Procedure

You can save analysis results, the time when the data was saved, and waveform data in ASCII format.



CAUTION

Do not remove the USB storage medium or turn the power OFF while the USB storage medium access indicator is blinking. This can damage the data on the medium or the device itself. Also, always place a USB storage medium in the removable state (following the procedure in section 6.1) before removing it.

French



ATTENTION

Ne retirez pas le dispositif de stockage USB et ne coupez pas l'alimentation lorsque le voyant d'accès au dispositif de stockage USB clignote.


Cela risquerait d'endommager le dispositif ou les données se trouvant sur ce dernier. De plus, toujours faire passer un support de stockage USB à l'état de retrait en toute sécurité (en suivant la procédure figurant à la section 6.1) avant de le retirer.

Selecting the Method of Automatically Setting the File Name

Select the method of automatically setting the file name by referring to page 6-2.

Setting the Type of File to Save to DATA

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap FILE. A function menu appears for saving and loading data.
- 3. Tap Item Select. A menu appears for selecting the type of file to save or load.
- 4. Tap Data. Data is selected, and the menu returns to the previous level.
- 5. Tap Write. A file list appears.




6

6-25

Selecting the Storage Device and Data Format

6. Tap Memory to select INT (internal memory) or EXT (USB storage device).



Selecting Data Items to Save

- 7. Tap Output Item Setting. A menu appears for selecting the data items to save.
- 8. Tap the data items to select ON (save) or OFF (not save).
- 9. Tap Return. The menu returns to the previous level.

≡ Menu	YOKOGAWA 🔶		2018 Feb 28 15:0	4 — M onu
Memory		WRITE : DATA TO FILE		Date & Time
INT EXT	FILE NAME> INT:\D0009.CSV			OFF ON
File Name	FILE NAME	DATE & TIME	LABEL/PROGRAM NAME	Label
	D0009.CSV	<new file=""></new>	LABEL/PROGRAM NAME	OFF ON
Output Item	DFB-LD	2018/02/28 14:58:20	<directory></directory>	Data Area
Setting	D0000.CSV	2018/02/28 15:03:50		OFF ON
P	D0001.CSV	2018/02/28 15:03:50		Condition
	D0002.CSV	2018/02/28 15:03:50		
	D0003.CSV	2018/02/28 15:03:51		OFF ON
Write Mode	D0004.CSV	2018/02/28 15:03:53		Trace Data
OVER ADD	D0005.CSV	2018/02/28 15:03:53		OFF ON
Make	D0006.CSV	2018/02/28 15:03:53		Output Window
Directory	D0007.CSV	2018/02/28 15:03:53		
	D0008.CSV	2018/02/28 15:03:54		OFF ON
File Sort				
FILE NAME				
Execute				
-				
Write				Output
Return				Return
	TOTAL: 11FILES		FREE: 577,380,352 BYTES	1
4				۶ <u>ـــــ</u>

Entering the Name of a File to Save

If you do not set a file name, the file will automatically be assigned a name using a serial number or date.

For instructions on how to create directories and sort the file list, see page 6-5.

- 10. Tap the line displaying "NEW FILE" to move the cursor to it.
- 11. Tap File Name. A keyboard appears.
- 12. Use the keyboard to input the new file name.

For instructions on how to enter text, see section 3.3, "Entering Numerical Values and Strings," in IM AQ6360-02EN.

13. Tap **Done**. The file name is confirmed, and the screen returns to the previous level.

DGAWA 🔶		2018 Feb	^{28 15:03} ≡ Menu
	WRITE : DATA TO FILE		Memory
ILE NAME> INT:\D0009.CSV	۶.		
FILE NAME	DATE & TIME	LABEL/PROGRAM NAME	File Name
D0009.CSV	<new file=""></new>		
DFB-LD	2018/02/28 14:58:20	<directory></directory>	Setting
D0000.CSV	2018/02/28 15:03:50		Security
D0001.CSV	2018/02/28 15:03:50		
D0002.CSV	2018/02/28 15:03:50		
D0003.CSV	2018/02/28 15:03:51		
D0004.CSV	2018/02/28 15:03:53		Write Mode
D0005.CSV	2018/02/28 15:03:53		
D0006.CSV	2018/02/28 15:03:53		Make
D0007.CSV	2018/02/28 15:03:53		Directory _
D0008.CSV	2018/02/28 15:03:54		
			File Sort
			FILE NAME
			Write
TOTAL: 11FILES		FREE: 577,380,352	Return
IUTAL: ITFILES		FREE: 577,380,357	ZBTIES

Setting the Save Method and Saving the File

- 14. Tap Write Mode to select OVER (overwrite) or ADD (add).
- **15.** To overwrite an existing file, move the cursor to the name of the file you want to overwrite.
- 16. Tap Execute. The file is saved.

If you tap **Return**, the data will not be saved. The menu will return to the previous level.

17. When overwriting a file, a confirmation message appears. Tap YES.

To cancel saving, tap NO.


Kogawa 🔶			2018 Feb 28 15:03	³ ≡ Menu
	WRITE : DATA TO FILE			Memory
FILE NAME> INT:\D0009.C	SV			INT E
FILE NAME	DATE & TIME	LABEL/PROG	RAM NAME	File Name
D0009.CSV	<new file=""></new>			
DFB-LD	2018/02/28 14:58:20	<direc< td=""><td>TORY></td><td>Output Iten Setting</td></direc<>	TORY>	Output Iten Setting
D0000.CSV	2018/02/28 15:03:50			Security
D0001.CSV	2018/02/28 15:03:50			
D0002.CSV	2018/02/28 15:03:50			
D0003.CSV	2018/02/28 15:03:51			
D0004.CSV	2018/02/28 15:03:53			Write Mode
D0005.CSV	2018/02/28 15:03:53			OVER A
D0006.CSV	2018/02/28 15:03:53			
D0007.CSV	2018/02/28 15:03:53			Directory
D0008.CSV	2018/02/28 15:03:54			
				File Sort
				FTI F NA
				Execute
				Write
				Return
TOTAL: 11 FILES		FREE:	577,380,352 BYTES	

6

Loading Analysis Data

Setting the Type of File to Load to DATA


- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap FILE. A function menu appears for saving and loading data.
- 3. Tap Item Select. A menu appears for selecting the type of file to save or load.
- 4. Tap Data. Data is selected, and the menu returns to the previous level.
- **5.** Tap **Read**. A file list appears.



Selecting the File to Load

- **6.** Tap **Memory** to select INT (internal memory) or EXT (USB storage device). The file list of the selected device appears.
- 7. Tap a line in the file list to move the cursor to the file you want to load.

You can sort the files tapping **File Sort**. For the operating procedure, see page 6-5.




Loading the File

7. Tap **Execute**. The file is loaded, and the data content is displayed.

If you tap **Return**, the file will not be loaded. The menu will return to the previous level.

- 8. Tap Done. The data content display closes.
- 9. Tap Return. The file list disappears.



Explanation

Extension

The file name extensions for saving data are shown below. CSV (ASCII format): .CSV

File Name

You can save files by assigning their names automatically or with specific names. If you do not specify a file name, the following file name will be assigned automatically according to the AUTO FILE NAME setting.

When AUTO FILE NAME is set to NUM

File name: DXXXX.CSV

XXXX is a serial number from 0000 to 9999.

When AUTO FILE NAME is set to DATE

File name: Dyyyymmdd_hhmmss.CSV

yyyymmdd:Year (Gregorian) month dayhhmmss:Hour (24 hours) minute second(Date/time when the file list was updated)

Note

- The date/time used when file names are assigned based on the date through remote commands or program commands is the date/time when the file is created.
- When assigning a file name manually, use characters that are allowed by MS-DOS. The maximum number of characters that you can use for a file name is 56 (including the extension).
 The characters that you can use are shown below.

!#\$%&'()-

0123456789@

ABCDEFGHIJKLMNOPQRSTUVWXYZ^

abcdefghijklmnopqrstuvwxyz{}

6

Data to Save

The following	data	can	be	saved.
---------------	------	-----	----	--------

le following data oan			
Saved Item	Default	t Value	Description
DATE&TIME	ON	Date and	d time
LABEL	ON	Label	
DATA AREA	ON	Data are	a value
CONDITION	ON	Measure	ement conditions
TRACE DATA	OFF	Trace da	ata
OUTPUT WINDOW	OFF	Output v	vindow data used by the program function

File Size

The file size varies depending on the data that you are saving. Check that there is sufficient free space at the storage destination before saving the data.

Sorting Files

You can sort the file list in ascending order by file name, file type, date, or label.

Overwriting

If a file with the same name exists at the save destination, you can select whether to overwrite the file or add data to the file. OVER: The file is overwritten.

ADD: Data is added to the existing data in the file.

Data Format

CSV

Data is saved in comma-separated (CSV) ASCII format.

Data Format

The CSV format is shown below.

	ionnat is shown below.	
60DAT2	Label	
TEST		
2018 Apr 07 16:42	Date/time of save	
<nf analysis=""></nf>		
TH[dB],20.00	-	
MODE DIFF[dB],3.00		
OFST(IN)[dB],0.00		
OFST(OUT)[dB],0.00		
ASE ALGO,AUTO-FIX		
FIT AREA,AUTO		Analysis results
MASK AREA,		header
FIT ALGO,LINEAR		and data
NO.,WAVELENGTH[nm],I	NPUT LVL[dBm],OUTPUT LVL[dBm],	
ASE LVL[dBm],RESOLN[n	m],GAIN[dB],NF[dB]	
1,1544.4983,-29.320,-2.26	0,-22.281,0.102,27.017,8.533	
2,1545.3041,-29.530,-2.42	0,-22.184,0.101,27.064,8.619	
CTRWL,1551.670000		
SPAN,20.000000		
REFL[dBm],-10.0	Measurement condition parameters	
LSCL,10.0		
RESLN,0.100		
AVG,1		
SMPL,2001		
HIGH 2		
NMSK,OFF		
1541.6700, -23.200	Waveform data for the sample point	ts (wavelength and level values)

6.6 Saving and Loading Program Data

Procedure

Programs created with the program function can be saved in binary format.



CAUTION

Do not remove the USB storage medium or turn the power OFF while the USB storage medium access indicator is blinking. This can damage the data on the medium or the device itself. Also, always place a USB storage medium in the removable state (following the procedure in section 6.1) before removing it.

French



ATTENTION

Ne retirez pas le dispositif de stockage USB et ne coupez pas l'alimentation lorsque le voyant d'accès au dispositif de stockage USB clignote. Cela risquerait d'endommager le dispositif ou les données se trouvant sur ce dernier. De plus, toujours faire passer un support de stockage USB à l'état de retrait en toute sécurité (en suivant la procédure figurant à la section 6.1) avant de le retirer.


Selecting the Method of Automatically Setting the File Name

Select the method of automatically setting the file name by referring to page 6-2.

Setting the Type of File to Save to PROGRAM

- 1. Tap **= Menu**. The Main Menu window appears.
- 2. Tap FILE. A function menu appears for saving and loading data.
- 3. Tap Item Select. A menu appears for selecting the type of file to save or load.
- 4. Tap Program. Program is selected, and the menu returns to the previous level.
- 5. Tap Write. A program list and a file list are displayed on the screen.

6.6 Saving and Loading Program Data



Selecting the Save Destination and Data Format

6. Tap Memory to select INT (internal memory) or EXT (USB storage device).



Selecting a Program Number to Save

 Tap a line in the program list to move the cursor to the program you want to save. You can move the cursor between the file list window (DOWN) and program list window (UP) by tapping Cursor.

окс	GAW	A 🔶		2018	Feb 28 15:09	≡ Menu	
		w	RITE : PROGRAM NO.03 TO I	FILE		Memory	
	_		PROGRAM LIST			INT EXT	
US	NO		PROGRAM NAME		EXEC NO.	File Name	
	01	Filter test				riic rearrie	 Selected program
•	02	Heatrun execute		,	2		
	03	Measure reference data		0	3	Cursor	number
	04				4	UP DOWN	
	05				5		1
	06				6		
	07				7		
	08				8		
Ļ	09				9		
			٧			Make	
FI	EN	AME> INT:\P0003.PGA				Directory	
		FILE NAME	DATE & TIME			File Sort	
	2003	PGA	<pre>ATE & TIME</pre>	LABEL/PROGRAM NA		1 11	
l I÷	FB-L		2018/02/28 14:58:20	<directory></directory>		FILE NAME	
		, PGA	2018/02/28 15:08:54			Execute	
		, PGA	2018/02/28 15:08:59				
		, PGA		Measure reference d	ata 📗		
[.]			,,			-	
						Write	
	TAL	5 FILES		FREE: 574,91	4,560 BYTES	Return	
						7	

6

Saving and Loading Data

Setting the Name of a File to Save

If you do not set a file name, the file will automatically be assigned a name using a serial number or date.

For instructions on how to create directories and sort the file list, see page 6-5.

8. Tap **Cursor** to move the cursor to the file list window (DOWN). An underscore is displayed at the program number selected in step 7.

You can also move the cursor to the file list window by tapping the window.

- 9. Tap the line displaying "NEW FILE" to move the cursor to it.
- 10. Tap File Name. A keyboard appears.
- 11. Use the keyboard to input the new file name.

For instructions on how to enter text, see section 3.3, "Entering Numerical Values and Strings," in IM AQ6360-02EN.

12. Tap **Done**. The file name is confirmed, and the screen returns to the previous level.

YOK	GA	WA 🔶			2018 Feb 28 15:10	≡ Menu	
			WRITE : PROGRAM NO.02	TO FILE		Memory	
			PROGRAM LIST			INT EVT	
US	NO		PROGRAM NAME		EXEC NO.	File Name	
	01	Filter test			1		Set the file name
	02	Heatrun execute			2		
	-	Measure reference data	•		3	Cursor	••
	03		a		4	UP DOWN	Moves the curso
	1					OP DOWN	
	05				5		
	06				6		
	07				7		
	08				8		
ŧ	09				9		
	_		•			Make Directory	
E	ILE I	NAME> INT:\P0003.PGA				Directory	 Makes a director
						File Sort	
	000	FILE NAME	DATE & TIME	LABEL/PROGF	CAM NAME		 Sorts the file list
	FB-			:20 <direct< th=""><th></th><th>FILE NAME</th><th></th></direct<>		FILE NAME	
			2018/02/28 14:58		UKY>		
		00.PGA		:54 Filter test			
		01.PGA		:59 Heatrun execut			
P	000	D2.PGA	2018/02/28 15:09	:01 Measure refere	ence data		
						Write	
1	DTAL	L: 5FILES		FREE:	574,914,560 BYTES	Return	
_						Ļ	

Saving the File

- **13.** To overwrite an existing file, move the cursor to the name of the file you want to overwrite.
- 14. Tap Execute. The file is saved.

If you tap **Return**, the data will not be saved. The menu will return to the previous level.


15. When overwriting a file, a confirmation message appears. Tap **YES**. To cancel saving, tap **NO**.

WRIT Filter test Heatrun execute Measure reference data	E : PROGRAM NO.02 TO F PROGRAM LIST PROGRAM NAME	TLE	EXEC NO.	Mern File N	<u>INT</u> EX
Heatrun execute			1	File N	_
Heatrun execute	PROGRAM NAME		1	File N	_
Heatrun execute			1	File N	ame
Heatrun execute					
			2		
			3	Curse	or
			4		JP DOW
			5		
			-		
			-		
	•		,	Mako	
]	Direc	tory
AME> INT:\P0003.PGA					
FILE NAME	DATE & TIME	LABEL/PROGRAM N	AME	File S	ort
3.PGA	<new file=""></new>			F	
LD	2018/02/28 14:58:20	<directory></directory>	·	Evoc	uto
0. PGA	2018/02/28 15:08:54	Filter test		Exec	ne
1.PGA	2018/02/28 15:08:59	Heatrun execute			
2.PGA	2018/02/28 15:09:01	Measure reference	data	-	
				Writ	
.: 5FILES		FREE: 574,9	14,560 BYTES	Retu	'n
	3. PGA LD 0. PGA 1. PGA 2. PGA	INT:\P0003.PGA FILE NAME DATE & TIME 3.PGA •KEW FILE> 0.0 PGA 2018/02/28 41:58:20 0.PGA 2018/02/28 15:08:54 1:9CA 2.PGA 2018/02/28 15:09:01 2018/02/28 15:09:01	INT:\P0003.PGA FILE NAME DATE & TIME LABEL/PROGRAM N 3.06A <new file=""> 0.101/02/28 11:58:20 <0.1018/02/28 11:58:20</new>	NT:\P0003.PGA FILE NAME DATE & TIME LABEL/PROGRAM NAME 3.PGA <ktw file=""> LD 2018/02/28 0.PGA 2018/02/28 15:08:54 Filter test 1.PGA 2018/02/28 15:09:59 Heatrun execute 2.PGA 2018/02/28 15:09:01 Measure reference data</ktw>	INT:\P0003.PGA Make FILE NAME DATE & TIME LABEL/PROGRAM NAME SI PGA CMSE & TIME LABEL/PROGRAM NAME SI PGA 2018/02/28 15:08:54 Filter test L. PGA 2018/02/28 15:08:59 Heatrun execute 2. PGA 2018/02/28 15:09:01 Measure reference data

Loading a Program File

Setting the Type of File to Load to PROGRAM

- 1. Tap **= Menu**. The Main Menu window appears.
- 2. Tap FILE. A function menu appears for saving and loading data.
- 3. Tap Item Select. A menu appears for selecting the type of file to save or load.
- 4. Tap Program. Program is selected, and the menu returns to the previous level.
- 5. Tap Read. A file list and a program list appear.



Selecting the File to Load

- **6.** Tap **Memory** to select INT (internal memory) or EXT (USB storage device). The file list of the selected device appears.
- 7. Tap **Cursor** to move the cursor to the file list window (UP). You can also move the cursor to the file list window by tapping the window.
- **8.** Tap a line in the file list to move the cursor to the file you want to load. You can sort the files tapping **File Sort**. For the operating procedure, see page 6-5.

KOGAWA	*		2018	Feb 28 15:10	= Monu	
	R	EAD : FILE TO PROGRAM NO.	.02		Memory	
FILE NA	ME> INT:\P0001.PGA				INT EXT	
	FILE NAME	DATE & TIME	LABEL/PROGRAM NAM	1E		
DFB-LD		2018/02/28 14:58:20	<directory></directory>		1 1	
P0000.	PGA	2018/02/28 15:08:54	Filter test	11	Cursor	
P0001.		2018/02/28 15:08:59			UP DOWN	
P0002.	PGA	2018/02/28 15:09:01	Measure reference da	ata		
TOTAL:	4FILES	•	FREE: 573,464	,576 BYTES		
		PROGRAM LIST				
JS NO		PROGRAM NAME		EXEC NO.	File Sort	
* 01 F	ilter test			1		 Sorts fil
* <u>02</u> н	eatrun execute			2	FILE NAME	
* 03 м	easure reference data			3	Execute	
04				4		
05				5		
06				6	-	
07				7	Read	
08				8		
09				9	Return	


Selecting the Program Number to Load To

- **9.** Tap **Cursor** to move the cursor to the program list window (DOWN). You can also move the cursor to the program list window by tapping the window.
- **10.** Tap a line in the program list to move the cursor to the load destination program number.

	VA 🔶		2018 Feb	28 15:1	י≡ י	Menu
	RE	AD : FILE TO PROGRAM NO	.05		Merno	гу
FILE N	IAME> INT:\P0001.PGA					<u>int</u> e
	FILE NAME	DATE & TIME	LABEL/PROGRAM NAME			
DFB-L	_D	2018/02/28 14:58:20	<directory></directory>			
P0000). PGA	2018/02/28 15:08:54	Filter test		Curso	r
P0001	L. PGA	2018/02/28 15:08:59	Heatrun execute		U 0	IP DO
P0002	2.PGA	2018/02/28 15:09:01	Measure reference data			
TOTAL	: 4FILES					
TOTAL	: 4FILES	•	FREE: 573,464,57	6 BYTES		
	: 4FILES	PROGRAM LIST	FREE: 573,464,57			
	: 4FILES		FREE: 573,464,57	EXEC	File Sc	ort
S NO	Filter test	PROGRAM LIST	FREE: 573,464,57		File Sc	
S NO * 01	· · · · · · · · · · · · · · · · · · ·	PROGRAM LIST	FREE: 573,464,57	EXEC NO.	FIL	E N/
S NO * 01 * 02	Filter test	PROGRAM LIST	FREE: 573,464,57	EXEC NO.		E NA
S NO * 01 * 02	Filter test Heatrun execute	PROGRAM LIST	FREE: 573,464,57	EXEC NO. 1 2 3 4	FIL	E NA
S NO * 01 * 02 * 03 04 05	Filter test Heatrun execute	PROGRAM LIST	FREE: 573,464,57	EXEC NO. 1 2 3	FIL	E NA
S NO * 01 * 02 * 03 04	Filter test Heatrun execute	PROGRAM LIST	FREE: 573,464,57	EXEC NO. 1 2 3 4	FIL Execu	E NA
S NO * 01 * 02 * 03 04 05	Filter test Heatrun execute	PROGRAM LIST	FREE: 573,464,57	EXEC NO. 1 2 3 4 5	FIL	E NA
S NO * 01 * 02 * 03 04 05 06	Filter test Heatrun execute	PROGRAM LIST	FREE: 573,464,57	EXEC NO. 1 2 3 4 5 6	FIL Execu	E NA

Loading the File

- 11. Tap Execute. The file is loaded and registered in the specified program number. If you tap Return, the file will not be loaded. The menu will return to the previous level.
- 12. Tap Return. The file list and program list disappear.



Explanation

Extension

The file name extensions for saving data are shown below. BIN (binary format): .PGA

File Name

You can save files by assigning their names automatically or with specific names. If you do not specify a file name, the following file name will be assigned automatically according to the AUTO FILE NAME setting.

When AUTO FILE NAME is set to NUM

File name: PXXXX.PGA

XXXX is a serial number from 0000 to 9999.

When AUTO FILE NAME is set to DATE

File name: Pyyyymmdd_hhmmss.PGA

yyyymmdd:	Year (Gregorian) month day		
hhmmss:	Hour (24 hours) minute second		
(Date/time when the file list was updated)			

Note _

- The date/time used when file names are assigned based on the date through remote commands or program commands is the date/time when the file is created.
- When assigning a file name manually, use characters that are allowed by MS-DOS. The maximum number of characters that you can use for a file name is 56 (including the extension).
 The characters that you can use are shown below.
 !#\$%&'()-

0123456789@ ABCDEFGHIJKLMNOPQRSTUVWXYZ^ abcdefghijklmnopqrstuvwxyz{}

File Size

The file size is about 13 KB.

Data Format

Data is saved in binary format.

6.7 Saving Screen Capture Data

Procedure

You can capture the screen and save it in a file.



CAUTION

Do not remove the USB storage medium or turn the power OFF while the USB storage medium access indicator is blinking. This can damage the data on the medium or the device itself. Also, always place a USB storage medium in the removable state (following the procedure in section 6.1) before removing it.

French



ATTENTION


Ne retirez pas le dispositif de stockage USB et ne coupez pas l'alimentation lorsque le voyant d'accès au dispositif de stockage USB clignote. Cela risquerait d'endommager le dispositif ou les données se trouvant sur ce dernier. De plus, toujours faire passer un support de stockage USB à l'état de retrait en toute sécurité (en suivant la procédure figurant à la section 6.1) avant de le retirer.

Selecting the Method of Automatically Setting the File Name

Select the method of automatically setting the file name by referring to page 6-2.

Setting the Type of File to Save to GRAPHIC

- 1. Tap **= Menu**. The Main Menu window appears.
- 2. Tap FILE. A function menu appears for saving and loading data.
- 3. Tap Item Select. A menu appears for selecting the type of file to save or load.
- 4. Tap Graphics. Graphics is selected, and the menu returns to the previous level.
- **5.** Tap **Write**. A file list appears.




Selecting the Save Destination and Data Format

6. Tap Memory to select INT (internal memory) or EXT (USB storage device).



Selecting the Color

- 7. Tap Mode. A menu appears for selecting the color.
- **8.** Tap **Black & White** (black and white), **Color**, or **Preset Color** (only waveform markers in color).



Selecting the File Type

9. Tap File Type to select BMP or TIFF.


Kogawa 🔶		201	8 Feb 28 15:12	² ≡ Menu
	WRITE : GRAPHICS TO FILE			Memory
ILE NAME> INT:\G0032.BM	,			
FILE NAME	DATE & TIME	LABEL/PROGRAM N	AME 🔺	File Name
G0032.BMP	<new file=""></new>			
DFB-LD	2018/02/28 14:58:20	<directory></directory>		Mode
G0000. BMP	2018/02/28 14:51:27			R
G0001.BMP	2018/02/28 14:54:17			File Type
G0002.BMP	2018/02/28 14:54:23			
G0003.BMP	2018/02/28 14:55:20			BMP T
G0004.BMP	2018/02/28 14:55:24			
G0005.BMP	2018/02/28 14:55:34			
G0006.BMP	2018/02/28 14:58:20			Make
G0007.BMP	2018/02/28 14:59:57			Directory
G0008.BMP	2018/02/28 15:00:14			
G0009. BMP	2018/02/28 15:00:28			File Sort
G0010.BMP	2018/02/28 15:00:43			FILE NA
G0011.BMP	2018/02/28 15:00:58			Execute
G0012.BMP	2018/02/28 15:01:44			
G0013.BMP	2018/02/28 15:02:16			
G0014.BMP	2018/02/28 15:02:26			
G0015.BMP	2018/02/28 15:02:46			Write
G0016.BMP	2018/02/28 15:02:52			
G0017.BMP	2018/02/28 15:03:17		T	Return
TOTAL: 34 FILES		FREE: 571,5	31,264 BYTES	Return

Setting the Name of a File to Save

If you do not set a file name, the file will automatically be assigned a name using a serial number or date.

For instructions on how to create directories and sort the file list, see page 6-5.

- 10. Tap the line displaying "NEW FILE" to move the cursor to it.
- 11. Tap File Name. A keyboard appears.
- 12. Use the keyboard to input the new file name.
 - For instructions on how to enter text, see section 3.3, "Entering Numerical Values and Strings," in IM AQ6360-02EN.
- **13.** Tap **Done**. The file name is confirmed, and the screen returns to the previous level.




Saving the File

- **14.** To overwrite an existing file, move the cursor to the name of the file you want to overwrite.
- 15. Tap Execute. The file is saved.

If you tap **Return**, the data will not be saved. The menu will return to the previous level.

 When overwriting a file, a confirmation message appears. Tap YES. To cancel saving, tap NO.



Explanation

Extension

File Name

You can save files by assigning their names automatically or with specific names. If you do not specify a file name, the following file name will be assigned automatically according to the AUTO FILE NAME setting.

When AUTO FILE NAME is set to NUM

File name: GXXXX.BMP (or TIF)

XXXX is a serial number from 0000 to 9999.

When AUTO FILE NAME is set to DATE

File name: Gyyyymmdd_hhmmss.BMP (or .TIF)

yyyymmdd: Year (Gregorian) month day

hhmmss: Hour (24 hours) minute second

(Date/time when the file list was updated)

Note.

- The date/time used when file names are assigned based on the date through remote commands or program commands is the date/time when the file is created.
- When assigning a file name manually, use characters that are allowed by MS-DOS. The maximum number of characters that you can use for a file name is 56 (including the extension).
 The characters that you can use are shown below.

!#\$%&'()-0123456789@ ABCDEFGHIJKLMNOPQRSTUVWXYZ^

abcdefghijklmnopqrstuvwxyz{}[—]

saved in black and white.

Color

Black & White: A black-and-white screen capture is produced. Color: A color screen capture is produced. Preset Color: Only the waveforms and markers are saved in color. All other items are

Data Format

You can save the data in bitmap format (BMP) or TIFF format.

File Size

The file size varies depending the data format and color setting. BMP (color): Varies depending on the display color. BMP (black and white): Approx. 52 KB TIFF (color): Approx. 412 KB TIFF (black and white): Approx. 52 KB 6

6.8 File Operations

Procedure

You can perform file operations such as renaming and copying files.



CAUTION

Do not remove the USB storage medium or turn the power OFF while the USB storage medium access indicator is blinking. This can damage the data on the medium or the device itself. Also, always place a USB storage medium in the removable state (following the procedure in section 6.1) before removing it.

French



ATTENTION

Ne retirez pas le dispositif de stockage USB et ne coupez pas l'alimentation lorsque le voyant d'accès au dispositif de stockage USB clignote. Cela risquerait d'endommager le dispositif ou les données se trouvant sur ce dernier. De plus, toujours faire passer un support de stockage USB à l'état de retrait en toute sécurité (en suivant la procédure figurant à la section 6.1) avant de le retirer.

Selecting the Storage Device of the File

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap FILE. A function menu appears for saving and loading data.
- 2. Tap File Operation. A file operation menu appears.
- **3.** Tap **Memory** to select INT (internal memory) or EXT (USB storage device). The file list of the selected device appears.

≡ Menu	YOKOGAWA 🔶		2018 Feb 28 15:1	³ = Monu
rite		FILE OPERATION		Memory
ad	FILE NAME> INT:\DFB-LD			
	FILE NAME	DATE & TIME	LABEL/PROGRAM NAME	
J	DFB-LD	2018/02/28 14:58:20	<directory></directory>	
ern Select	A0000.CSV	2018/02/28 15:02:00		Сору
GRAPHICS	A0001.CSV	2018/02/28 15:02:01		
rto	A0002.CSV	2018/02/28 15:02:01		Rename
e Name	A0003.CSV	2018/02/28 15:02:01		Kename
NUM DATE	A0009.CSV	2018/02/28 15:02:06		
	A0010.CSV	2018/02/28 15:02:07		Make Directory
	D0000.CSV	2018/02/28 15:03:50		Directory
ove	D0001.CSV	2018/02/28 15:03:50		
torage	D0002.CSV	2018/02/28 15:03:50		
	D0003.CSV	2018/02/28 15:03:51		
ion	D0004.CSV	2018/02/28 15:03:53		File Sort
	D0005.CSV	2018/02/28 15:03:53		FILE NAME
	D0006.CSV	2018/02/28 15:03:53		File
	D0007.CSV	2018/02/28 15:03:53		Select
	D0008.CSV	2018/02/28 15:03:54		
	D0009.CSV	2018/02/28 15:05:21		
-	G0000. BMP	2018/02/28 14:51:27		File
	G0001. BMP	2018/02/28 14:54:17		Operation
	G0002. BMP	2018/02/28 14:54:23	•	Exit
1	TOTAL: 64 FILES		FREE: 571,248,640 BYTES	EAIL
				- L

Selecting a File or Directory

4. Tap a line in the file list to move the cursor to a file or directory.

To move into a directory, double-tap the directory.


Double-tap ".." to move up one directory.

— Moves to the parent directory



Selecting All Files

- 5. Tap File Select. A file selection menu appears.
- Tap All Select. All files are selected.
 Tapping All Clear clears the file selection.
- 7. Tap Return. The menu returns to the previous level.



Deleting Files and Directories

- 8. Select files or directories by following step 4 or steps 5 to 7.
- 9. Tap Delete. A menu appears for confirming the deletion.
- 10. Tap YES. The selected files and directories will be deleted. Tap NO if you do not want to delete them. The menu returns to the previous level.

okogawa 🔶		2018 Fe
	FILE OPERATION	
FILE NAME> INT:\DFB-LD\W	0005. WVA	
FILE NAME	DATE & TIME	LABEL/PROGRAM NAME
 Result data	2018/02/28 15:14:24	<directory></directory>
G0000, BMP	2018/02/28 14:51:27	
G0001. BMP	2018/02/28 14:54:17	
G0002, BMP	2018/02/28 14:54:23	
G0003, BMP	2018/02/28 14:55:20	
G0004.BMP	2018/02/28 14:55:24	
G0005. BMP	2018/02/28 14:55:34	
G0006. BMP	2018/02/28 14:58:20	
G0007.BMP	2018/02/28 15:14:38	
W0000. WVA	2018/02/28 14:56:07	
W0001.WVA	2018/02/28 14:56:31	
w0002.wvA	2018/02/28 14:56:45	
W0003.WVA	2018/02/28 14:57:01	
W0004.WVA	2018/02/28 14:57:19	
W0005.WVA	2018/02/28 14:57:28	
W0006.WVA	2018/0	DELETE
W0007.WVA	2018/0 Are	you sure ?
TOTAL: 18FILES		FREE: 570,281,9

6

Copying Files and Directories

- 8. Select files or directories by following step 4 or steps 5 to 7.
- 9. Tap Copy.
- 10. Display the copy destination file list by following steps 3 and 4.

If the copy destination storage device is different from the copy source storage device, tap **Memory** to select the copy destination storage device.

To paste with the same name, proceed to step 11.

To paste with a different name, proceed to step 12.

- **11.** To paste with the same name, tap **Execute**. The selected files or directories are pasted.
- 12. To paste with a different name, tap File Name. A keyboard appears.
- 13. Use the keyboard to input the new file name.

For instructions on how to enter text, see section 3.3, "Entering Numerical Values and Strings," in IM AQ6360-02EN.

- 14. Tap Done. The file name is confirmed, and the keyboard disappears.
- **15.** Tap **Execute**. The file or directory is pasted with the specified name. Tap **Cancel** if you do not want to change the file name or directory name.

Note.


- When pasting in the same directory as the copy source, change the name before pasting.
- While pasting is in progress, you cannot cancel the operation.

Name of the file or directory to be pasted

	N	ame of tl	ne copied	file or directory				
≡ Menu		YOKOGAWA 🔶				2018 Feb 28 15:1	5 🔳 Menu]
Memory				FILE OPERATION			Memory	
INT EXT	L	COPY FROM>	INT:\DFB-LD\W00	04.WVA			INTEXT	
Delete		COPY TO >	INT:\W0004.WVA				File Name	
Delece			FILE NAME	DATE & TIME	LABEL/PROGR	AM NAME		Paste with a
		DFB-LD		2018/02/28 15:15:13	<direct< td=""><td>ORY></td><td></td><td></td></direct<>	ORY>		
Сору		A0000.C5V		2018/02/28 15:02:00				different name.
		A0001.CSV		2018/02/28 15:02:01				
		A0002.CSV		2018/02/28 15:02:01				
		A0003.CSV		2018/02/28 15:02:01				
		A0009.CSV		2018/02/28 15:02:06				
Make Directory		A0010.CSV		2018/02/28 15:02:07				
Directory		D0000.CSV		2018/02/28 15:03:50				
	➡	D0001.CSV		2018/02/28 15:03:50				
		D0002.CSV		2018/02/28 15:03:50				
		D0003.CSV		2018/02/28 15:03:51				
File Sort		D0004.CSV		2018/02/28 15:03:53				
FILE NAME		D0005.CSV		2018/02/28 15:03:53				
		D0006.CSV		2018/02/28 15:03:53			Execute	
File Select		D0007.CSV		2018/02/28 15:03:53			Execute	Executes pasting
		D0008.C5V		2018/02/28 15:03:54			L	
		D0009.C5V		2018/02/28 15:05:21				Ĩ
		G0000, BMP		2018/02/28 14:51:27			Copy	
File Operation		G0001. BMP		2018/02/28 14:54:17				
		G0002. BMP		2018/02/28 14:54:23				
Exit			5 FILES	2020, 02, 20 14: 54:25	FREE: 5	69,798,656 BYTES	Cancel	
			011000			05,150,05001125	'L	
							,	1

Renaming a File or Directory

- 5. Select the file or directory you want to rename by following step 4.
- 6. Tap Rename.
- 7. Tap File Name. A keyboard appears.
- Use the keyboard to input the new file name.
 For instructions on how to enter text, see section 3.3, "Entering Numerical Values and Strings," in IM AQ6360-02EN.
- **9.** Tap **Done**. The file name or directory name is confirmed, and the screen returns to the previous level.
- **10.** Tap **Execute**. The file or directory is renamed. Tap **Cancel** if you do not want to change the file name or directory name.




Making a Directory

- **5.** Display the file list of the directory you want to make a directory in by following steps 3 and 4.
- 6. Tap Make Directory.
- 7. Tap Directory Name. A keyboard appears.
- **8.** Use the keyboard to input the new file name.

For instructions on how to enter text, see section 3.3, "Entering Numerical Values and Strings," in IM AQ6360-02EN.

- **9.** Tap **Done**. The directory name is confirmed, and the screen returns to the previous level.
- **10.** Tap **Execute**. A new directory is created. Tap **Cancel** if you do not want to create the directory.



Sorting Files

- 5. Display the file list by following steps 3 and 4.
- 6. Tap File Sort. A menu appears for selecting the item to sort by.
- **7.** Tap the item you want to sort by. The files are sorted in ascending order by the selected item.

	1	
🗮 Menu		= Manu
Memory		File Name
INT EXT		
Delete		File Type
Сору		File Date
Rename		File Label
Make		
Directory		
	\rightarrow	
File Sort		
FILE NAME		
Select		
Select		
LP		
		File Sort
File Operation		ا کترکی ا
Exit		Return
ι		<u>ل</u>

Explanation

File Names and Directory Names

For file and directory names, use characters that are allowed by MS-DOS. The maximum number of characters that you can use for a file name is 56 (including the extension). The characters that you can use are shown below.

!#\$%&'()-0123456789@

ABCDEFGHIJKLMNOPQRSTUVWXYZ^

abcdefghijklmnopqrstuvwxyz{}

Sorting Files

You can sort the file list in ascending order by file name, file type, date, or label.


7.1 Screen Display

Procedure

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SYSTEM.
- 3. Tap More to display the More 3/4 function menu.

Setting the Number of Decimal Places to Display for Level Data

- Tap Level Display Digit. A menu appears for setting the number of decimal places.
- 5. Tap the number of decimal places you want to use.
 - 1DIGIT The number of decimal places displayed for level data is set to 1.
 - 2DIGIT The number of decimal places displayed for level data is set to 2.
 - 3DIGIT The number of decimal places displayed for level data is set to 3.



Enabling the Transparent Display

4. Continuing from step 3, tap **Window Transparent OFF ON**. Each time you tap, the value switches between ON and OFF. When set to ON, the parameter input window and overview display window are displayed transparently.

Changing the Display Colors

4. Continuing from step 3, tap **Color Mode**. Each time you tap, the value switches between COLOR and B&W (black and white).

7.2 Registering User Keys

Procedure

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SYSTEM. A function menu for the system appears.
- **3.** Tap **User Key Define**. A registration screen (USER KEY DEFINE MODE) appears.
- **4.** Display the Main Menu window, and tap the function containing the key you want to register.

If necessary, tap More to change the function menu pages.


- **5.** Tap the key you want to register. The name of the key appears in the key registration display area of the registration screen.
- 6. Display the Main Menu window, and tap USER. User keys appear.

If necessary, tap More to change the user key pages.

7. Tap a user key.

The key selected in step 5 will be registered. At the same time, the key registration display area is cleared. If you tap a key that is already registered, it will be overwritten.

- **8.** To clear a registered key, tap the key with the key registration display area in a blank state.
- **9.** To close the registration screen (USER KEY DEFINE MODE), tap **X** or **UNDO**/ **LOCAL** in the Main Menu window.



Note _

- As a general rule, only the first level function menus can be registered. (Lower level function menus cannot be registered.) Keys that cannot be registered do not appear in the key registration display area.
- Registered user keys execute actions like other normal keys on the function menus.


Explanation

Up to 24 function menu keys can be registered as user keys. To display the user keys, display the Main Menu window, and tap **USER**. By registering frequently used keys as user keys, you can access them simply by tapping **USER**.

Procedure

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SYSTEM. A function menu for the system appears.
- 3. Tap More to display the More 4/4 function menu.
- 4. Tap Parameter Initialize. An initialization item setting menu appears.
- 5. Select the initialization type according to the items you want to initialize.
- 6. Tap Execute. Initialization is executed.

To cancel, tap Cancel.



Explanation

You can restore all settings to their factory defaults.

The following four types of initialization are available depending on the items to be initialized.

· Parameter Clear

The parameter setting value of each function is initialized.

The waveform data of traces A to G is also initialized.

- Use this to initialize the instrument to the default condition.
- Parameter & Data Clear

Parameter values and program data are initialized.

Cal Data Clear

Wavelength calibration value and resolution calibration value are initialized.

All Clear

All parameter values, data, and wavelength calibration value are initialized.

The default values for each setting are shown below.

SWEEP

Function	Default Value	Maximum Value	Minimum Value
Sweep Marker L1-L2 OFF/ON	OFF	-	-
Sweep Interval *****s	MINIMUM=0	99999	MINIMUM=0

CENTER

Function	Default Value	Maximum Value	Minimum Value
Center Wavelength ****.***nm	1425.000	1650.000	1200.000
Center Frequency ***.****THz	215.7597	250.0000	181.5000
Start Wavelength ****.***nm	1200.000	1650.000	975.000
Start Frequency ***.****THz	181.6924	250.0000	147.2500
Stop Wavelength ****.***nm	1650.000	1875.000	1200.000
Stop Frequency ***.****THz	249.8270	284.2500	181.5000
Auto Center OFF/ON	OFF	-	-

SPAN

Function	Default Value	Maximum Value	Minimum Value
Span Wavelength ****.*nm	450.0	450.0	0 / 0.1
Span Frequency ***.**THz	68.13	68.50	0/0.01
Start Wavelength ****.***nm	1200.000	1650.000	975.000
Start Frequency ***.***THz	181.6924	250.0000	147.2500
Stop Wavelength ****.***nm	1650.000	1875.000	1200.000
Stop Frequency ***.***THz	249.8270	284.2500	181.5000
0nm Sweep Time**s	MINIMUM	50	MINIMUM

LEVEL

	Function	Default Value	Maximum Value	Minimum Value
Reference Level	Log	-10.0	30.0	-90.0
Reference Level	Linear	100µW	1000mW	1.00pW
Log Scale **.*dB/D		10.0 , ON	10.0	0.1
Linear Scale		OFF	-	-
Linear Base Level *	**.*mW	0.0	REF×0.9	0.0
Auto Ref Level OFF	F/ON	OFF	-	-
Level Unit dBm / d	IBm/nm / dBm/THz	dBm	-	-
Sub Log **.*dB/D		5.0 , ON	10.0	0.1
Sub Linear *.***/D		0.125 , OFF	1.250	0.005
Sub Scale **.*dB/kr	n	5.0 , OFF	10.0	0.1
Sub Scale **.*%/D		10.0 , OFF	125.0	0.5
Offset Level **.*dB		0.0	99.9	-99.9
Scale Minimum *.**		0.00	1.25	0.00
Offset Level **.*dB/	km	0.0	99.9	-99.9
Scale Minimum **.*	%	0.0	100.0	0.0
Length **.***km		1.000	99.999	0.001
Auto Sub Scale OFF/ON		OFF	-	-
Y Scale Division **		10	10	8
Ref Level Position *	**DIV	8	10	0
Sub Ref level Positi	ion **DIV	5	10	0

SETUP

	Function	Default Value	Maximum Value	Minimum Value
Resolution *.*nm	1	1	2	0.1
	NORM/HOLD	OFF	-	-
	NORM/AUTO	ON	-	-
Consitivity	NORMAL	OFF	-	-
Sensitivity	MID	OFF	-	-
	HIGH1	OFF	-	-
	HIGH2	OFF	-	-
Average Times ***		1	999	1
Sampling Points AUTO		ON	-	-
Sampling Points	****	<sampling auto="" point=""> calculated value, OFF</sampling>	50001	101
Sampling Interval *.****nm		<pre><sampling auto="" point=""> calculated value, OFF</sampling></pre>	SPAN/100	0.001
Medium AIR/VACUUM		VAC	-	-
Sweep Speed 1x/2x		1x	-	-
Horizontal Scale nm/THz		nm	-	-
Smoothing OFF/ON		OFF	-	-
Fiber Connector	NORM/ANGLED	NORM	-	-

ZOOM

Function	Default Value	Maximum Value	Minimum Value	
	Measurement center			
Zoom Center Wavelength ****.***nm	wavelength of the last	1650.000	1200.000	
	measurement or loaded trace			
	Measurement center			
Zoom Center Frequency ***.***THz	frequency of the last	250.0000	181.5000	
	measurement or loaded trace			
Zoom Span Wavelength ****.*nm	Measurement span of the last	450.0	0.1	
	measurement or loaded trace	450.0	0.1	
Zoom Span Frequency ***.****THz	Measurement span of the last	68.50	0.01	
	measurement or loaded trace	00.50	0.01	
	Measurement start			
Zoom Start Wavelength ****.***nm	wavelength of the last	1649.950	975.000	
	measurement or loaded trace			
	Measurement start frequency			
Zoom Start Frequency ***.****THz	of the last measurement or	249.9950	147.2500	
	loaded trace			
	Measurement stop			
Zoom Stop Wavelength ****.***nm	wavelength of the last	1875.000	1200.050	
	measurement or loaded trace			
	Measurement stop frequency			
Zoom Stop Frequency ***.***THz	of the last measurement or	284.2500	181.5050	
	loaded trace			
Overview Display OFF/L/R	R	-	-	
Overview Size LARGE/SMALL	LARGE	-	-	

DISPLAY

	Function		Default Value	Maximum Value	Minimum Value
Normal Display		ON	-	-	
Split Display			OFF	-	-
	Trace A UF	P/LOW	UP	-	-
	Trace B UF	P/LOW	UP	-	-
	Trace C UI	P/LOW	LOW	-	-
	Trace D U	P/LOW	UP	-	-
	Trace E UP/LOW		UP	-	-
Split Display	Trace F UP/LOW		LOW	-	-
	Trace G UI	P/LOW	LOW	-	-
		Upper Hold OFF/ON	OFF	-	-
	Hold	Lower Hold OFF/ON	OFF	-	-
Label		// AQ6360 OPTICAL SPCTRUM ANALYZER //	-	-	
Noise Mask ***dB		OFF	0	OFF(-999)	
Mask Line VE	RT / HRZN		HRZN	-	-

TRACE

	Funct	ion	Default Value	Maximum Value	Minimum Value
Active Trace A/B/C/D/E/F/G			A	-	-
View @ DISP/BLANK		Trace A=DISP, Trace B/C/D/E/F/G =BLANK	-	-	
Fix @			Trace B/C/D/E/F/G	-	-
Hold @	Max Hold		No Trace, Trace A, C, E, G	-	-
-	Min Hold		No Trace, Trace B, D, F	-	-
Roll Average	*		No Trace, 2	100	2
Calculate C	C Log Math @	0000	C=A-B(LOG), ON	-	-
@@@@	Linear Math	0000	C=A+B(LIN), OFF	-	-
Calculate F @@@@	LOG MATH @@@@		F=C-D(LOG), ON	-	-
	Linear Math	0000	F=C+D(LIN), OFF	-	-
	Power/NBV	V @@@@	F=Pwr/NBW A, OFF	-	-
	Log Math @@@@		G=C-F(LOG), ON	-	-
	Linear Math	0000	G=C+F(LIN), OFF	-	-
	Normalize (0000	G=NORMA, OFF	-	-
			G=CRVFITA, OFF	-	-
		Threshold **dB	20	99	0
Calculate (Curve Fit @@@@@	Operation Area ALL / INSIDE L1-L2 / OUTSIDE L1-L2	ALL	-	-
		Fitting Algorithm	GAUSS	-	-
			G=PKCVFITA, OFF	-	-
		Threshold **dB	2020	9999	0
	Peak Curve Fit @@@@@	Operation Area ALL / INSIDE L1-L2 / OUTSIDE L1-L2	ALL	-	-
		Fitting Algorithm	GAUSS	-	-
	Source Tra	ce @	А	-	-
Trace Copy	Destination	Trace @	В	-	-

MARKER

	Function	Default Value	Maximum Value	Minimum Value
Marker Active OFF/ON		OFF	-	-
Set Marker	Set	1	1024	1
Line Marker 1 OFF/	ON	OFF	WL=1650.000 FREQ=249.82705	WL=1200.000 FREQ=181.69240
Line Marker 2 OFF/	ON	OFF	WL=1650.000 FREQ=249.82705	WL=1200.000 FREQ=181.69240
Line Marker 3 OFF/	ON	OFF	LOG=30.0 LINEAR=1000mW	LOG=-90.0 LINEAR=1.00pW
Line Marker 4 OFF/ON		OFF	LOG=30.0 LINEAR=1000mW	LOG=-90.0 LINEAR=1.00pW
Marker Display OFF	SET/SPACING	Offset	-	-
Marker Auto Update	OFF/ON	OFF	-	-
Marker Unit nm/THz	2	nm	-	-
Search / Ana Marke	r L1-L2 OFF/ON	OFF	-	-
Search / Ana Zoom	Area OFF/ON	ON	-	-
Sweep Marker L1-L	2 OFF/ON	OFF	-	-
	Adv. Marker Active ON/OFF	OFF	-	-
	Marker 1 Select	OFF	-	-
Advanced Marker	Marker 2 Select	OFF	-	-
	Marker 3 Select	OFF	-	-
	Marker 4 Select	OFF	-	-
	Bandwidth	0.1nm		

PEAK SEARCH

Fun	ction	Default Value	Maximum Value	Minimum Value
Peak Search		ON	-	-
Bottom Search		OFF	-	-
Set Marker	Set	1	1024	1
Auto Search OFF/ON		OFF	-	-
Mode Diff **.**dB	Mode Diff **.**dB		50.00	0.01
Search / Ana Marker L1-I	_2 OFF/ON	OFF	-	-
Search / Ana Zoom Area	OFF/ON	ON	-	-
Search Mode SINGL/MULTI		SINGL	-	-
Multi Coorob Cotting	Threshold **.**dB	50.00	99.99	0.01
Multi Search Setting	Sort by WL/LVL	WL	-	-

ANALYSIS

		Function	Default Value	Maximum Value	Minimum Value
		THRESH LEVEL *.**dB	3.00	50.00	0.01
	THRESH	К	1.00	10.00	1.00
		MODE FIT OFF/ON	OFF	-	-
0		THRESH LEVEL1 *.**dB	3.00	50.00	0.01
000	ENVELOPE	THRESH LEVEL2 *.**dB	13.00	50.00	0.01
0		К	1.00	10.00	1.00
Width (RMS	THRESH LEVEL *.**dB	20.00	50.00	0.01
, Vi	RIVIO	К	2.00	10.00	1.00
Spec	PEAK RMS	THRESH LEVEL *.**dB	20.00	50.00	0.01
0	FEAR RIVIS	К	2.00	10.00	1.00
		THRESH LEVEL *.**dB	3.00	50.00	0.01
	NOTCH	К	1.00	10.00	1.00
		TYPE PAEK/BOTTOM	BOTTOM	-	-

		Function	Default Value	Maximum Value	Minimum Value
		ALGO ENVELOPE/THRESH/RMS/PK-RMS	THRESH	-	-
	臣	THRESH **.**dB	20.00	50.00	0.01
	ND	THRESH2 **.**dB	20.00	50.00	0.01
	-XdB WIDTH	K	1.00	10.00	1.00
	×-	MODE FIT OFF/ON	OFF	-	-
		MODE DIFF *.**dB	3.00	50.00	0.01
	r	SMSR MODE SMSR1/SMSR2/SMSR3/SMSR4	SMSR1	-	-
	SMSR	SMSR MASK **.**nm	0.00	99.99	0.00
	ō	MODE DIFF **.**dB	3.00	50.00	0.01
		ALGO RMS/PK-RMS	RMS	-	-
	RMS	THRESH	20.00	50.00	0.01
	R	к	2.00	10.00	0.01
DFB-LD		MODE DIFF	3.00	50.00	0.01
	POWER	SPAN	0.40	10.00	0.01
		MODE DIFF	3.0	50.00	0.01
		NOISE ALGO	PIT	-	-
		NOISE AREA	AUTO	10.00	0.01
	氏	MASK AREA	-	10.00	0.01
3)	OSNR	FITTING ALGO	LINEAR	-	-
		NOISE BW	0.10	1.00	0.01
9 9		SIGNAL POWER	PEAK	-	-
))		INTEGRAL RANGE	10	999	10
	DTH	ALGO ENVELOPE/THRESH/RMS/PK-RMS	PK-RMS	-	-
	MID	THRESH **.**dB	20.00	50.00	0.01
	SPECTRUM WIDTH	THRESH2 **.**dB	20.00	50.00	0.01
		К	2.00	10.00	1.00
		MODE FIT OFF/ON	OFF	_	_
		MODE DIFF *.**dB	3.00	50.00	0.01
	MEAN WAVELENGTH	ALGO ENVELOPE/THRESH/RMS/PK-RMS	PK-RMS	-	-
	N N N	THRESH **.**dB	20.00	50.00	0.01
	VEL	THRESH2 **.**dB	20.00	50.00	0.01
D.	WA	K	2.00	10.00	1.00
FP-LD	AN	MODE FIT OFF/ON	OFF	-	-
	ШШ	MODE DIFF *.**dB	3.00	50.00	0.01
	TOTAL POWER	OFFSET LEVEL *.**dB	0.00	10.00	-10.00
		ALGO ENVELOPE/THRESH/RMS/PK-RMS	PK-RMS	-	-
	<u>o</u>	THRESH **.**dB	20.00	50.00	0.01
	MODE NO	THRESH2 **.**dB	20.00	50.00	0.01
	100	К	2.00	10.00	1.00
	2	MODE FIT OFF/ON	OFF	-	-
		MODE DIFF *.**dB	3.00	50.00	0.01

			Function	Default Value	Maximum Value	Minimum Value
		SPECTRUM WIDTH	ALGO ENVELOPE/THRESH/RMS/PK-RMS	THRESH	-	-
		M	THRESH **.**dB	3.00	50.00	0.01
		Σ	THRESH2 **.**dB	20.00	50.00	0.01
		TRI	К	1.00	10.00	1.00
		С Ш	MODE FIT OFF/ON	OFF	-	-
		Р.	MODE DIFF *.**dB	3.00	50.00	0.01
	LED	т	ALGO ENVELOPE/THRESH/RMS/PK-RMS	RMS	-	-
0		MEAN WAVELENGTH	THRESH **.**dB	20.00	50.00	0.01
000		MEAN /ELENC	THRESH2 **.**dB	20.00	50.00	0.01
0		VEL ME	K	2.00	10.00	1.00
s,		AN I	MODE FIT OFF/ON	OFF	-	-
lysi			MODE DIFF *.**dB	3.00	50.00	0.01
Analysis 1		TOTAL POWER	OFFSET LEVEL *.**dB	0.00	10.00	-10.00
		SMSR	SMSR MODE SMSR1/SMSR2/SMSR3/SMSR4	SMSR1	-	-
		DIVIOR	SMSR MASK *.**nm	0.00	99.99	0.00
	P	OWER	OFFSET LEVEL *.**dB	0.00	10.00	-10.00
		PMD	THRESH LEVEL *.**dB	3.00	50.00	0.01
		CHANNEL DETECTION SETTING	THRESH LEVEL *.**dB	3.00	50.00	0.01
		HAN	MODE DIFF *.**dB	3.00	50.00	0.01
		о Щ o	DISPLAY MASK OFF/*.*dB	OFF	0.00	-100.00
		SETTING	NOISE ALGO AUTO-FIX/MANUAL-FIX/ AUTO-CTR/MANUAL-CTR	AUTO-FIX	-	-
			NOISE AREA *.**nm	0.40	10.00	0.01
		NO	MASK AREA *.**nm	0.20	10.00	0.01
<u>n</u> a 0		INTERPOLATAION SETTING	FITTING ALGO LINEAR/GAUSS/LORENZ/ 3RD POLY/4TH POLY/5TH POLY	LINEAR	-	-
8 8	Σ	LZ	NOISE BW *.**nm	0.10	1.00	0.01
is 2	WDM		DUAL TRACE OFF/ON	OFF	-	-
Analysis 2		ŮN	DISPLAY TYPE ABSOLUTE/RELATIVE/ DRIFT(MEAS)/DRIFT(GRID)	ABSOLUTE	-	-
		DISPLAY SETTING	CH RELATION OFFSET/SPACING	OFFSET	-	-
		ISPLA	REF CH HIGHEST/****CH	HIGHEST	1024	1
			OUTPUT SLOPE OFF/ON	OFF	-	-
			POINT DISPLAY OFF/ON	ON	-	-
		OTHER	SIGNAL POWER PEAK/INTEGRAL	PEAK	-	-
		OTHER	INTEGRAL RANGE	10.0	999.9	1.0

		Function	Default Value	Maximum Value	Minimum Value
	CHANNEL DETECTION SETTING	THRESH LEVEL *.**dB	3.00	50.00	0.01
	CHAI DETE SET	MODE DIFF *.**dB	3.00	50.00	0.01
		OFFSET(IN) *.**dB	0.00	99.99	-99.99
		OFFSET(OUT) *.**dB	0.00	99.99	-99.99
	ON SETT	ASE ALGO LINEAR/GAUSS/LORENZ/ 3RD POLY/4TH POLY/5TH POLY	LINEAR	-	-
Į Ž	AIC	FITTING AREA *.**nm	0.40	10.00	0.01
EDFA-NF	[A]	MASK AREA *.**nm	0.20	10.00	0.01
	INTERPOLATAION SETTING	FITTING ALGO LINEAR/GAUSS/LORENZ/ 3RD POLY/4TH POLY/5TH POLY	LINEAR	-	-
	=	POINT DISPLAY OFF/ON	ON	-	-
	CULA- TTING	RES BW MEASURED/CAL DATA	CAL DATA	-	-
	NF CALCULA- TION SETTING	SHOT NOISE OFF/ON	ON	-	-
9	PEAK LEVEL	SW OFF/ON	ON	-	-
Analysis 2 @@@@	PEAK WAVE LENGTH	SW OFF/ON	ON	-	-
alys	CENTER WAVELENGTH	SW OFF/ON	ON	-	-
Ans		ALGO THRESH/RMS	THRESH	-	-
		THRESH LEVEL *.**dB	3.00	50.00	0.01
	Ш Ц Ц Ц Ц	К	1.00	10.00	1.00
	°≹	MODE FIT OFF/ON	OFF	-	-
	>	MODE DIFF *.**dB	3.00	50.00	0.01
		SW OFF/ON	ON	-	-
못	ECTRUM MIDTH	ALGO THRESH/RMS	THRESH	-	-
LTER-PK	ECTRU	THRESH LEVEL *.**dB	3.00	50.00	0.01
	l m ≥	К	1.00	10.00	1.00
Ē	SP	MODE FIT OFF/ON	OFF	-	-
		MODE DIFF *.**dB	3.00	50.00	0.01
	RIPPLE WIDTH	SW OFF/ON	ON	-	-
		THRESH LEVEL *.**dB	3.00	50.00	0.01
		MODE DIFF *.***dB SW OFF/ON	0.500 ON	50.000	0.001
	×	ALGO THRESH/PK LEVEL/GRID	THRESH	-	-
	ALI	THRESH LEVEL *.**dB	3.00	50.00	0.01
	CROSS TALK	К	1.00	10.00	1.00
	Sos	MODE FIT OFF/ON	OFF	-	-
	CH	MODE DIFF *.**dB	3.00	50.00	0.01
		CH SPACE ±*.**nm	0.40	50.00	0.00
		SEARCH AREA ±*.**nm	0.01	10.00	0.01

		Function	Default Value	Maximum Value	Minimum Value
	BOTTOM LEVEL	SW OFF/ON	ON	-	-
	BOTTOM WAVE LENGTH	SW OFF/ON	ON	-	-
	~ -	SW OFF/ON	ON	-	-
	CENTER WAVE LENGTH	ALGO PEAK/BOTTOM	BOTTOM	-	-
5		THRESH LEVEL *.**dB	3.00	50.00	0.01
FILTER-BTM		MODE DIFF *.**dB	3.00	50.00	0.01
		SW OFF/ON	ON	-	-
13	NOTCH WIDTH	ALGO PEAK/BOTTOM	BOTTOM	-	-
		THRESH LEVEL *.**dB	3.00	50.00	0.01
	2-	MODE DIFF *.**dB	3.00	50.00	0.01
		SW OFF/ON	ON	-	-
	CROSS TALK	ALGO PEAK/BOTTOM/BOTTOM LVL/ GRID	BOTTOM	-	-
	Ö	THRESH LEVEL *.**dB	20.00	50.00	0.01
	CR	MODE DIFF *.**dB	3.00	50.00	0.01
ລ)		CH SPACE ±*.**nm	0.40	50.00	0.00
8		SEARCH AREA ±*.**nm	0.01	10.00	0.01
5 00 0 00	CHANNEL DETECTION/ NOMINAL WAVELENGTH	ALGO PEAK/MEAN/GRID FIT/GRID	MEAN	-	-
Analysis 2		THRESH LEVEL *.*dB	3.0	50.0	0.1
haly	N H H H H H H H H H H H H H H H H H H H	MODE DIFF *.*dB	3.0	50.0	0.1
₹		TEST BAND *.***nm	0.100	9.999	0.001
	PEAK WAVELENGTH / LEVEL	SW OFF/ON	ON	-	-
wdm fil-pk	XdB WIDTH/ CENTER WAVELENGTH	SW OFF/ON	ON	-	-
5	XdB STOP BAND	SW OFF/ON	ON	-	-
	ST(BAI	THRESH LEVEL *.***dB	-10.000	30.000	-90.000
		SW OFF/ON	ON	-	-
	XdB PASS BAND	THRESH LEVEL *.*dB	3.0	50.0	0.1
	~ C B	TEST BAND *.**nm	0.20	99.99	0.01
	RIPPLE	SW OFF/ON	ON	-	-
	RIP	TEST BAND *.**nm	0.20	99.99	0.01
	ω Υ	SW OFF/ON	ON	-	-
	CROSS TALK	SPACING *.**nm	0.80	99.99	0.01
	10	TEST BAND *.**nm	0.20	99.99	0.01

			Function	Default Value	Maximum Value	Minimum Value
		CHANNEL DETECTION / NOMINAL WAVELENGTH	ALGO BOTTOM/NOTCH(P)/NOTCH(B)/ GRID FIT/GRID	NOTCH(B)	-	-
			THRESH LEVEL *.*dB	20.0	50.0	0.1
		NNE VAV	MODE DIFF *.*dB	20.0	50.0	0.1
		CHA	TEST BAND *.***nm	0.100	9.999	0.001
		BOTTOM WAVELENGTH / LEVEL	SW OFF/ON	ON	-	-
Analysis 2 @@@@	-BTM	XdB NOCH WIDTH / CENTER WAVELENGTH	SW OFF/ON	ON	-	-
lysis 2 (wdm fil-btm	XdB NC CENTER	ALGORITHM NOTCH(P)/NOTCH(B)	NOTCH(B)	-	-
Ana	\$		THRESH LEVEL *.*dB	3.0	50.0	0.1
		UD D	SW OFF/ON	ON	-	-
		XdB STO BAND	THRESH LEVEL *.***dB	-10.000	30.000	-90.000
		ELIMINATION XdB STOP BAND BAND	SW OFF/ON	ON	-	-
			THRESH LEVEL *.*dB	3.0	50.0	0.1
		XdB E	TEST BAND *.**nm	0.20	99.99	0.01
			SW OFF/ON	ON	-	-
		RIPPLE	TEST BAND *.**nm	0.20	99.99	0.01
		S	SW OFF/ON	ON	-	-
		CROSS TALK	SPACING *.**nm	0.80	99.99	0.01
		Ϋ́́Υ	TEST BAND *.**nm	0.20	99.99	0.01
Spec	Widt	n Thresh '	*.**dB	3.00	50.00	0.01
ح≥	Trac	e & Table	/Table/Trace/Graph & Table/Graph	Trace & Table	-	-
Switch Display	Gra	oh & Table	e/ Line Marker Y1 OFF/ON	OFF	-	-
ΩД	Gra	oh	Line Marker Y2 OFF/ON	OFF	-	-
Auto	Analy	sis OFF/0	DN	OFF	-	-
Searc	ch / A	na Markei	L1-L2 OFF/ON	OFF	-	-
Sear	ch / A	na Zoom	Area OFF/ON	ON	-	-

		Function		Default Value	Maximum Value	Minimum Value
	Memory IN	Memory INT/EXT			-	-
	_ Trace $@ \rightarrow$ File		А	-	-	
	Trace	File Type BIN/CSV		BIN	-	-
	Craphica	Mode Black & White/Color/Preset Color		Color	-	-
	Graphics	File Type BMP/TIFF		BMP	-	-
			Date & Time OFF/ON	ON	-	-
			Label OFF/ON	ON	-	-
Write			Data Area OFF/ON	ON	-	-
5	Data	Output Item Setting	Condition OFF/ON	ON	-	-
			Trace Data OFF/ON	OFF	-	-
			Output Window OFF/ON	OFF	-	-
		Write Mode OVER/ADD	i	OVER		
	Program	Cursor UP/DOWN		DOWN	-	-
	File Sort @	@@@		File Name	-	-
	Memory IN ⁻	T/EXT		INT	-	-
-	Trace	Trace $@ \rightarrow File$		А	-	-
Read	Trace	View LIST/THMB		LIST	-	-
ш	Program	Cursor UP/DOWN		DOWN	-	-
	File Sort @	@@@@@@@@@@		File Name	-	-
tem	Select @@@	000		Trace	-	-
Auto	File Name N	IUM/DATE		NUM	-	-
u	Memory IN	T/EXT		INT	-	-
Operation	Сору	Memory INT/EXT		INT	-	-
File Op	File Sort @	@@@@@@@@@@		File Name	-	-

Function	Default Value	Maximum Value	Minimum Value
Execute 1 **	01 (program number)	-	-
Execute 2 **	02 (program number)	-	-
Execute 3 **	03 (program number)	-	-
Execute 4 **	04 (program number)	-	-
Execute 5 **	05 (program number)	-	-
Execute 6 **	06 (program number)	-	-
Execute 7 **	07 (program number)	-	-
Execute 8 **	08 (program number)	-	-
Execute 9 **	09 (program number)	-	-
Execute 10 **	10 (program number)	-	-
Execute 11 **	11 (program number)	-	-
Execute 12 **	12 (program number)	-	-
Execute 13 **	13 (program number)	-	-
Execute 14 **	14 (program number)	-	-
Execute 15 **	15 (program number)	-	-
Execute 16 **	16 (program number)	-	-
Execute 17 **	17 (program number)	-	-
Execute 18 **	18 (program number)	-	-
Execute 19 **	19 (program number)	-	-
Execute 20 **	20 (program number)	-	-
Execute 21 **	21 (program number)	-	-

		Function	Default Value	Maximum Value	Minimum Value
	Built-in Sou	rce	OFF ¹	-	-
ength ation	External La	ser ****.***nm	1523.488, ON ¹	1650.000	1200.000
Wavelength Calibration	External Ga	is Cell ****.***nm	1530.372, OFF	1650.000	1200.000
30	Emission Li	ne ****.***nm	1473.684, OFF	1650.000	1200.000
Emission Line ****.***nm Vavelength Shift **.***nm		0.000	5.000	-5.000	
_evel Shift *		-	0.000	60.000	-60.000
	200GHz Sp	acing	ON	-	-
	100GHz Sp	-	OFF	-	-
	50GHz Spa	cing	OFF	-	-
	25GHz Spa	cing	OFF	-	-
Ļ	12.5GHz S	pacing	OFF	-	-
Grid Editor		Start Wavelength ****.***nm	1528.7734	1650.0000	1200.0000
Ш р		Start Wavelength ****.****THz	192.1000	249.8270	181.6924
G	Custom	Stop Wavelength ****.***nm	1560.6062	1650.0000	1200.0000
		Stop Wavelength ****.****THz	196.1000	249.8270	181.6924
		Spacing ***.*GHz	50.0	999.9	0.1
	Reference	Navelength **** ****nm	1552.5244	1650.0000	1200.0000
	Reference Wavelength ****.***THz		193.1000	249.8270	181.6924
emote Interface @@@@		GP-IB	-	-	
GP-IB	My Address **		1	_	-
Setting	Command Format @@@@		AQ6360	-	-
	TCP/IP Setting		AUTO (DHCP)	-	-
n	Remote Port No.		10001	65535	1024
Network Setting	Command I	Format @@@@	AQ6360	-	-
N N N	Remote	Monitor Port OFF/ON	ON	-	-
etwo	Monitor	Port No.	20001 (FIX)	-	-
ž	Folder Shar	ing DISABLE/READ ONLY	DISABLE		
	Firewall OF	F/ON	ON		
Auto Offset Setting	Auto Offset	OFF/ON	ON	-	-
AL Off Set	Interval ***	min	10	999	10
Jncal Warn	ing OFF/ON		ON	-	-
Buzzer	Click OFF/0	DN	ON	-	-
Buz	Warning OF	F/ON	ON	-	-
_evel Displa	y Digit *		2	3	1
Nindow Tra	nsparent OFI	F/ON	ON	-	-
×	YR-MO-DY		ON	-	-
Clock	MO-DY-YR		OFF	-	_
Set (DY-MO-YR		OFF		
			COLOR	-	
Color Mode @@@@			QWERTY		


*1 For the /LFC and /LSC options, the default value of Built-in Source is ON.

7.4 Help

Procedure

- 1. Display the function menu that you want to display the help for.
- 2. Tap **Menu**. The Main Menu window appears.
- 3. Tap HELP. An explanation appears for the displayed function menu.
- If MORE INFO is displayed in the explanation, a further detailed explanation is available. Tap MORE INFO, or select MORE INFO with the arrow keys and then tap Select.
- 5. To finish, tap Quit Help.

Menu that appears when HELP is tapped



7.5 Registering and Recalling Character Strings

On the character input screen of this instrument, you can register character strings input to the keyboard shown on the screen and recall them for use.

Procedure

Registering a Character String


- **1.** Display the character input screen, and enter the character string that you want to register with the keyboard.
- 2. Tap Preset Word on the function menu. A preset word list appears.
- **3.** Tap a line in the preset word list to move the cursor to the number you want to register at. You can also move the cursor by tapping the arrow keys.
- 4. Tap Save. The character string is registered at the specified number.
- 5. To close the preset word list, tap Return.

Recalling a Character String

- **1.** Using the keyboard, move the cursor to the position where you want to enter a character string.
- 2. Tap Preset Word on the function menu. A preset word list appears.
- **3.** Tap a line in the preset word list to move the cursor to the character string you want to recall. You can also move the cursor by tapping the arrow keys.
- 4. Tap Recall. The character string will be recalled at the specified position.
- 5. To close the preset word list, tap Return.

Deleting a Character String

- Display the character input screen, and tap Preset Word on the function menu. A
 preset word list appears.
- **2.** Tap a line in the preset word list to move the cursor to the character string you want to delete. You can also move the cursor by tapping the arrow keys.
- 3. Tap Clear. The character string will be deleted.



List of registered character strings


7.6 Locking the Keys

This function prevents all operations except for the function menu containing user keys. For details on how to register user keys, see section 7.2, "Registering User Keys."

Procedure

Locking the Keys

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SYSTEM. A function menu for the system appears.
- 3. Tap More to display the More 3/4 function menu.
- 4. Tap Operation Lock. A parameter input window appears.
- 5. Enter a password in the parameter input window. The default password is 1234.
- **6.** Tap Lock. A message appears stating that the keys have been locked, and the function menu changes to a USER menu.



Note .

- If no user keys are registered, nothing appears on the USER function menu. In the screen example, three keys, CENTER WL, ZOOM CENTER WL, and DISPLAY OFF, are registered.
- When the keys are locked, the following operations can be performed in addition to the registered user keys.
 - USER, LOCAL (release remote mode), HELP, and COPY in the Main Menu window
 - POWER switch
- If you forget the password, initialize the data (All Clear). For the procedure, see section 7.3, "Data Initialization."
- The power switch is enabled even while the keys are locked. If you turn off the instrument in the lock mode, the it start in lock mode when the power is turned back on.

Changing the Password


- 6. Tap Change Password. A parameter input window appears.
- 7. Enter a new 4-digit password in the parameter input window.
- **8.** Enter the password entered in step 7 again in the parameter input window. A password change completion message appears.

Note

- The characters that can be used for the password are numbers from 0 to 9.
- If you forget the password when the keys are locked, you will not be able to unlock. If you change the password from the default, manage your password carefully.

Unlocking the Keys

- **1.** Display the Main Menu window, and tap any of the locked keys (other than USER, LOCAL, COPY, or HELP keys or POWER switch).
- 2. Tap Unlock. A parameter input window appears.
- **3.** Enter the password in the parameter input window. A message appears stating that the keys have been unlocked.



Note

Even when the keys are locked, you can still use the instrument remote commands and program commands as usual. However, if the instrument is in remote mode as a result of receiving REN (Remote Enable) or a listen address with ATN set to True from the controller, the key lock cannot be released. In such a case, Tap LOCAL on the Main Menu window to switch the instrument to remote mode, and then release the key lock. For details on switching between local and remote modes, see section 1.2 in the Remote Control User's Manual (IM AQ6360-17EN).

7.7 Other Settings


Procedure

Setting the UNCAL mark and Warning Display

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SYSTEM.
- 3. Tap More to display the More 3/4 function menu.
- Tap Uncal Warning. Each time you tap, the value switches between ON and OFF. When set to ON, the UNCAL mark and warning can be displayed.

Setting the Buzzer

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SYSTEM.
- 3. Tap More to display the More 3/4 function menu.
- Tap Buzzer. A menu appears for turning on and off the click sound and warning sound.
- Tap Click or Warning. Each time you tap, the value switches between ON and OFF. When set to ON, the buzzer sound is enabled.



Setting the Test Mode

The test mode is used to adjust the instrument at the factory and is not used in ordinary situations.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SYSTEM.
- **3.** Tap **More** to display the More 4/4 function menu.
- 4. Tap Test Mode. A parameter input window appears.

Setting the Automatic Offset

You can set whether to perform automatic offset on the amplifier circuit in the instrument.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SYSTEM.
- 3. Tap More to display the More 2/4 function menu.
- 4. Tap Auto Offset Setting. The automatic offset setup menu appears.
- **5.** Tap **Auto Offset**. Each time you tap, the value switches between ON and OFF. When set to ON, automatic offset is enabled.
- Tap Interval to set the automatic offset execution interval. (We recommend the default value of 10min.)

Note .

- If the AUTO OFFSET is set to OFF, the offset can vary over time, and the level axis performance can degrade. Normally, have this turned on.

Sharing the Remote Monitor

This function can be used to monitor the instrument's screen and control the instrument from a remote PC that is connected over TCP/IP.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SYSTEM.
- **3.** Tap **More** to display the More 2/4 function menu.
- 4. Tap Network Setting. An Ethernet setup menu appears.
- 5. Tap Remote Monitor. A remote monitor setup menu appears.
- **6.** Tap **Monitor Port**. Each time you tap, the value switches between ON and OFF. When this is set to ON, the remote monitor is enabled.

Sharing Directories

The user area directory of the instrument's internal memory can be shared on a PC.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SYSTEM.
- **3.** Tap **More** to display the More 2/4 function menu.
- 4. Tap Network Setting. An Ethernet setup menu appears.
- 5. Tap Folder Sharing. A directory sharing setup menu appears.
- 6. Tap Read Only. Directory sharing is enabled.

Tapping **Disable** disables directory sharing.

Configuring a Firewall

You can close the TCP port when the communication interface (Ethernet), remote monitoring, and directory sharing are not in use.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SYSTEM.
- **3.** Tap **More** to display the More 2/4 function menu.
- 4. Tap Network Setting. An Ethernet setup menu appears.
- Tap Firewall. Each time you tap, the value switches between ON and OFF. When set to ON, the firewall is enabled.

Setting the Language

You can set the language for the function menu and messages to English or Chinese.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap SYSTEM.
- 3. Tap More to display the More 3/4 function menu.
- 4. Tap Language. A language setting menu appears.
- 5. Tap the language you want to use.

Setting the Keyboard Display

You can set the language for the function menu and messages to English or Chinese.

- 1. Tap **= Menu**. The Main Menu window appears.
- 2. Tap SYSTEM.
- **3.** Tap **More** to display the More 4/4 function menu.
- 4. Tap Screen KYBD Layout.
- Tap QWERTY. A QWERTY keyboard display is selected.
 Tap QWERTZ. A QWERTZ keyboard display is selected.

Turning the Display OFF

This function can be used to temporarily turn the display off.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap DISPLAY.
- 3. Tap Display Off. The display turns OFF.

Tapping the screen or operating the mouse will turn the display on.

Clearing Measured Data, Analysis Conditions, Parameters, Etc.

The PRESET key clears all internal settings of the instrument except for the remote interface (ETHERNET and GP-IB) settings.

- 1. Tap **Menu**. The Main Menu window appears.
- 2. Tap PRESET. A message appears for confirmation.
- Tap YES. The measured data and parameter settings are cleared. If you do not want to clear the settings, tap No. The function menu will return to the previous level.

7


Explanation

Automatic Offset

When Auto Offset is set to ON, the offset of the internal amplifier circuit is adjusted at the specified interval (default value: 10min). (Default value: ON)

When Auto Offset is set to OFF, automatic offset adjustment is not executed. When the setting is changed from OFF to ON, an offset adjustment is executed immediately. If repeat sweep is in progress, offset adjustment is executed when sweeping reaches 100%. If a single sweep is in progress, offset adjustment is executed when the sweep is completed.

During offset adjustment, a message indicating that the offset is being adjusted is displayed in the lower-left corner and in the top center of the screen.



Note

If, during offset adjustment, you use key operations or remote commands to execute a sweep, the sweep will start after the offset adjustment is completed.

Remote Monitoring

This function can be used to monitor the instrument's screen and control the instrument from a remote PC that is connected to the instrument through a TCP/IP port. To use this function, you need remote monitoring software (not included). You cannot use the remote monitoring port to perform remote control with normal remote commands.

User Name and Password

A user name and password are required to access the instrument using this function. Use the menu that is displayed when you tap Remote User Account in the Ethernet setup to specify these settings. See the remote control user's manual, IM AQ6360-17EN.

Monitor Port

Enables and disables the remote monitor TCP/IP port. If you set this to OFF, the remote monitor is disabled.

Port No.

This is the remote monitor TCP/IP port number. It is fixed to 20001. You cannot use this port to perform remote control with normal remote commands.

Disconnect

During remote monitoring, tap this key to disconnect the instrument from the remote PC. This key can only be used when the instrument is connected to a PC.

Sharing Directories

The user area directory of the instrument's internal memory can be shared on a PC. When the user area directory is shared, files in the directory can be copied to the PC over a network. You cannot save files to the instrument.

Firewall

This feature closes the TCP port to cut off the communication when features that use the TCP port are set to off.

Feature Name	Operation
Key Name	
Sharing Directories	Disable: Communication is cut off (the TCP port is closed).
<folder sharing=""></folder>	Read Only: Communication is not cut off (the TCP port is open).
Remote monitoring	OFF: Communication is cut off (the TCP port is closed).
<monitor off="" on="" port=""></monitor>	ON: Communication is not cut off (the TCP port is open).
Communication interface	GP-IB: Communication is cut off (the TCP port is closed).
<remote interface=""></remote>	ETHERNET: Communication is not cut off (the TCP port is open).


Language

You can set the language for the following items to English or Chinese.

- Function menus
- · Title of parameter input windows
- Warnings and messages
- · Help

Setting the Keyboard Display

You can select a QWERTY keyboard or QWERTZ keyboard. The positions of the Y and Z keys on the keyboard display are switched.



Turning the Display OFF


This function can be used to temporarily turn the display off. Use this function when you are using the instrument in a darkroom or similar environment in which the light from the screen has an effect on the work.

Display Off

Turns off the backlight, which will also turn the display off.

When Remote Commands Have Been Used to Turn the Display OFF

If remote commands have been used to turn the display off, even if you perform touch panel or mouse operations to turn the display on, the following message will be displayed and the display will be turned off after approximately 5 seconds.



To keep the display turned on, use a remote command, or Tap LOCAL on the Main Menu window to switch the instrument from remote to local mode.

Clearing Measured Data, Analysis Conditions, Parameters, Etc.

This function clears all measurement parameters, display parameters, analysis parameters, and the waveform display. It is the same operation as when the instrument receives an *RST remote command.

The following data is not cleared.

- · Remote interface (ETHERNET and GP-IB) settings
- wavelength calibration data
- · Various type of data saved to internal memory
- · Registered programs created using the program function


7.8 Displaying the System Information

Procedure

Displaying the System Information

Displaying the System Information

- 1. Tap **Menu** . The Main Menu window appears.
- 2. Tap SYSTEM.
- 3. Tap More to display the More 4/4 function menu.
- 4. Tap System Information. A system information menu appears.
- 5. Tap System Information. The system information is displayed on the screen.
- 6. Tap **Return** to return to the previous menu.




Displayed Information

Model				
Special code (may not be displayed)				
Serial number				
MAC address of the Ethernet port				
TCP/IP settings				
-				


Displaying or Clearing the System Log and Copying to USB Memory Displaying the System Log

- 1. Tap **Menu** . The Main Menu window appears.
- 2. Tap SYSTEM.
- 3. Tap More to display the More 4/4 function menu.
- 4. Tap System Information. A system information menu appears.
- 5. Tap System Log. A system log menu appears.
- 6. Tap View. The system log is displayed on the screen.
- 7. Tap **Done** to return to the previous menu.



Clearing the System Log

8. Tap Clear and then YES. The system log will be cleared.



Copying the System Log to USB Memory

 Connect a USB memory device, and then tap Save to USB Memory. The system log will be copied to the USB memory device. File name: SystemLog.txt

Appendix 1 Grid Table for WDM Wavelength

Some analysis functions refer to the grid table for analysis (see the following table). The instrument has a table of nominal center frequencies specified by the ITU-T (International Telecommunication Union-Telecommunication sector) G692. It also has two additional tables: the standard grid table created according to the predefined wavelength (frequency) range and the custom grid table that users can edit freely.

List of Analysis Functions with Grid Tables

Function	Item	Parameter Name	Parameter
WDM	DISPLAY SETTING	DISPLAY TYPE	DRIFT(GRID)
FILTER PEAK	CROSS TALK	ALGO	GRID
FILTER BOTTOM	CROSS TALK	ALGO	GRID
WDM FILTER PEAK	CAHNEL DETECTION/	ALGO	GRIF FIT
	NOMINAL WAVELENGTH		GRID
WDM FILTER BOTTO	M CAHNEL DETECTION/	ALGO	GRIF FIT
	NOMINAL WAVELENGTH		GRID

Note .

The unit of the wavelength axis in the grid tables can be set to wavelength or frequency using the MARKER UNIT setting.

The standard and two custom grid tables have different parameter ranges. The following table shows the parameter ranges.

	Туре	Parameter Range
Standard grid table		
-	Start frequency	191.1000 THz (fixed)
	Stop frequency	196.1000 THz (fixed)
	Reference frequency	181.6924 to 249.8270 THz
	Frequency spacing	Select 200 GHz, 100 GHz, 50 GHz, 25
GHz, or 11.5 GHz.		
Custom grid table		
-	Start frequency	181.6924 to 249.8270 THz
	Stop frequency	181.6924 to 249.8270 THz
	Reference frequency	181.6924 to 249.8270 THz
	Frequency spacing	0.1 to 999.9GHz

Standard grid table

This grid table is created with pre-defined wavelength (frequency) ranges. It can be created by setting the reference wavelength (frequency) and frequency spacing.

Custom grid table

This is a grid table that users can edit as they like.

It is created automatically by setting the start/stop wavelength (frequency), reference wavelength (frequency), and frequency spacing.

Users can add or delete an arbitrary channel to/from the created grid table or edit wavelength (frequency) values for each channel there.

Appendix 2 Data Calculation Algorithms for Spectrum Widths

The instrument can calculate spectrum widths of waveforms being displayed. This section provides four types of spectrum width calculation methods as well as algorithms for the notch width calculation.

THRESH Method


This method is used to obtain the spectrum widths of two points, which are lower than the peak level by a threshold value (THRESH [dB]) specified by a parameter, as well as their center wavelengths.

The following table shows the details of the parameters of the THRESH method.

Parameter	Abbreviation	Default Value	Setting Range	Unit	Description
THRESH	TH	3.00	0.01 to 50.00	dB	Threshold value
THRESH K	К	1.00	1.00 to 10.00	-	Multiplying factor
MODE FIT	MODE FIT	OFF	ON / OFF	-	Sets whether the half of maximum point is aligned to the mode peak.

Algorithms differ depending on the number of mode peaks. Algorithms for these numbers are described below.

One mode peak



- A mode search is performed to obtain the mode peaks.
- Wavelengths, which cross the line below the mode peak by the threshold value (THRESH[dB]), are assigned to λ_1 and λ_2 .
- New λ_1 and λ_2 are obtained by multiplying factor K to the original λ_1 and λ_2 according to the following equations.

 λ 'C = ($\lambda_2 + \lambda_1$)/2

$$\Lambda_1 = \mathsf{K} \times (\lambda_1 - \lambda'\mathsf{C}) + \lambda'\mathsf{C}$$

$$\lambda_2 = K \times (\lambda_2 - \lambda'C) + \lambda'C$$

• The spectral width is determined from the following equation.

```
\Delta \lambda = \lambda_2 - \lambda_1
```

- Center wavelength λC is determined from the following equation. λC = $(\lambda_2$ + $\lambda_1)/2$


Note -

If "MODE FIT" is set to ON for one mode peak, the spectral width $\Delta\lambda$ and the center wavelength λC will become as follows.

Δλ = 0.0000nm

 λC = mode peak wavelength

Two or more mode peaks



- If "MODE FIT" is ON, the wavelengths of the mode peaks, which are outmost from the threshold value (THRESH[dB]) among the mode peaks, are assigned to λ₁ and λ₂. If "MODE FIT" is OFF, the wavelengths, which are located outside λ1 and λ2, and which cross the line below the mode peak with the largest mode peak level by the threshold value (THRESH[dB]), are assigned to λ'₁ and λ'₂.
- If "MODE FIT" is ON, New $\lambda 1$ and $\lambda 2$ are obtained by multiplying factor K to the original $\lambda 1$ and $\lambda 2$ according to the following equations.

When "MODE FIT" is ON

$$\lambda'C = (\lambda_2 + \lambda_1)/2$$

$$\begin{split} \lambda_1 &= \mathsf{K} \times (\lambda_1 \ - \ \lambda'\mathsf{C}) + \lambda'\mathsf{C} \\ \lambda_2 &= \mathsf{K} \times (\lambda_2 - \ \lambda'\mathsf{C}) + \lambda'\mathsf{C} \end{split}$$

When "MODE FIT" is OFF λ 'C = $(\lambda'2+\lambda'_1)/2$

$$\lambda'_{1} = \mathsf{K} \times (\lambda'_{1} - \lambda'\mathsf{C}) + \lambda'\mathsf{C}$$

$$\lambda'_2 = K \times (\lambda'_2 - \lambda'C) + \lambda'C$$

• The spectral width is determined from the following equation.

 $\Delta \lambda = \lambda_2 - \lambda_1$ (when "MODE FIT" is ON)

 $\Delta \lambda = \lambda'_2 - \lambda'_1$ (when "MODE FIT" OFF)

- Center wavelength λC is determined from the following equation.

 λC = (λ_2 + $\lambda_1)/2~$ (when "MODE FIT" is ON)

 $\lambda C = (\lambda'_2 + \lambda'_1)/2$ (when "MODE FIT" is OFF)

MODE displayed in the data area are to be the number of mode peaks between λ_1 and $\lambda_2.$

ENVELOPE (envelope curve) Method

This method is used in conjunction with a straight line (envelope) connecting mode peaks to obtain the spectrum widths of the two points, which are lower than the peaks by a configured threshold value (THRESH [dB]), as well as their center wavelengths. The following table shows the details of the parameters of the ENVELOPE method.


		0			
Parameter	Abbreviation	Default Value	Setting Range	Unit	Description
THRESH 1	TH1	3.00	0.01 to 50.00	dB	Threshold value
THRESH 2	TH2	13.00	0.01 to 50.00	dB	Threshold value when the number of modes is calculated
К	К	1.00	1.00 to 10.00	-	Multiplying factor

Algorithms differ depending on the number of valid mode peaks.

Valid mode peaks mean the mode peaks, among the mode peaks obtained from a mode search, whose level (LOG) is equal to or greater than the line that is below the peak level by the lower limit (THRESH2).

Algorithms for these numbers of valid modes are described below.

One valid mode peak



- A mode search is performed to obtain the mode peaks.
- Wavelengths, which cross the line below the mode peak by the threshold value (THRESH[dB]), are assigned to λ_1 and λ_2 .
- New $\lambda 1$ and $\lambda 2$ are obtained by multiplying factor K to the original $\lambda 1$ and $\lambda 2$ according to the following equations.


$$\lambda'C = (\lambda_2 + \lambda_1)/2$$

$$\lambda_1 = \mathsf{K} \times (\lambda_1 \ - \ \lambda'\mathsf{C}) + \lambda'\mathsf{C}$$

$$\lambda_2 = K \times (\lambda_2 - \lambda'C) + \lambda'C$$

- The spectral width is determined from the following equation. $\Delta\lambda = \lambda_2 \ \lambda_1$
- Center wavelength λC is determined from the following equation. $\lambda C = (\lambda_2 + \lambda_1)/2$

Two valid mode peaks




- The levels (LOG) of the two valid mode peaks are assigned to LG1 and LG2 in order from the left.
- λ_1 and λ_2 are obtained using the following method.
 - When |LG2−LG1| ≤ threshold value (THRESH1[dB])
 λ becomes λ₁ and λ₂ from the left in order.
 - When |LG2-LG1| > threshold value (THRESH1[dB])
 Two valid mode peaks are connected with a straight line (envelope).
 If LG1>LG2, the wavelength for the left mode peak is assigned to λ₁. The
 wavelength of the point where the line below the peak level by the threshold
 value (THRESH[dB]) and the straight line (envelope) cross is assigned to λ₂.
 If LG1<LG2, the wavelength for the right mode peak is assigned to λ₂.
 If LG1<LG2, the wavelength for the right mode peak is assigned to λ₂. The
 wavelength of the point where the line below the peak level by the threshold
 value (THRESH[dB]) and the straight line (envelope) cross is assigned to λ₁.
- New λ_1 and λ_2 are obtained by multiplying factor K to the original λ_1 and λ_2 according to the following equations.

$$\begin{split} \lambda'C &= (\lambda_2 + \lambda_1)/2 \\ \lambda_1 &= \mathsf{K} \times (\lambda_1 - \lambda'C) + \lambda'C \\ \lambda_2 &= \mathsf{K} \times (\lambda_2 - \lambda'C) + \lambda'C \end{split}$$

- The spectral width is determined from the following equation. $\Delta\lambda=\lambda_2\ -\lambda_1$
- Center wavelength λC is determined from the following equation. $\lambda C = (\lambda_2 + \lambda_1)/2$

Three or more valid mode peaks



- The levels (LOG) of three or more valid mode peaks are assigned to LG1, LG2, . . ., LGn in order from the left. The level of the mode peak at the highest level is assigned to LGp.
- λ_1 is obtained using the following method.
 - When |LGp-LG1| ≤ threshold value (THRESH1[dB])
 - The wavelength of the LG1 mode peak is assigned to λ_1 .
 - When |LGp-LG1| > threshold value (THRESH1[dB])
 - i The leftmost mode peak that is greater than |LGp-THRESH1| is determined.
 - ii The mode peak obtained in (i) and the highest mode peak on the left of (i) are connected with a straight line.
 - iii The point where the line of |LGp-THRESH1| and the straight line (envelope) cross is assigned to λ_1 .
- λ_2 is obtained using the following method.
 - When |LGp-LGn| ≤ threshold value (THRESH1[dB])
 - The wavelength of the LG1 mode peak is assigned to λ_2 .
 - When |LGp-LGn| > threshold value (THRESH1[dB])
 - i The rightmost mode peak that is greater than |LGp-THRESH1| is determined.
 - ii The mode peak obtained in (i) and the highest mode peak on the right of (i) are connected with a straight line.
 - iii The point where the line of |LGp-THRESH1| and the straight line (envelope) cross is assigned to λ_2 .
- New λ_1 and λ_2 are obtained by multiplying factor K to the original λ_1 and λ_2 according to the following equations.

 $\lambda' C = (\lambda_2 + \lambda_1)/2$

 $\lambda_1 = \mathsf{K} \times (\lambda_1 - \lambda'\mathsf{C}) + \lambda'\mathsf{C}$ $\lambda_2 = \mathsf{K} \times (\lambda_2 - \lambda'\mathsf{C}) + \lambda'\mathsf{C}$


- The spectral width is determined from the following equation. $\Delta\lambda=\lambda_2-\lambda_1$
- Center wavelength λC is determined from the following equation. λC = $(\lambda_2 + \lambda_1)/2$

RMS Method

The RMS method is used to obtain the spectrum width and its center wavelength. The following table shows the details of the parameters of the RMS method.

Parameter	Abbreviation	Default Value	Setting Range	Unit	Description
THRESH	TH	20.00	0.01 to 50.00	dB	Threshold value
K	К	1.00	1.00 to 10.00	-	Multiplying factor

The algorithm is described below.



- The data points exceeding the threshold value TH, within the displayed waveform, are removed, and the spectrum width is determined by the following calculation.
- When the wavelength at each point is λ_i and the level at each point is Pi, the mean wavelength λc can be found by the following expression.

$$\lambda c = \frac{\sum Pi \times \lambda_i}{\sum Pi}$$

- Mean wavelength λc found above is used to find spectrum width $\Delta \lambda c$ with the following expression.


$$\Delta \lambda = \kappa_{x} \sqrt{\frac{\sum_{i} \mathsf{Pi} x (\lambda_{i} - \lambda_{c})^{2}}{\sum_{i} \mathsf{Pi}}}$$

PEAK RMS Method

The PEAK RMS method is used to obtain the spectrum width and its center wavelength. The following table shows the details of the parameters of the PEAK RMS method.

Parameter	Abbreviation	Default Value	Setting Range	Unit	Description
THRESH	TH	20.00	0.01 to 50.00	dB	Threshold value
К	К	1.00	1.00 to 10.00	-	Multiplying factor

The algorithm is described below.



- The mode peaks exceeding the threshold value TH, within the displayed waveform, are removed, and the spectrum width is determined by the following calculation.
 MODE NUM in the data area shows the number of mode peaks exceeding the threshold value TH.
- When the wavelength at each point is λ_i and the level at each point is Pi, the mean wavelength λc can be found by the following expression.

$$\lambda c = \frac{\sum Pi \times \lambda_i}{\sum Pi}$$

- Mean wavelength λc found above is used to find spectrum width $\Delta \lambda$ with the following expression.

$$\Delta \lambda = \kappa x \sqrt{\frac{\sum Pi x (\lambda_i - \lambda_c)^2}{\sum Pi}}$$

NOTCH Width Measurement

The bottom level is determined, and the NOTCH width for the bottom level and its center wavelength are determined.


Parameter	Abbreviation	Default Value	Setting Range	Unit	Description
THRESH	TH	3.00	0.01 to 50.00	dB	Threshold value
K	К	1.00	1.00 to 10.00	-	Multiplying factor
TYPE	TYPE	BOTTOM	BOTTOM / PEAK	-	Reference position for searching

The following table shows the details of the NOTCH analysis parameters.

The algorithm is described below. The algorithm differs depending on the analysis type (BOTTOM or PEAK).

The algorithms for each type of analysis are described below.

When "TYPE" is BOTTOM




- The minimum level "LGmin" is obtained. The wavelength of this point assigned to λ min.
- The rightmost wavelength located on the left of λmin and that crosses the level (LOG) of |LGmin + threshold value (THRESH[dB])| is assigned to λA.
- Set the leftmost wavelength located on the right of λmin and that crosses the level (LOG) of |LGmin + threshold value (THRESH[dB])| is assigned to λB.
- New λA and λB are obtained by multiplying factor K.

$$\lambda$$
'C = (λ B+ λ A)/2

 $\lambda A = K \times (\lambda A - \lambda'C) + \lambda'C$

- $\lambda B = K \times (\lambda B \lambda'C) + \lambda'C$
- The notch width is determined from the following equation. $\Delta\lambda = \lambda A \, \lambda B$
- Center wavelength λC is determined from the following equation. $\lambda C = (\lambda A + \lambda B)/2$

Appendix 2 Data Calculation Algorithms for Spectrum Widths



When "TYPE" is PEAK

- The minimum level "LGmin" is obtained. The wavelength of this point assigned to $\lambda\text{min.}$
- LG0 at the peak level (LOG) on the left of LGmin is determined. The wavelength of this point assigned to $\lambda 0$.
- LG1 at the peak level (LOG) on the right of LGmin is determined. The wavelength of this point assigned to $\lambda 1$.
- The larger of the two levels, LG0 o LG1, is assigned to Lp.
- The leftmost wavelength between λ0 and λ1 crossing the level (LOG) of |Lp-threshold value (THRESH[dB])| is assigned to λA.
- The rightmost wavelength between λ0 and λ1 crossing the level (LOG) of |Lpthreshold value (THRESH[dB])| is assigned to λB.
- New λA and λB are obtained by multiplying factor K.
 - λ 'C = (λ B+ λ A)/2

 $\lambda \mathsf{A} = \mathsf{K} \times (\lambda \mathsf{A} \ - \ \lambda' \mathsf{C}) + \lambda' \mathsf{C}$

 $\lambda B = K \times (\lambda B - \lambda' C) + \lambda' C$

- The notch width is determined from the following equation.
 - $\Delta \lambda = \lambda A \lambda B$
- Center wavelength λC is determined from the following equation. $\lambda C = (\lambda A + \lambda B)/2$

Appendix 3 Details of Each Analysis Function

This section describes the algorithms of analyses available under ANALYSIS 1. ANALYSIS 1 provides such functions as collective analysis of various light sources, power analysis, SMSR analysis, and PMD analysis.

SMSR Analysis Function

The optical spectrum after the measurement of DFB-LD is used to analyze the SMSR (Side Mode Suppression Ratio) of DFB-LD.


The following table shows the details of the SMSR analysis parameters.							
Parameter	Abbreviation	Default Value	Setting Range	Unit	Description		
SMSR MODE	MODE	SMSR1	SMSR1/SMSR2/ SMSR3/SMSR4	-	Execution mode during SMSR measurement		
SMSR MASK	MASK	±0.00	0.00 to 99.99	nm	Setting of near-peak mask range during SMSR1 or SMSR3 measurement		

The algorithm differs depending on the SMSR mode.

The analysis algorithms of each mode are described below.

SMSR1

The main mode is defined as the highest mode peak. The side mode is defined as the highest mode peak outside of the mask area.



The analysis algorithm for the SMSR1 mode is as follows:

- 1. A mode search is performed to determine the mode peak.
- 1. The wavelength of the main mode is assigned to λA .
- 3. The wavelength of the side mode is assigned to λB .

If relevant points do not exist, the wavelength of the highest level outside of the mask area is assigned to λB .


If there are multiple wavelengths that can be assigned to λB , the leftmost wavelength is assigned to λB .

- 4. The levels (linear values) of λA and λB are assigned to LA and LB, respectively.
- 5. SMSR and $\Delta\lambda$ are determined from the following equations.

SMSR = LA / LB $\Delta \lambda = \lambda B - \lambda A$

SMSR2

The main mode is defined as the highest mode peak. The side mode is defined as the highest mode peak adjacent to the main mode.




The analysis algorithm for the SMSR2 mode is as follows:

- 1. A mode search is performed to determine the mode peak.
- 1. The wavelength of the main mode is assigned to λA .
- 3. The wavelength of the side mode is assigned to λB . If there are no mode peaks other than the one whose wavelength has been set to λA , λB is set to λA .
- 4. The levels (linear values) of λA and λB are assigned to LA and LB, respectively.
- 5. SMSR and $\Delta\lambda$ are determined from the following equations.

SMSR = LA / LB
Δλ = λB
$$-$$
 λA

SMSR3

The main mode is defined as the highest mode peak. The side modes are defined as the highest mode peaks outside of the mask area—one on the left side and one on the right side of the mask area.



The analysis algorithm for the SMSR3 mode is as follows:

- 1. A mode search is performed to determine the mode peak.
- 1. The main mode point is assigned to PA. The wavelength of this point is assigned to λA .
- 3. The wavelength of the side mode that has a wavelength shorter than PA is assigned to λB . The wavelength of the side mode that has a wavelength longer than PA is assigned to λC .


If relevant points do not exist, for the levels outside the mask area, the wavelength at the highest level whose wavelength is shorter than PA is assigned to λB and the wavelength at the highest level whose wavelength is longer than PA is assigned to λC .

- 4. The levels (linear values) of λA , λB , and λC are assigned to LA, LB, and LC, respectively.
- 5. SMSR and $\Delta\lambda$ are determined from the following equations.

SMSR(L) = LA / LB SMSR(R) = LA / LC $\Delta\lambda(L) = \lambda B - \lambda A$ $\Delta\lambda(R) = \lambda C - \lambda A$

SMSR4

The main mode is defined as the highest mode peak. The side modes are defined as the mode peaks adjacent to the main mode.



The analysis algorithm for the SMSR4 mode is as follows:

- 1. A mode search is performed to determine the mode peak.
- 1. The main mode point is assigned to PA. The wavelength of this point is assigned to λA .
- 3. The wavelength of the side mode that has a wavelength shorter than PA is assigned to λB . The wavelength of the side mode that has a wavelength longer than PA is assigned to λC .

If there is no mode peak whose wavelength is shorter than PA, λB is set to λA . If there is no mode peak whose wavelength is longer than PA, λC is set to λA .

- 4. The levels (linear values) of λA , λB , and λC are assigned to LA, LB, and LC, respectively.
- 5. SMSR and $\Delta\lambda$ are determined from the following equations.

SMSR(L) = LA / LBSMSR(R) = LA / LC $\Delta\lambda(L) = \lambda B - \lambda A$ $\Delta\lambda(R) = \lambda C - \lambda A$

Power Analysis Function

This function determines the total power by integrating the level values of the measured waveform.

Using the line marker search function and zoom area search function is convenient when performing power analysis.

The following table shows the details of power analysis parameters.

Parameter	Abbreviation	Default Value	Setting Range	Unit	Description
POWER OFFSET	OFST	0.00	-10.00 to 10.00	dB	Compensation value in power measurement

The algorithm is described below.

· The resolution bandwidth is determined for all display points.

(The values for $\lambda x = \lambda SHIFT + \lambda OFST$ are determined through interpolation using a table.)

In the vacuum wavelength mode (MEAS WL AIR/VACUUM key under SET UP), the following equation is used to obtain λx .

$$\lambda 0 = \lambda + \lambda SHIFT$$

 $\lambda x = \lambda 0 / N(\lambda 0) + \lambda OFST$

If the X-axis display mode is frequency, the equation below is used to convert the resolution bandwidth (frequency) Ri for all display points to wavelength values.

$$Ri = (\lambda i \times \lambda i \times Rfi)/C$$

where λi : Wavelength (nm) at each point

- Rfi: Resolution bandwidth (THz)
- C: Speed of light in the vacuum (1.99792458 x 10⁸[m/s])
- The resolution bandwidth for the ith point is assigned to Ri and the level to Li.
- The total power is determined from the following equation.

POWER = $\frac{\text{SPAN}}{\text{SAMPLE - 1}} \times \sum \frac{\text{Li}}{\text{Ri}} \times \text{POWEROFFSET}$


PMD Analysis Function

PMD values are analyzed from measured waveforms.

The following table shows the details of PMD analysis parameters.

Parameter	Abbreviation	Default Va	lue Setting Range	Unit	Description
THRESH	TH	10.00	0.01 to 50.00	dB	Threshold value

The algorithm is described below.



- A mode search is performed to obtain the mode peaks.
- Of these mode peaks, the ones whose level (LOG) is equal to or greater than the line that is below the peak level by the lower limit (THRESH) are considered valid mode peaks.
- The frequency of the leftmost valid mode peak is assigned to F1 (THz).
- The frequency of the rightmost valid mode peak is assigned to F2 (THz).
- The number of mode peaks between F1 and F2 is assigned to N.
- The PMD value is determined from the following equation. $\label{eq:PMD} \mathsf{PMD} = (\mathsf{N-1}) \, / \, (\mathsf{F2}\text{-}\mathsf{F1})$

DFB-LD Analysis Function

The following parameters for DFB-LD light sources are analyzed collectively.

- -XdB WIDTH (Center WL/SPWD)
- SMSR
- RMS
- POWER
- OSNR

The following table shows the details of DFB-LD analysis parameters.

Parameter	Abbreviation	Default Value	Setting Range	Unit	Description
	ALGO	THRESH	ENVELOPE/ THRESH/RMS/ PK-RMS	-	-
-XdB	THRESH	20.00	0.01 to 50.00	dB	-
WIDTH (Center WL/	THRESH2	20.00	0.01 to 50.00	dB	Valid only when ALGO is ENVELOPE.
SPWD)	К	1.00	1.00 to 10.00	-	-
	MODE FIT	OFF	ON / OFF	-	Valid only when ALGO is THRESH.
	MODE DIFF	3.00	0.01 to 50.00	dB	Invalid when ALGO is RMS.
SMSR	SMSR MODE	SMSR1	SMSR1/ SMSR2/ SMSR3/ SMSR4	-	-
	SMSR MASK	±0.00	0.00 to 99.99	nm	-
	MODE DIFF	3.00	0.01 to 50.00	dB	-
	ALGO	RMS	RMS/PK-RMS	-	-
RMS	THRESH	20.00	0.01 to 50.00	dB	-
	К	1.00	0.01 to 10.00	-	-
	MODE DIFF	3.00	0.01 to 50.00	dB	Invalid when ALGO is RMS.
POWER	SPAN	0.40	0.01 to 10.00	nm	-
	MODE DIFF	3.00	0.01 to 50.00	dB	-
	NOISE ALGO	PIT	AUTO-FIX/ MANUAL-FIX/ AUTO-CTR/ MANUAL-CTR/ PIT	-	-
	NOISE AREA	AUTO	AUTO/ 0.01 to 10.00	nm	-
	MASK AREA	-	-/ 0.01 to 10.00	nm	-
OSNR	FITTING ALGO	LINEAR	LINEAR/ GAUSS/ LORENZ/3RD POLY/4TH POLY/5TH POLY	-	-
	NOISE BW	0.10	0.01 to 1.00	nm	-
	SIGNAL POWER	PEAK	PEAK/ INTEGRAL	-	-
	INTEGRAL RANGE	10	10 to 999	GHz	-

For details on the DFB-LD analysis algorithms, see the data calculation algorithms for spectrum widths, the SMSR analysis algorithms, and the WDM analysis algorithms (OSNR analysis).

FP-LD Analysis Function

- The following parameters for FP-LD light sources are analyzed collectively.
 - SPECTRUM WIDTH
 - MEAN WAVELENGTH
 - TOTAL POWER
 - MODE NO.

The following table shows the details of $\ensuremath{\mathsf{FP-LD}}$ analysis parameters.

Parameter	Abbreviation	Default Value	Setting Range	Unit	Description
	ALGO	PK-RMS	ENVELOPE / THRESH / RMS / PK- RMS	-	
	THRESH	20	0.01 to 50.00	dB	
SPECTRUM WIDTH	THRESH2	20	0.01 to 50.00	dB	Valid only when ALGO is ENVELOPE.
	К	2	1.00 to 10.00	-	
	MODE FIT	OFF	ON / OFF	-	Valid only when ALGO is THRESH.
	MODE DIFF	3	0.01 to 50.00	dB	
	ALGO	PK-RMS	ENVELOPE / THRESH / RMS / PK- RMS	-	
	THRESH	20	0.01 to 50.00	dB	
MEAN WAVELENGTH	THRESH2	20	0.01 to 50.00	dB	Valid only when ALGO is ENVELOPE.
	К	2	1.00 to 10.00	-	
	MODE FIT	OFF	ON / OFF	-	Valid only when ALGO is THRESH.
	MODE DIFF	3	0.01 to 50.00	dB	
TOTAL POWER	OFFSET LEVEL	0	-10.00 to 10.00	dB	
	ALGO	PK-RMS	ENVELOPE / THRESH / RMS / PK- RMS	-	
	THRESH	20.00	0.01 to 50.00	dB	
MODE NO.	THRESH2	20.00	0.01 to 50.00	dB	Valid only when ALGO is ENVELOPE.
	К	1.00	1.00 to 10.00	-	
	MODE FIT	OFF	ON / OFF	-	Valid only when ALGO is THRESH.
	MODE DIFF	3.00	0.01 to 50.00	dB	

For details on the FP-LD analysis algorithms, see the data calculation algorithms for spectrum widths and power analysis algorithms.

LED Analysis Function

The following parameters for LED light sources are analyzed collectively.

- SPECTRUM WIDTH
- MEAN WAVELENGTH
- TOTAL POWER
- The following table shows the details of LED analysis parameters.

Parameter	Abbreviation	Default Value	Setting Range	Unit	Description
	ALGO	THRESH	ENVELOPE / THRESH / RMS / PK-RMS	-	
	THRESH	3	0.01 to 50.00	dB	
SPECTRUM WIDTH	THRESH2	20	0.01 to 50.00	dB	Valid only when ALGO is ENVELOPE.
	К	1	1.00 to 10.00	-	
	MODE FIT	OFF	ON / OFF	-	Valid only when ALGO is THRESH.
	MODE DIFF	3	0.01 to 50.00	dB	
	ALGO	RMS	ENVELOPE / THRESH / RMS / PK-RMS	-	
	THRESH	20	0.01 to 50.00	dB	
MEAN WAVELENGTH	THRESH2	20	0.01 to 50.00	dB	Valid only when ALGO is ENVELOPE.
WAVELENGTT	К	2	1.00 to 10.00		
	MODE FIT	OFF	ON / OFF	-	Valid only when ALGO is THRESH.
	MODE DIFF	3	0.01 to 50.00	dB	
TOTAL POWER	OFFSET LEVEL	0	-10.00 to 10.00	dB	

For details on the LED analysis algorithms, see the data calculation algorithms for spectrum widths and power analysis algorithms.

Appendix 4 WDM Analysis Function

This function provides the analyses of noise level and SNR in each mode within the measurement range of WDM waveforms.

Analysis Items

NO.: WAVELENGTH: LEVEL:	Channel number i Center wavelength λi of the channel Level (peak level – noise level) Li of the channel
OFFSET WL:	Relative wavelength to the wavelength of the reference channel (REF)
OFFSET LVL:	Relative level to the level of the reference channel (REF)
SPACING:	Wavelength spacing to the adjacent channel
LVL DIFF:	Level difference from then adjacent channel
NOISE:	Noise level LNi of the channel
SNR:	SNR value SNi of the channel
GRID WL:	Nearest grid wavelength to the channel
MEAS WL:	Center wavelength λi of the channel
REL WL:	Relative wavelength to the nearest grid wavelength of the channel

Note .

dBm/nm and dBm/THz figures are changed to dBm figures before execution.

Parameters

Channel Detection Parameters

Parameter Name	Default	Setting Range	Unit	Description
THRESH	20.0	0.1 to 99.9	dB	Threshold value for channel detection.
MODE DIFF	3.0	0.0 to 50.0	dB	Minimum value for peak/bottom difference during channel detection.
DISPLAY MASK	OFF	OFF, -100.0 to 0.0	dBm	Levels equal to or below this level are not detected as WDM channels.

Appendix 4 WDM Analysis Function


Parameter Name	Default	Setting Range	Unit	Description
NOISE ALGO	AUTO-FIX	AUTO-FIX MANUAL-FIX AUTO-CTR MANUAL-CTR PIT	-	Selection of algorithms for noise level measurement.
NOISE AREA	0.40nm	0.01 to 10.00nm	nm	A range of waveform data for use in noise level analysis is specified as a range centering on channel wavelengths. When N_ALGO is: • AUTO-FIX "AUTO" • MANUAL-FIX **.** • AUTO-CTR "Between Ch" • MANUAL-CTR "Between Ch" • PIT "-"
MASK AREA	0.20nm	0.01 to 10.00nm	nm	Specifies the signal optical spectrum range to be masked within the waveform data, while using the channel wavelength as its center. When N_ALGO is: • AUTO-FIX "–" • MANUAL-FIX When F_ALGO is LINEAR: "–" Other cases: Parameter value input • AUTO-CTR: "–" • MANUAL-CTR When F_ALGO is LINEAR: "–" Other causes: Parameter value input Limiter is applied during input to ensure NOISE AREA ≥ MASK AREA. • PIT "–"
FITTING ALGO	LINEAR	LINEAR GAUSS LORENZ 3RD POLY 4TH POLY 5TH POLY	-	Selection of a fitting algorithm for obtaining noise levels.
NOISE BW	0.10nm	0.01 to 1.00 nm	nm	Noise bandwidth setting.
DUAL TRACE	OFF	ON/OFF	-	OFF: The active trace is analyzed. ON: Wavelengths and levels are calculated from TRACE A. Noise levels are calculated from TRACE B.

Display Para	1	1		
Parameter Name	Default	Setting Range	Unit	Description
DISPLAY TYPE	ABSOLUTE	ABSOLUTE RELATIVE DRIFT(MEAS) DRIFT(GRID)	-	Setting of the format to display wavelengths, levels, noises, and SNRs, which are the results of analyses. ABSOLUTE: Absolute values RELATIVE: Relative values to the grid DRIFT(MEAS): Drift relative to a past measured wavelength DRIFT(GRID): Drift relative to the grid wavelength
CH RELATION	OFFSET	OFFSET SPACING	-	Setting of the format to display wavelengths between channels and level relative values during DISPLAY: ABSOLUTE. This parameter is valid only when DISPLAY is set to ABSOLUTE. OFFSET: Offset values by using one arbitrary channel as the reference. SPACING: Offset values compared to an adjacent channel
REF CH	HIGHEST	HIGHEST ****	-	Setting of the reference channel when CH RELATION is set to OFFSET. This parameter is valid only when DISPLAY is set to ABSOLUTE and also when CH RELATION is set to OFFSET. HIGHEST: A channel with the highest level is used as the reference. ****: The ****th channel is used as the reference.
MAX/MIN RESET	_	_	-	Tapping resets MAX/MIN. Button valid only when DISPLAY is set to DRIFT.
OUTPUT SLOPE	OFF	ON/OFF	-	ON/OFF of the function to obtain the least square approximation line of the channel peak.
POINT DISPLAY	ON	ON/OFF	-	ON/OFF of the function to display the data range used for fitting into the waveform window.

Other Settings

Parameter Name	Default	Setting Range	Unit	Description
SIGNAL POWER	PEAK	PEAK INTEGRAL	-	Setting of the signal power calculation method PEAK: Peak level value INTEGRAL: Level value obtained by integration
INTEGRAL RANGE	10	10 to 999	GHz	Setting of the integral range for determining the signal power Valid when the SIGNAL POWER setting is INTEGRAL. If the set value is Δ f, the integral is calculated in the range of channel center wavelength $\pm \Delta$ f.

Analysis Algorithm



- **1.** Channel detection is performed on the measured waveform data according to the following procedure.
 - All maximum points and minimum points are found to obtain mode peaks where peak/ bottom differences between maximum points and minimum points on both sides are equal to or greater than MODE DIFF.
 - Of the obtained mode peaks, only the ones whose level difference compared to the highest peak is equal to or greater than THRESH are chosen. However, mode peaks with a level difference equal to or less than DISPLAY MASK are excluded. The number of mode peaks chosen in this manner is the number of channels N.
- **1.** The wavelength λ 'i of each mode peak is determined.
- **3.** The center wavelengths λ 'i of each mode peak that are 2 points down A[dB] to the left and right from mode peak λ 'I are determined (where A[dB] is 3 dB or the MODE DIFF setting, whichever is smaller).
- **4.** The signal level LSi of each mode is determined according to the parameter SIGNAL POWER setting.
 - For "PEAK"
 - LSi = Level LPi of each mode peak
 - For "INTEGRAL"
 - LSi = The integral of the power value in the range of the center wavelength $\pm \Delta f \, [GHz]$ of each mode
 - (Δf: parameter INTEGRAL RANGE setting value)
- **5.** The noise area and mask area for performing the NOISE fitting are determined according to the setting of the parameter NOISE ALGO.

If the mask area is set outside the noise area when the channel wavelength λi is the center, the mask area and the noise area will be the same value.

- **6.** The measurement resolution RBi of each channel is determined from the values stored in the instrument.
- 7. Fitting waveforms are generated from the noise area and mask area determined in 5 according to the setting of the parameter FITTING ALGO, and the level at the center wavelength λi is determined as the noise level LNi.
- **8.** The signal level LSi and noise level LNi obtained in 4 and 7 are used to determine the level Li of each channel using the following equation.

Li = LSi(linear) – LNi(linear)

- 9. The normalized noise level LNNi is determined from the following equation. LNNi = [LNi(LOG) - 10×Log(RBi[nm])] + 10×Log(NBW) NBW =noise bandwidth (configurable parameter)
- 10. The mode peak level Li obtained in 8 and 9 and the normalized noise level LNNi are used to determine SNi from the following equation. SNi = Li - LNNi
- **11.** The analysis results found above are displayed according to the DISPLAY SETTING parameter.

Automatic Parameter Setting Function

This instrument has a function that automatically configures the noise area and mask area settings.

To perform automatic setting, set the algorithm to AUTO-FIX, AUTO-CTR, or PIT.

AUTO-FIX

Noise Algorithm

The left and right noise areas (NA_Ri, NA_Li) of each channel are determined according to the number of detected WDM channels as follows:

When the number of WDM channels "n" is 1

The measurement resolution of SNi calculation trace and the value of the noise measurement point NOISE AREA in accordance with the resolution are determined internally, and then the values are found from the following equations.

NA_Ri = λi + NOISE AREA NA_Li = λi – NOISE AREA

When the number of WDM channels "n" is 2 or more

The channel spacing of each channel (spacing of λi .) is determined. With the minimum spacing assigned to SPACING and using NOISE AREA = SPACING / 2, the NOISE AREA is determined using the following equation.

NA_Ri = λ i + NOISE AREA (i = 1,2,...,n) NA_Li = λ i – NOISE AREA (i = 1,2,...,n)

Fitting Algorithm

When AUTO-FIX is selected, LINEAR is used for the fitting algorithm. The details of the calculation are as follows:

- ELi and ERi are determined as the level (LOG) of each position of the noise areas NA_Li and NA_Ri.
- The data of the straight line connecting the two points of ELi and ERi is used to fill the inside of the fitting range.
- The level of λi of the data generated in the fitting is assigned to the noise level LNi.

Note -

Because LINEAR is used, it is not possible to set mask areas.

AUTO-CTR

Noise Algorithm

The left and right noise areas (NA_Ri, NA_Li) of each channel are determined according to the number of detected WDM channels as follows (while treating the center points between channels as NA Ri and NA Li).

When the number of WDM channels "n" is 1

The measurement resolution of SNi calculation trace and the value of the noise measurement point NOISE AREA in accordance with the resolution are determined internally, and then the values are found from the following equations.

NA_Ri = λ_i + NOISE AREA

NA_Li = λ_i – NOISE AREA

When the number of WDM channels "n" is 2 or more

 $\lambda N1 = (3\lambda_1 - \lambda_2)/2$

 $\lambda Ni = (\lambda_i - \lambda_{i-1})/2$

 $\lambda Nn+1 = (3\lambda_n - \lambda_{n-1})/2$

When the above values are calculated, the following results will be obtained.

i=1,2,...,n

NA_Li = λNi NA_Ri = λNi+1

Fitting Algorithm

When AUTO-CTR is selected, LINEAR is used for the fitting algorithm. The details of the calculation are as follows:

- ELi and ERi are determined as the level (LOG) of each position of the noise areas NA Li and NA Ri.
- The data of the straight line connecting the two points of ELi and ERi is used to fill the inside of the fitting range.
- The level of λ i of the data generated in the fitting is assigned to the noise level LNi.

Note -

Because LINEAR is used, it is not possible to set mask areas.

PIT

Noise Algorithm

For each channel, the minimum level position in the area up to the next channel is determined from the measured waveform and used as NOISE AREA. For the left-most and right-most channels, the internal NOISE AREA is used for the outer NOISE AREA.

When the number of WDM channels "n" is 1

The measurement resolution of SNi calculation trace and the value of the noise measurement point NOISE AREA in accordance with the resolution are determined internally, and then the values are found from the following equations.

 $NA_Ri = \lambda i + NOISE AREA$

NA_Li = λi – NOISE AREA

When the number of WDM channels "n" is 2 or more

```
i=1

NA_Li = \lambda i - (\lambda Ni - \lambda i)

NA_Ri = \lambda Ni

i=2,3,...,n-1

NA_Li = \lambda N(i - 1)

NA_Ri = \lambda Ni

i=n

NA_Li = \lambda N(i - 1)

NA_Ri = \lambda i + (\lambda i - \lambda N(i - 1))
```

Fitting Algorithm

When PIT is selected, LINEAR is used for the fitting algorithm. The details of the calculation are as follows:

- ELi and ERi are determined as the level (LOG) of each position of the noise areas NA_Li and NA_Ri.
- The data of the straight line connecting the two points of ELi and ERi is used to fill the inside of the fitting range.
- The level of λi of the data generated in the fitting is assigned to the noise level LNi.

Note.

Because LINEAR is used, it is not possible to set mask areas.

DUAL TRACE Parameter Setting

This function enables more precise analyses by measuring waveforms with different measurement resolutions at trace A and trace B and also by performing measurements with resolutions different in noise level from the signal level of each channel. When "DUAL TRACE" is ON, targets for the analysis of each trace are as follows:


TRACE A: trace subject to channel detection

TRACE A: calculation traces λi and Li

TRACE B: noise level LNi calculation trace

OUTPUT SLOPE Function

The parameter "OUTPUT SLOPE" provides a function to obtain the least square approximation curve of channel peaks. his function makes it possible to measure gain tilts. If "OUTPUT SLOPE" is set to ON, results will be displayed in the waveform display section and in the analysis table.



Items to be Displayed When DISPLAY is Set ABSOLUTE

Results of analyses are displayed with absolute values.

YOKOGAWA 🔶					18 Feb 16 19:31	= Menu
Δ : TR A Δ0001: 1550.121 TR A Δ0002: 1550.921 TR A Δ0003: 1551.721	0nm -10.19dB 0nm -9.77dB	m		B	FIX /BLK FIX /BLK FIX /BLK FIX /BLK FIX /BLK	Spec Width THRESH
TR A Δ0004: 1552.531 Δ0005:	0nm -8.97dB	m			FIX /BLK FIX /BLK	Analysis 1
<meas. conditions=""></meas.>		_		SPEED: 1>		DFB-LD
START: 1546.291 nm			R: 1551.291 nm		nm	
RES: 0.1 nm	SENS: MID	A\	/G: 1	SMPL: 100	L(M)	Analysis 2
	-+				·	WDM
0.0 REF	-+	++	+.			Analysis
-10.0	.Ψ.	Ψ.	Q	ζ		Execute
		f-li	- <u>+</u> ++/	· · · · · · · · · · · · · · · · · · ·		WDM
-20.0		ŀ-ŧ	-+	· {		Spec Width
5.0	/	• × · /	• X × 7	• ×		(mesn
dB/D						Parameter
-40.0 1549.116 nm		ING 1551.46		0.47 nm/D	1553.816 nm	Setting
		MODE DIFE: 3.0dE		0.47 nm/D	1553.816 nm	
	N AREA:AUTO	M AREA:	F ALG:	INEAR NOIS	E BW:0.10nm	Switch
NO. WAVELENGTH	LEVEL [dBm]	OFFSET WL	OFFSET LEVEL	NOISE [dBm/NBW]	SNR [dB]	Display TRACE&TABLE
1 1550.1173	-10,223	-2.4091	-1.205	-30,307	20.083	F
2 1550.9191	-10.238	-1.6073	-1.219	-29.701	19.463	Auto Analysis
3 1551.7233	-9.818	-0.8031	-0.800	-29.165	19.347	OFF ON
4 1552.5264	-9.018	(REF)	(REF)	-28.701	19.683	
						Analysis
						More 1/2
[more 1/2
	VL WL NOI SRC	1-2 WL OFS A	NA SRC SCL REF	CTR 1-2 OTH	RPT SGL STP	

Explanations of displayed items

•	
NO:	Channel number
WAVELENGTH:	Center wavelength λi of the channel
LEVEL:	Level (peak level – noise level) of the channel
OFFSET WL:	Relative wavelength to the wavelength of the reference channel (REF)
OFFSET LVL:	Relative wavelength to the wavelength of the reference channel (REF)
SPCAING:	Wavelength spacing to the adjacent channel
LVL DIFF:	Level difference from then adjacent channel
NOISE:	Noise level of the channel
SNR:	SNR value of the channel


- OFFSET WL/LVL is displayed when the parameter CH RELATION is "OFFSET." SPACING and LVL DIFF are displayed when the parameter CH RELATION is "SPACING."
- When ABSOLUTE and CH RELATION are OFFSET, it is possible either to set the reference channel to the mode peak with the highest level or to set a mode peak that will become the reference arbitrarily.
 - When REF CH is HIGHEST

The WDM mode peak with the highest level shall be the reference. The wavelength difference and level difference (LOG) compared to it shall be OFFSET WL and OFFSET LVL of each WDM mode peak.

When REF CH is ***
 REF CHANNEL*** shall be the reference. The wavelength difference and level difference (LOG) against it shall be OFFSET WL and OFFSET LVL of each WDM mode peak. (If the ***th mode peak does not exist, the WDM mode peak on the longest wavelength shall be the reference.)

RELATIVE

Of the analysis results, wavelength values are displayed as relative values to the values in the grid table.




Explanations of displayed items

•	
NO:	Channel number
GRID WL:	Grid wavelength of the channel
MEAS WL:	Center wavelength λi of the channel
REL WL:	Relative wavelength to the grid wavelengths of the channel
MEAS LVL:	Level (peak level – noise level) of the channel
NOISE:	Noise level of the channel
SNR:	SNR value of the channel

DRIFT(MEAS)

Wavelengths measured previously are used as references to display wavelength/level changes (drifts).



Explanations of displayed items


NO:	Channel number
REF WL:	Reference wavelength of the channel (previous wavelength measured)
MEAS WL:	Center wavelength λi of the channel
DIFF MAX (wavelength):	Maximum value of the relative wavelength to the reference wavelength of the channel
DIFF MIN (wavelength):	Minimum value of the relative wavelength to the reference wavelength of the channel
REF LVL:	Reference level of the channel (previous measurement level)
MEAS WL:	Measurement level of the channel
DIFF MAX (level):	Maximum value of the relative level to the reference level of the channel
DIFF MIN (level):	Minimum value of the relative level to the reference level of the channel

Reference wavelength/level can be changed under the following conditions.

- Active trace waveform data when MAX/MIN RESET is set by the parameter.
- The first waveform data measured when wavelength axes (SPAN WL/START WL/ STOP WL) were changed according to the measurement conditions.

DRIFT(GRID)

Grid wavelengths are used as references to display wavelength/level changes (drifts). Note that reference levels are previous measurement levels.



Explanations of displayed items

NO:	Channel number
GRID WL:	Reference wavelength of the channel (grid wavelength)
MEAS WL:	Center wavelength λi of the channel
DIFF MAX (wavelength):	Maximum value of the relative wavelength to the reference wavelength of the channel
DIFF MIN (wavelength):	Minimum value of the relative wavelength to the reference wavelength of the channel
REF LVL:	Reference level of the channel (previous measurement level)
MEAS WL:	Measurement level of the channel
DIFF MAX (level):	Maximum value of the relative level to the reference level of the channel
DIFF MIN (level):	Minimum value of the relative level to the reference level of the channel

- Absolute values and reference values to the grid table are displayed. The grid table can be freely configured.
- Reference wavelengths/levels can be changed under the following conditions:
 - When MAX/MIN RESET is set by the parameter, reset is performed by the active trace waveform data.
 - Reset is performed by the first waveform data that was measured when wavelength axes (SPAN WL/START WL/STOP WL) were changed by measurement conditions.

Appendix 5 Optical Amp Analysis Function

This function analyzes gains and NF (noise figures) of optical fiber amplifiers.

Analysis Items

- λi Center wavelength of each channel. Center frequency in frequency mode.
- LINi Signal optical power of each channel (after OFFSET compensation)
- LOUTi Output optical power of each channel (after OFFSET compensation)
- LASEi ASE power of each channel (after OFFSET compensation)
- Rbi Measurement resolution of each channel
- Gi Gain of each channel
- Nfi NF of each channel

Parameters

Channel Detection Parameters

Parameter Name	Default	Setting Range	Unit	Description		
THRESH	20.0	0.1 to 99.9	dB	Threshold value for channel detection.		
MODE DIFF	3.0	0.0 to 50.0	dB	Minimum value for peak/bottom difference during channel detection.		
OFFSET(IN)	0.00	-99.99 to 99.99	dB	Level offset value of signal optical power.		
OFFSET(OUT)	0.00	-99.99 to 99.99	dB	Level offset value of output optical power.		
ASE ALGO	AUTO-FIX	AUTO-FIX MANUAL-FIX AUTO-CTR MANUAL-CTR	-	Selection of the algorithm for ASE level measurement.		
FITTING AREA	0.40nm	0.01 to 10.00nm	nm	A range of waveform data for use in ASE level analysis is specified as a range centering on channel wavelengths. When A_ALGO is: AUTO-FIX: "AUTO" • MANUAL-FIX: **.** • AUTO-CTR: "Between Ch" • MANUAL-CTR: "Between Ch"		
MASK AREA	0.20nm	0.01 to 10.00nm	nm	 Specifies the signal optical spectrum range to be masked within the waveform data, while using the channel wavelength as its center. When A_ALGO is: AUTO-FIX: "" MANUAL-FIX When F_ALGO is LINEAR: "" Other cases: Parameter value input AUTO-CTR: "" MANUAL-CTR When F_ALGO is LINEAR: "" Other cases: Parameter value input LINEAR: "" MANUAL-CTR When F_ALGO is LINEAR: "" Other cases: Parameter value input AUTO-CTR: ALGO is LINEAR: "" MANUAL-CTR When F_ALGO is LINEAR: "" Other cases: Parameter value input 		
FITTING ALGO	LINEAR	LINEAR GAUSS LORENZ 3RD POLY 4TH POLY 5TH POLY	-	Selection of a fitting algorithm for obtaining ASE levels.		
POINT DISPLAY	ON	ON / OFF	-	ON/OFF of the function to display the data range used for fitting into the waveform window.		

Appendix 5 Optical Amp Analysis Function

RES BW	CAL DATA	MEASURED CAL DATA	-	Sets the method for calculating the measurement resolution RBi of each channel. MEASURED: The value of the THRESH 3dB width is determined for each channel from the TRACE B waveform and set to RBi. CAL DATA: The resolution bandwidth stored in the instrument is set to RBi.
SHOT NOISE	ON	ON / OFF	-	Selects whether the Shot Noise component is included in computation of the NF value. ON: Included. OFF: Not included.

Analysis Algorithm

- 1. WDM analysis is performed on the signal optical waveform data of TRACE A to perform channel detection. However, the DISPLAY MASK parameter is not used.
- 1. The center wavelength λi of each channel and signal optical level LIN'i of TRACE A optical signal are determined.
- 3. The output optical level LOUT'i of each channel is determined from the output optical waveform data of TRACE B.
- 4. LINi and LOUTi, which are generated by compensating OFFSET (IN,OUT) for signal optical level and output optical level, respectively are determined.
- 5. The fitting area and mask area for performing the ASE fitting are determined according to the setting of the parameter ASE ALGO.
- Measurement resolution RBi of each channel is determined.
 MEASURED: The value of the THRESH 3dB width for each channel is determined

from the TRACE B waveform and assigned to RBi. CAL DATA: The resolution bandwidth stored in the instrument is assigned to RBi.

- 7. The signal optical SE elements contained in the output optical spectrum is removed in the following order, and the result is written into TRACE C.
 - Levels (linear) on both sides of the channel of the fitting area that was obtained in 5 are determined.
 - The obtained levels on both sides are used to obtain the provisional ASE level LB'i via the linear interpolation.
 - LBi, which is generated by compensating OFFSET (OUT) for the provisional ASE level LB'i is determined.
 - The provisional gain G'i is determined from the following equation. G'i=(LOUTi – LBi)/LINi
 - The TRACE A data (linear) is multiplied by the provisional gain G'i and subtract the result from the TRACE B data (linear). Then, the result is written into TRACE C.
- In the TRACE C data (linear) generated in 7, fitting is performed according to the settings of the parameter FITTING ALGO, and the estimated ASE spectrum is created in TRACE C.

The data used in the fitting is from the range of the center wavelength of each channel ± FITTING AREA to the range of MASK AREA.

The level at λi in TRACE C is determined in terms of the ASE level LASE'i (linear). Then, LASEi, which is generated by compensating OFFSET (OUT), is determined.

Gain G and NF (linear) are calculated from the following equations.

Gain G

Gi = (LOUTi – LASEi)/LINi

NF value (during the air wavelength mode)

NFi =
$$\frac{N(\lambda_i)^2}{h \times c^2} \times \frac{\lambda_i^3}{RBi} \times \frac{LASEi}{G} + \frac{1}{G}$$
 (SHOT NOISE parameter: ON)

NFi =
$$\frac{N(\lambda_i)^2}{h x c^2} x \frac{\lambda_i^3}{RBi} x \frac{LASEi}{G}$$
 (SHOT NOISE parameter: OFF)

NF value (during the vacuum wavelength mode)

$$NFi = \frac{1}{h \times c^2} \times \frac{\lambda i^3}{RBi} \times \frac{LASEi}{G} + \frac{1}{G}$$
(SHOT NOISE parameter: ON)
$$NFi = \frac{1}{h \times c^2} \times \frac{\lambda i^3}{RBi} \times \frac{LASEi}{G}$$
(SHOT NOISE parameter: OFF)

where $N(\lambda i)$: Refraction index of the air

C: Speed of light in the vacuum (1.99792458 x 10⁸[m/s])

h: Planck's constant 6.6260755 × 10⁻³⁴ [J•s]

• Nfi, Gi, and LASEi are converted into LOG.

Automatic Parameter Setting Function

This instrument has a function that automatically configures the fitting area and mask area settings.

AUTO-FIX

ASE Algorithm

The fitting algorithm is LINEAR.

Since the algorithm is LINEAR, the mask area setting will not be required. The left and right fitting areas (NA_Ri, NA_Li) of each channel are determined according to the number of detected channels as follows:

When the number of channels "n" is 1

The measurement resolution of trace B and the value of the noise measurement point FITTING AREA in accordance with the resolution are determined internally, and then the values are found from the following equations.

NA_Ri = λ i + FITTING AREA NA_Li = λ i - FITTING AREA

When the number of channels "n" is 2 or more

The channel spacing of each channel (spacing of λi .) is determined. With the minimum spacing assigned to SPACING and using FITTING AREA = SPACING / 2, the FITTING AREA is determined using the following equation.

FITTING AREA = SPACING / 2

NA_Ri = λi + FITTING AREA (i =1,2,...,n) NA Li = λi - FITTING AREA (i =1,2,...,n)

AUTO-CTR

ASE Algorithm

The fitting algorithm is LINEAR.

Since the algorithm is LINEAR, the mask area setting will not be required. The left and right fitting areas (NA_Ri, NA_Li) of each channel are determined according to the number of detected channels as follows (while treating the center points between channels as NA_Ri and NA_Li).

When the number of channels "n" is 1

The measurement resolution of trace B and the value of the noise measurement point FITTING AREA in accordance with the resolution are determined internally, and then the values are found from the following equations.

NA_Ri = λi + FITTING AREA NA Li = λi – FITTING AREA

When the number of channels "n" is 2 or more

$$\begin{split} \lambda N1 &= (3\lambda_1 - \lambda_2) \,/\, 2 \\ i &= 2, 3, \dots, n \\ \lambda Ni &= (\lambda_i + \lambda_{i-1}) \,/\, 2 \\ \lambda Nn &+ 1 &= (3\lambda - \lambda_{n-1}) \,/\, 2 \\ \end{split}$$
 When the above values are calculated, the following results will be obtained. i &= 1, 2, \dots, n \end{split}

 $NA_Li = \lambda Ni$

 $NA_Ri = \lambda N_{i+1}$

Appendix 6 Optical Filter Analysis Function

FILTER PEAK Analysis Function

This function analyzes collectively the measured waveforms of optical filters via multiple parameters.


It can be used for filter analysis only if the number of modes is one. Items and algorithms for analysis are the same as in the AQ6317 series.

Analysis Items

PEAK LVL: Peak level PEAK WL: Peak wavelength CENTER WL: Center wavelength SPECTRUM WIDTH: Wavelength width at threshold value TH RIPPLE WIDTH: Ripple width CROSS TALK: Crosstalk

Parame	eters				
Item	Parameter Name	Default	Setting Range	Unit	Description
PEAK LEVEL	SW	ON	ON or OFF	-	Display ON/OFF switch.
PEAL WL	SW	ON	ON or OFF	-	Display ON/OFF switch.
	SW	ON	ON or OFF	-	Display ON/OFF switch.
	ALGO	THRESH	THRESH RMS	-	Selection of algorithm for spectrum width.
	THRESH LVL	THRESH : 3.00 RMS : 3.00	0.1 to 50.0	dB	Threshold value for channel detection.
CENTER WL	к	THRESH : 1.00 RMS : -	1.00 to 10.00	-	Multiplying factor Valid only when ALGO is THRESH.
	MODE FIT	THRESH : OFF RMS : -	ON or OFF	-	Whether "half of maximum point" is set to the mode peak. Valid only when ALGO is THRESH.
	MODE DIFF	THRESH : 3.00 RMS : -	0.0 to 50.0	dB	Minimum value of the peak/bottom differ- ence during channel detection. Valid only when ALGO is THRESH.
	SW	ON	ON or OFF	-	Display ON/OFF switch.
	ALGO	THRESH	THRESH RMS	-	Selection of algorithm for spectrum width.
SPECTRUM	THRESH LVL	THRESH : 3.00 RMS : 3.00	0.1 to 50.0	dB	Threshold value for channel detection.
WIDTH	к	THRESH : 1.00 RMS : -	1.00 to 10.00	-	Multiplying factor Valid only when ALGO is THRESH.
	MODE FIT	THRESH : OFF RMS : -	ON or OFF	-	Whether "half of maximum point" is set to the mode peak. Valid only when ALGO is THRESH.
SPECTRUM WIDTH	MODE DIFF	THRESH : 3.00 RMS : -	0.0 to 50.0	dB	Minimum value of the peak/bottom differ- ence during channel detection. Valid only when ALGO is THRESH.
	SW	ON	ON or OFF	-	Display ON/OFF switch.
RIPPLE	THRESH LVL	3	0.1 to 50.0	dB	Threshold value for channel detection.
WIDTH	MODE DIFF	0.5	0.000 to 50.000	dB	Minimum value for peak/bottom difference during channel detection.
	SW	ON	ON or OFF	-	Display ON/OFF switch.
	ALGO	THRESH	THRESH PK LVL GRID	-	Selection of algorithm for spectrum width.
	THRESH LVL	THRESH : 3.00 PK LVL : - GRID : -	0.1 to 50.0	dB	Threshold value for channel detection. Valid only when ALGO is THRESH.
CROSS TALK	К	THRESH : 1.00 PK LVL : - GRID : -	1.00 to 10.00	-	Multiplying factor Valid only when ALGO is THRESH.
	MODE FIT	THRESH : OFF PK LVL : - GRID : -	ON or OFF	-	Whether "half of maximum point" is set to the mode peak. Valid only when ALGO is THRESH.
	MODE DIFF	THRESH : 3.00 PK LVL : - GRID : -	0.0 to 50.0	-	Minimum value of the peak/bottom differ- ence during channel detection. Valid only when ALGO is THRESH.
	CH SPACE	0.4	0.00 to 50.00	nm	Channel spacing setting.
	SEARCH AREA	0.01	0.01 to 10.00	nm	Analysis range setting. Valid only when ALGO is GRID.

Analysis Details



- (1) Peak level (PEAK LVL)
- (2) Peak wavelength (PEAK WL)
- (3) Center wavelength (MEAN WL):

value of the level at the waveform peak position value of the wavelength at the waveform peak position

value of the center wavelength at the threshold value TH

spectrum width at the threshold value TH

- (4) Spectrum width (SPEC WD):
- (5) Cross talk (CRS TALK)
 - In the case of THRESH / PEAK LV algorithms

The value of the level on the reference wavelength (MEAN WL for THRESH and PEAK WL for PEAK LV) is determined. Also, the value of the level at the wavelength which is $\pm\lambda$ CH SPACE[nm] away from the reference wavelength is determined. Then, the difference in level value between the two is assumed to be the cross talk.

In the case of ITU-T algorithms

The ITU-T grid wavelength, which is nearest to the peak wavelength, is assigned to the reference wavelength. The difference between the bottom level within the range of the reference wavelength $\pm\lambda$ SEARCH AREA[nm] and the peak level within the range of the position $\pm\lambda$ CH SPACE[nm] away from the reference wavelength $\pm\lambda$ SEARCH AREA[nm] are assumed to be the cross talk.

(6) Ripple width (RIPPLE WD) A spectrum width search is performed. The value of the peak level – bottom level within the obtained spectrum width is assumed to be the ripple width.

Note .

- Unless the parameter "MODE DIFF" is set to a value smaller than uneven portions of a waveform regarded as a ripple, RIPPLE = 0 will result.
- RIPPLE = 0 if the parameter setting is "THRESH" < "MODE DIFF"

FILTER BOTTOM Analysis Function

This function analyzes collectively the measured waveforms of optical filters via multiple parameters.

It is used for filter analysis if the number of modes is one. Items and algorithms for analysis are the same as in the AQ6317 series.


Analysis Items

BOTTOM LVL:	Bottom level
BOTTOM WL:	Bottom wavelength
CENTER WL:	Center wavelength
NOTCH WIDTH:	Notch width
CROSS TALK:	Crosstalk

Parameters

Item	Parameter Name	Default	Setting Range	Unit	Description
BOTTOM LEVEL	sw	ON	ON or OFF	-	Display ON/OFF switch.
BOTTOM WL	SW	ON	ON or OFF	-	Display ON/OFF switch.
	SW	ON	ON or OFF	-	Display ON/OFF switch.
	ALGO	BOTTOM	PEAK BOTTOM	-	Selection of algorithm for spectrum width.
CENTER WL	THRESH LVL	3	0.1 to 50.0	dB	Threshold value for channel detection.
	MODE DIFF	3	0.0 to 50.0	dB	Minimum value for peak/bottom difference during channel detection.
NOTCH	SW	ON	ON or OFF	-	Display ON/OFF switch.
	ALGO	BOTTOM	PEAK BOTTOM	-	Selection of algorithm for spectrum width.
WIDTH	THRESH LVL	3	0.1 to 50.0	dB	Threshold value for channel detection.
	MODE DIFF	3	0.0 to 50.0	dB	Minimum value for peak/bottom difference during channel detection.
					Valid only when ALGO is THRESH.
	SW	ON	ON or OFF	-	Display ON/OFF switch.
	ALGO	BOTTOM	PEAK BOTTOM BOTTOM_LVL GRID	-	Selection of algorithm for spectrum width.
CROSS TALK	THRESH LVL	3	0.1 to 50.0	dB	Threshold value for channel detection. Valid when ALGO is PEAK/ BOTTOM.
	MODE DIFF	3	00 to 50.0	-	Multiplying factor Valid only when ALGO is THRESH.
	CH SPACE	0.4	0.0 to 50.00	nm	Channel spacing setting.
	SEARCH AREA	0.01	0.01 to 10.00	nm	Analysis range setting. Valid only when ALGO is GRID.

Analysis Details



(1) Bottom level (BTM LVL)

Value of level at the waveform bottom position

(2) Bottom wavelength (BTM WL) Value of wavelength at the waveform bottom position (3) Center wavelength (MEAN WL) Value of center wavelength at the threshold

value TH

(4) Notch width (NOTCH WD) Notch width at the threshold value TH

(5) Cross talk (CRS TALK)

In the case of PEAK / BOTTOM / BOTTOM LV algorithms

The level value at the reference wavelength (MEAN WL for PEAK/BOTTOM, BOTTOM WL for BOTTOM LV) is determined. Also, the level value at the wavelength which is $\pm\lambda$ CH SPACE[nm] away from the reference wavelength is determined. Then, the difference in level value between the two is assumed to be the cross talk.

In the case of ITU-T algorithms

The ITU-T grid wavelength, which is nearest the bottom wavelength, is assigned to the reference wavelength. The difference between the peak level within the range of the reference wavelength $\pm\lambda$ SEARCH AREA[nm] and the bottom level within the range of the position $\pm\lambda$ CH SPACE[nm] away from the reference wavelength $\pm\lambda$ SEARCH AREA[nm] is assumed to be the cross talk.

WDM FILTER PEAK Analysis Function

This function analyzes collectively multiple items for each channel via the measured waveforms of multi-channel optical filters.

Unlike the FILTER PEAK analysis, filter analysis is possible on multi-mode waveforms.

Analysis Items

Analysis Item	Description
Nominal Wavelength	Reference wavelength/frequency of each channel.
Peak Wavelength / Level	Peak wavelength/frequency and level of each channel.
xdB Width / Center Wavelength	xdB width of each channel and its center wavelength/ frequency.
xdB stop-band	Wavelength width/frequency width across xdB of each channel.
xdB pass-band	Pass band xdB from the bottom within the test band of each channel.
Ripple	Max-min level (flatness) within the test band of each channel.
Cross Talk	Difference in level from the position xnm away from each channel.

Parameters

Item	Parameter Name	Default	Setting Range	Unit
	ALGO	MEAN	PEAK / MEAN / GRID/ GRID FIT	-
Channel Detection,	MODE DIFF	3	0.1 to 50.0	dB
Nominal Wavelength	THRESH	20	0.1 to 99.9	dB
	TEST BAND	0.1	0.001 to 9.999	nm
Peak Wavelength/ Level	SW	ON	ON / OFF	-
XdB Width	SW	ON	ON / OFF	-
Center Wavelength	THRESH	3	0.1 to 50.0	dB
VdD stan hand	SW	ON	ON / OFF	-
XdB stop-band	THRESH LVL	-10	-90.00 to 30.00	dB
	SW	ON	ON / OFF	-
XdB pass-band	THRESH	3.0	0.1 to 50.0	dB
	TEST BAND	0.20	0.01 to 99.99	nm
Diante	SW	ON	ON / OFF	-
Ripple	TEST BAND	0.20	0.01 to 99.99	nm
	SW	ON	ON / OFF	-
Cross Talk	SPACING	0.80	0.01 to 99.99	nm
	TEST BAND	0.20	0.01 to 99.99	nm

Analysis Algorithm

Channel Detection, Nominal Wavelength

Parameter THRESH MODE DIFF ALGO TEST BAND

Procedure

PEAK

- Channel: Each mode peak detected via a mode search (except for the mode peaks at levels which are lower than the mode at the highest level by THRESH[dB] or less.)
- · Reference wavelength: Wavelength of each mode peak.
- Peak wavelength/level: Wavelength and level of each mode peak.

MEAN

- Channel: Each mode peak detected via a mode search (except for the mode peaks at levels which are lower than the mode at the highest level by THRESH[dB] or less.)
- Reference wavelength: 3 dB center wavelength at each mode peak.
- Peak wavelength/level: Wavelength and level of each mode peak.

GRID FIT

- Channel: Modes within the range of grid wavelength ± (TEST BAND/2) among the mode peaks detected via a mode search (except for the mode peaks at levels which are lower than the mode at the highest level by THRESH[dB] or less.) If the number of relevant modes in one grid is more than one, only the mode at the highest level will be regarded as the channel.
- Reference wavelength: Grid wavelength nearest to each channel.
- Peak wavelength/level: Wavelength and level of the mode peak of each channel.

GRID

- Channel: A mode search is not be performed. All grid wavelengths within the range of analysis are used as channels.
- Reference wavelength: Grid wavelength of each channel
- Peak wavelength/level: Peak wavelength and peak level within the range of grid wavelength ± (TEST BAND/2) of each channel.


PEAK LVL/PEAK WL

Parameter THRESH MODE DIFF

Procedure

- WDM analysis is performed on the waveform data of an active trace, and channels are detected. However, the DISPLAY MASK parameter is not used.
- The mode peak wavelength (PEAK WL) of each channel of the active trace and its signal optical level (PEAK LVL) are determined.

XdB Width




Parameter

THRESH

Procedure

The width (xdB_Width), which is below the peak level LPi of each channel by the parameter THRESH_LEVEL both on the left and on the right, and its center wavelength are determined.

The algorithm for analysis is the same as the algorithm THRESH of the spectrum width.




Parameter

THRESH

Procedure

The width (xdB_stop-band) that centers on the reference wavelength λi of each channel and that is located below by the parameter THRESH_LEVEL both on the left and on the right is determined.


XdB pass-band



Parameter

THRESH TEST BAND

- A bottom search is performed within the range of parameter Test_Band/2 by centering on reference wavelength λi of each channel and obtain the bottom level (LBi).
- The width (xdB_pass-band) that is below the bottom level LBi obtained in the above procedure by the parameter THRESH _LEVEL is determined.




Parameter

TEST BAND

Procedure

- A peak search and bottom search are performed within the range of parameter Test_ Band/2 by centering on the reference wavelength λi of each channel, and the peak level (LP'i) and the bottom level (LB'i) are determined.
- The peak level (LP'i) and bottom level (LB'i) obtained in the above procedure are used to obtain the ripple from the following equation:

Ripple = LP'I – LB'i



Parameter SPACING TEST BAND

- A bottom search is performed within the range of parameter Test_Band/2 by centering on reference wavelength (λ i) of each channel and obtain the bottom level (LBi).
- A peak search is performed within the range of parameter Test_Band/2 while centering on the point (λi-λSP) that is obtained by subtracting the parameter SPACING from the reference wavelength λi of each channel. Then, the peak level (LPLi) is determined.
- A peak search is performed within the range of parameter Test_Band/2 while centering on the point (λi+λSP) that is obtained by adding the parameter SPACING to the reference wavelength λi of each channel. Then, the peak level (LPRi) is determined.
- The values obtained in the above procedure are used to obtain the left and right cross talks (XTLi, XTRi) of each channel from the following equations:
 XTLi = LBi LPLi
 XTRi = LBi LPRi

WDM FILTER BOTTOM Analysis Function

This function analyzes collectively multiple items for each channel via the measured waveforms of multi-channel optical filters.

Unlike the FILTER BOTTOM analysis, filter analysis is possible on multi-mode waveforms.

Analysis Items

Analysis Item	Description
Nominal Wavelength	Reference wavelength/frequency of each channel.
Bottom Wavelength / Level	Peak wavelength/frequency and level of each channel.
xdB Notch Width frequency. / Center Wavelength	xdB notch width of each channel and its center wavelength/
xdB stop-band xdB Elimination band	Wavelength width/frequency width across xdB of each channel. Elimination band xdB from the bottom within the test band of each channel.
6Ripple	Max-min level (flatness) within the test band of each channel.
Cross Talk	Difference in level from the position xnm away from each channel.

Parameters

Item	Parameter Name	Default	Setting Range	Unit
Channel Detection,	ALGO	NOTCH(B)	PEAK / NOTCH(P)/ NOTCH(B) / GRID / GRID FIT	-
Nominal	MODE DIFF	3.0	0.1 to 50.0	dB
Wavelength	THRESH	20.0	0.1 to 99.9	dB
	TEST BAND	0.100	0.001 to 9.999	nm
Bottom Wavelength/Level	SW	ON	ON / OFF	-
	SW	ON	ON / OFF	-
XdB Width Center Wavelength	ALGORITHM	NOTCH(B)	NOTCH(P) / NOTCH(B)	-
Center wavelength	THRESH	3.0	0.1 to 50.0	dB
	SW	ON	ON / OFF	-
XdB stop-band	THRESH	-10.000	-90.000 to 30.000	dB
	SW	ON	ON / OFF	-
XdB Elimination ban	THRESH	3.0	0.1 to 50.0	dB
ban	TEST BAND	0.20	0.01 to 99.99	nm
Dinala	SW	ON	ON / OFF	-
Ripple	TEST BAND	0.20	0.01 to 99.99	nm
	SW	ON	ON / OFF	-
Cross Talk	SPACING	0.80	0.01 to 99.99	nm
	TEST BAND	0.20	0.01 to 99.99	nm

Analysis Algorithm NOMINAL WAVELENGTH Parameter ALGO MODE DIFF THRESH TEST BAND Procedure BOTTOM Channel: Each mode bottom detected by a mode search (except for the mode bottoms at levels which are above the mode at the lowest level by THRESH[dB] or more.) · Reference wavelength: Wavelength of each mode bottom. • Bottom wavelength/level: Wavelength/level of each mode bottom. NOTCH(B) · Channel: Each mode bottom detected by a mode search (except for the mode bottoms at levels which are above the mode at the lowest level by THRESH[dB] or more.) Reference wavelength: 3 dB-center wavelength with each mode bottom as the reference (ALGO=BOTTOM). · Bottom wavelength/level: Wavelength and level of each mode peak. NOTCH(P) Channel: Each mode peak detected via a mode search (except for the mode bottoms at levels which are above the mode at the lowest level by THRESH[dB] or more.) · Reference wavelength: 3 dB-center wavelength with each mode bottom as the reference (ALGO=PEAK). • Bottom wavelength/level: Wavelength/level of each mode bottom. GRID FIT Channel: Modes within the range of grid wavelength ± (TEST BAND/2) among the mode bottoms detected via a mode search (except for the mode bottoms at levels which are above the mode at the lowest level by THRESH[dB] or more.) If the number of relevant modes in one GRID is more than one, only the mode at the lowest level will be regarded as the channel. · Reference wavelength: Grid wavelength nearest to each channel. Bottom wavelength/level: Wavelength and level of the mode bottom of each channel. GRID Channel: A mode search is not be performed. All grid wavelengths within the range of analysis are used as channels. Reference wavelength: Grid wavelength of each channel Peak wavelength/level: Bottom wavelength and bottom level within the range of ٠ grid wavelength ± (TEST BAND/2) of each channel.

BOTTOM WL / BOTTOM LVL

Parameter THRESH MODE DIFF

Procedure

The wavelength λ 'i of the mode bottom of each channel and its signal optical level LBi are determined.

XdB_NOTCH_WIDTH/CENTER WAVELENGTH


Parameter

ALGO

Procedure


The xdB notch width (xdB_Notch_Width) of each channel and its center wavelength/ frequency (Center_Wavelength) are determined according to the settings of the parameter ALGO.






The width (xdB_Notch_Width) between the two points, which are above the bottom level of each channel by the parameter THRESH_LEVEL, and its center wavelength (Center_ Wavelength) are determined.





The width (xdB_Notch_Width) between the two points, which are below the higher point of either the left peak level or the right peak level of each channel by the parameter THRESH_LEVEL, and its center wavelength/frequency (Center_Wavelength) are determined.




Parameter THRESH

Procedure

The width (xdB_stop-Band) that centers on the nominal wavelength λi of each channel and that is located below by the parameter THRESH_LEVEL both on the left and on the right is determined.


XdB_ELIMINATION BAND



Parameter THRESH TEST BAND

- A peak search is performed within the range of the parameter Test_Band/2 by centering on the nominal wavelength λi of a channel, and the peak level (LPi) is determined.
- The width (xdB_Elimination_Wavelength) that is above the peak level LPi obtained in the above procedure by the parameter THRESH_LEVEL both on the left and on the right is determined.






Parameter

TEST BAND

- A peak search and bottom search are performed within the range of parameter Test_ Band/2 by centering on the reference wavelength λi of each channel, and the peak level (LP'i) and the bottom level (LB'i) are determined.
- The peak level (LP'i)and bottom level (LB'i) obtained in the above procedure is used to obtain the ripple (Ripple) from the following equation: Ripple = LP'i – LB'i




Parameter SPACING TEST BAND

- A peak search is performed within the range of parameter Test_Band/2 while centering on the reference wavelength λi of each channel, and the peak level (LP"i) is determined.
- A bottom search is performed within the range of parameter Test_Band/2 while centering on the point (λi-λSP) that is obtained by subtracting the parameter SPACING (λSP) from the reference wavelength λi of each channel. Then, the bottom level (LPLi) is determined.
- A bottom search is performed within the range of parameter Test_Band/2 while centering on the point (λi+λSP) that is obtained by subtracting the parameter SPACING (λSP) from the reference wavelength λi of each channel. Then, the bottom level (LPRi) is determined.
- The values obtained in the above procedure are used to obtain the left and right cross talks (XTLi, XTRi) of each channel from the following equations:
 XTLi = LP"i LPLi
 XTRi = LP"i LPRi

Appendix 7 Function Menu Tree Diagram

The menu structure of the instrument is illustrated below. Some menus have been omitted.

SWEEP




CENTER

Center Wavelength 1553.200nm	Sets the center wavelength (frequency) (3.5, 5.11)
Start Wavelength 1543.200nm	Sets the measurement start wavelength (frequency) (3.5, 3.6)
Stop Wavelength 1563.200nm	Sets the measurement stop wavelength (frequency) (3.5, 3.6)
Peak WL -> Center Mean WL -> Center	Sets the center wavelength (frequency) to the peak wavelength (frequency) (1.2, 3.5)
Auto Center <u>OFF</u> ON	Sets the center wavelength (frequency) to the RMS 20 dB center wavelength of the measured waveform (1.2, 3.5)
View Scale	Sets the center wavelength (frequency) to the peak wavelength (frequency) for each sweep (3.5)
Center	Assigns the current scale to the measurement scale of the next sweep (1.2, 3.5)

SPAN


Span Wavelength 20.0nm	Sets the sweep span (3.6, 5.11)
Start Wavelength 1543.200nm	Sets the measurement start wavelength (frequency) (3.5, 3.6)
Stop Wavelength 1563.200nm	Sets the measurement stop wavelength (frequency) (3.5, 3.6)
Δλ -> Span	Sets the sweep span to RMS 20dB width of the measured waveform × 6 (1.2, 3.6)
Time 2sec	Sets the screen range measurement time for 0 nm sweep (5.11)
View Scale -> Measure	Assigns the current scale to the measurement scale of the next sweep (1.2, 3.5)
Span	

LEVEL




- 1 Reference level setting (3.1, 3.4)
- 2 LOG scale setting (3.2, 3.4)
- 3 Linear scale setting (3.2, 3.4)
- 4 Linear scale bottom settings (3.2)
- 5 Setting the peak level to the reference level (1.2, 3.4)
- 6 Automatic setting of reference level (3.4)
- 7 Vertical scale unit setting (3.2)
- 8 Initialization of the main vertical scale (3.2)
- 9 Setting the sub scale to LOG (3.3)
- 10 Setting the sub scale to LINEAR (3.3)
- 11 Setting the sub scale to dB/km (3.3)
- 12 Setting the sub scale to % (3.3)
- 13 Linear subscale bottom setting or offset level setting for LOG (3.3)
- 14 Optical fiber length setting (3.3)
- 15 Automatic scaling of subscale (3.3)
- 16 Initialization of the sub vertical scale (3.3)
- 17 Number of divisions in the level axis (3.2)
- 18 Reference level position on the screen (3.2)
- 19 Reference level position on the sub scale (3.3)

SETUP




- 1 Measurement resolution setting (3.7, 5.11 in this manual, 4.4 in IM AQ6360-02EN)
- 2 Measurement sensitivity (3.9)
- 3 Average times setting (3.11)
- 4 Automatic sampling points setting (3.7, 3.8)
- 5 Manual sampling points setting (3.8)
- 6 Sampling interval setting (3.8)
- 7 Air wavelength/vacuum wavelength mode (3.2)
- 8 Sweep speed setting (3.10)
- 9 Horizontal scale unit setting (3.2)
- 10 Smoothing (3.16)
- 11 Fiber connector setting (2.5 in IM AQ6360-02EN)

ZOOM




- 1 Setting the center wavelength (frequency) of the zoom display (4.1)
- 2 Setting the span of the zoom display (4.1)
- 3 Setting the start point of the zoom display (4.1)
- 4 Setting the stop point of the zoom display (4.1)
- 5 Setting the peak position to the center of the zoom display (1.2, 4.1)
- 6 Assigning the current scale to the measurement scale of the next sweep (1.2, 3.5)
- 7 Initializing the display scale (4.1)
- 8 Setting the display position of the overview (4.1)
- 9 Setting the size of the overview (4.1)

DISPLAY



- 1 Normal display (4.10)
- 2 Split display (4.10)
 - 2-1 Display position setting (4.10)
 - 2-2 Display position fixing (4.10)
- 3 Label setting (3.3 in IM AQ6360-02EN)
- 4 Noise mask setting (4.11)
- 5 Mask method setting (4.11)
- 6 Trace clearing (4.12)
- 7 Turning the display off (7.7)

TRACE(More 1/2)




- Active trace setting (3.12, 4.2 to 4.8, 5.8, 5.9)
- 2 Show/hide active trace setting (3.12, 4.2 to 4.8, 5.8, 5.9)
- 3 Setting active trace to write mode (3.12, 4.2, 5.8, 5.9)
- 4 Setting active trace to fix mode (4.2, 5.8, 5.9)

1


- 5 Setting active trace to MAX/MIN hold mode (4.3)
- 6 Setting active trace sweeping to average mode (4.4)
- 7 Trace-to-trace calculation settings (trace C, F, G only) (4.5 to 4.8, 5.9)
 - 7-1 Trace-to-trace calculation in LOG (4.5, 5.9)
 - 7-2 Trace-to-trace calculation in LIN (4.5)
 - 7-3 Power density display (trace F only) (4.5, 4.8)
 - 7-4 Trace normalization (trace G only) (4.5, 4.6)
 - 7-5 Trace curve fitting (trace G only) (4.5, 4.7)
 - 7-6 Trace peak curve fitting (trace G only) (4.5, 4.7)
- 8 Trace condition list display (4.12)

TRACE(More 2/2)




- 1 Copy trace (4.12)
 - 1-1 Copy source trace setting (4.12)
 - 1-2 Copy target trace setting (4.12)
 - 1-3 Execute copy (4.12)
- 2 Trace clearing (4.12)

MARKER



- 1 Moving marker display on/off (4.9)
- 2 Setting moving markers to fixed markers (4.9, 4.13)
- 3 Clearing fixed markers (4.9, 4.13)
- 4 Setting the moving marker wavelength (frequency) to measurement center (1.2, 3.5, 4.9)
- 5 Setting the moving marker wavelength (frequency) to display scale center (1.2, 4.9)
- 6 Setting the moving marker level to reference level (1.2, 3.4, 4.9)
- 7 Advanced marker display (4.9)
 - 7-1 Advanced marker display on/off (4.9)
 - 7-2 Sets advanced markers (4.9)
 - 7-2-1 Selects the trace to assign the marker to (4.9)
 - 7-2-2 Sets moving markers (4.9)
 - 7-2-3 Sets power spectral density markers (4.9)
 - 7-2-4 Sets integrated power markers (4.9)
 - 7-2-5 Sets integration wavelength range (4.9)
 - 7-3 Executes a search based on advanced markers (4.9)
 - 7-3-1 Executes a peak search (4.9)
 - 7-3-2 Executes a bottom search (4.9)
 - 7-3-3 Sets the advanced marker from the current position to the next peak or bottom value (4.9)
 - 7-3-4 Sets the advanced marker from the current position to the next local peak or bottom value on the right (4.9)
 - 7-3-5 Sets the advanced marker from the current position to the next local peak or bottom value on the left (4.9)
- 8 Clear all displayed moving and fixed markers (4.9, 4.13)
- 9 Line markers on/off (4.9)
- 10 Setting the measurement span to between line markers L1 and L2 (1.2, 3.6, 4.9)
- 11 Setting the zoom span to between line markers L1 and L2 (1.2, 4.9)
- 12 Clear all displayed line markers (4.9)
- 13 Marker display settings (4.9)
- 14 Setting whether to automatically update the fixed marker's level values when updating active trace (4.9)
- 15 Marker value units setting (4.9, 5.10)
- 16 Setting the peak search, bottom search, and analysis function ranges to between line markers L1 and L2
 - (For both the PEAK SEARCH and ANALYSIS menus) (4.13, 5.12)
- 17 Setting the peak search, bottom search, and analysis function ranges to within the zoom range
- (For both the PEAK SEARCH and ANALYSIS menus) (4.13, 5.12)
- 18 Sweep between line markers (3.14)

PEAK SEARCH




- 1 Executing peak search (4.13)
- 2 Executing bottom search (4.13)
- 3 Moving the moving marker from the current position to the next peak/bottom value (4.13)
- 4 Moving the moving marker from the current position to the next peak/bottom value to the right (4.13)
- 5 Moving the moving marker from the current position to the next peak/bottom value to the left (4.13)
- 6 Setting the moving marker to the fixed marker (4.9, 4.13)
- 7 Clearing fixed markers (4.9, 4.13)
- 8 Clearing all displayed moving and fixed markers (4.9, 4.13)
- 9 Turning on/off peak/bottom search each sweep (4.13)
- 10 Setting the minimum peak/bottom difference of the mode judgment reference (4.13, 5.6)
- 11 Setting the peak search, bottom search, and analysis function ranges to between line markers L1 and L2

(For both the MARKER and ANALYSIS menus) (4.13, 5.12)

- 12 Setting the peak search, bottom search, and analysis function ranges to within the zoom range
 - (For both the MARKER and ANALYSIS menus) (4.13, 5.12)
- 13 Switching between the single and multi peak/bottom searches (4.13, 4.14)
- 14 Setting the threshold and sort order of the multi search (4.14)

ANALYSIS




- 1 Spectrum width analysis algorithm settings/execution (5.1, 5.2)
- 2 Analysis function settings (5.3 to 5.6)
 - (DFB-LD, FP-LD, LED, SMSR, POWER, PMD)
- Analysis function settings (5.7 to 5.9)
 (WDM, EDFA-NF, FILTER-PK, FILTER-BTM, WDM FIL-PK, WDM FIL-BTM)
- 4 Executing the specified analysis (chapter 5)
- 5 Spectrum width analysis threshold setting (5.1)
- 6 Analysis parameter settings (5.1 to 5.9)
- 7 Editing the ANALYSIS2 analysis results display screen (5.7 to 5.9)
- 8 Turning on/off automatic analysis each sweep (5.1)
- 9 Saving analysis results (5.1)
 - 9-1 Setting the save destination (6.5)
 - 9-2 Setting a file name (6.5)
 - 9-3 Setting overwrite or add (6.5)
 - 9-4 Creating a directory (6.5)
 - 9-5 Sort files (6.5)
 - 9-6 Executing saving (6.5)
- 10 Setting the peak search, bottom search, and analysis function ranges to between line markers L1 and L2

(For both the MARKER and PEAK SEARCH menus) (4.13, 5.12)

11 Setting the peak search, bottom search, and analysis function ranges to within the zoom range


(For both the MARKER and PEAK SEARCH menus) (4.13, 5.12)

FILE




- 1 Saving data (chapter 6)
 - 1-1 Setting the save destination for trace data (6.2)
 - 1-2 Setting a file name (6.2)
 - 1-3 Setting the trace to save (6.2)
 - 1-4 Setting the data format (6.2)
- 2 Loading data (chapter 6)
 - 2-1 Setting the loading source for trace data (6.2)
 - 2-2 Setting the loading destination trace (6.2)
 - 2-3 Switching list/thumbnail display (6.2)
- 3 Setting the target item (chapter 6)
- 4 Setting the method of assigning file names (6.2)
- 5 Removing the USB storage medium (6.1 in this manual, 2.3 in IM AQ6360-02EN)
- 6 File operation (6.8)
 - 6-1 Setting the target storage device (6.8)
 - 6-2 Deleting a file (6.8)
 - 6-3 Copying a file (6.8)6-3-1 Setting the paste destination (6.8)
 - 6-3-2 File name when saving to separate name (6.8)
 - 6-4 Renaming (6.8)
 - 6-5 Creating a directory (6.8)
 - 6-6 Sorting files (6.8)
 - 6-7 File selection (6.8)





ALL TRACE

- 1 Save destination setting for all trace data (6.3)
- 2 Setting a file name (6.3)
- 3 Load source setting for all trace data (6.3)




SETTING

- 1 Setting the save destination for settings (6.4)
- 2 Setting a file name (6.4)
- 3 Setting the loading source for settings (6.4)

DATA

- 1 Setting the save destination for analysis results data (6.5)
- 2 Setting a file name (6.5)
- 3 Setting the items to save (6.5)
- 4 Setting overwrite or add (6.5)
- 5 Setting the loading source for analysis results data (6.5)

Appendix 7 Function Menu Tree Diagram




PROGRAM

- 1 Setting the save destination for program data (6.6)
- 2 Setting a file name (6.6)
- 3 Switching the cursor target window (6.6) (setting the source/destination program number)
- 4 Setting the loading source for program data (6.6)
- 5 Switching the cursor target window (6.6) (setting the source/destination load file)

GRAPHIC


- 1 Setting the save destination for image data (6.7)
- 2 Setting a file name (6.7)
- 3 Color mode setting (6.7)
- 4 Data format setting (6.7)

PROGRAM (see IM AQ6360-17EN)




- 1 Program execution
 - 1-1 Program execution
 - 1-2 Registering programs to function menus
- 2 Editing programs
 - 2-1 Entering program names
 - 2-2 Editing lines
 - 2-2-1 Setting program lines
 - 2-2-2 Setting function commands
 - 2-2-3 Editing parameters
 - 2-2-4 Finalizing input values
 - 2-2-5 Special command settings
 - 2-2-6 Cutting/pasting lines
 - 2-2-6-1 Inserting lines
 - 2-2-6-2 Setting the target area
 - 2-2-6-3 Deleting an area
 - 2-2-6-4 Copying an area
 - 2-2-6-5 Pasting (inserting)
 - 2-2-6-6 Pasting (overwriting)
 - 2-3 Printing program lists
 - 2-3-1 Overwriting
 - 2-3-2 Copying and adding contents (merge)
- 2-4 Deleting programs
- 3 OUTPUT WINDOW display
 - 3-1 Closing the OUTPUT WINDOW
- 4 Executing programs registered to function menus

SYSTEM(More 1/4)




- 1 Wavelength calibration (2.6)
 - 1-1 Wavelength calibration using the internal light source (2.6)
 - 1-2 Wavelength calibration using a laser type external reference light source (2.6)
 - 1-3 Wavelength calibration using a gas cell type external reference light source (2.6)
 - 1-4 Wavelength calibration using an emission line type external reference light source (2.6)
 - 1-5 Wavelength calibration setting for wavelength calibration using an external reference light source (2.6)
 - 1-6 Executing wavelength calibration (2.6)
 - 1-7 Using the built-in reference light source of the AQ6370 series or the AQ6360 (2.6)
- 2 Setting the wavelength shift amount (value specified for the wavelength axis display value is added) (5.13)
- 3 Setting the level shift amount (value specified for the level axis display value is added) (5.13)
- 4 Editing the grid table (5.10)
 - 4-1 Creating a grid table with predetermined grid spacing (5.10)
 - 4-2 Creating a custom grid table (an arbitrary grid table) (5.10)
 - 4-2-1 Setting the start wavelength of the custom grid (5.10)
 - 4-2-2 Setting the stop wavelength of the custom grid (5.10)
 - 4-2-3 Setting the frequency spacing of the custom grid (5.10)
 - 4-2-4 Setting channel point wavelength of the custom grid (5.10)
 - 4-2-5 Inserting channel points of the custom grid (5.10)
 - 4-2-6 Deleting channel points of the custom grid (5.10)
 - 4-2-7 Finalizing input values of the custom grid (5.10)
 - 4-3 Setting the grid table reference wavelength (5.10)
- 5 Registering user keys (7.2)

SYSTEM(More 2/4)



- 1 Communication interface settings (see IM AQ6360-17EN)
- 2 GP-IB interface settings (see IM AQ6360-17EN)
 - 2-1 Setting the GP-IB port address
 - 2-2 Setting the command format
- 3 Ethernet interface settings (see IM AQ6360-17EN)
- 4 Auto offset ON/OFF (7.7)
- 5 Remote monitor (7.7)
- 6 Director sharing setting (7.7)
- 7 Firewall setting (7.7)

SYSTEM(More 3/4, More 4/4)



- 1 UNCAL, warning display on/off (7.7)
- 2 Buzzer settings (7.7)
- 3 Setting the number of level data digits (7.1)
- 4 Semitransparent display on/off (7.1)
- 5 Language setting (7.7)
- 6 Date/time setting (3.5 in IM AQ6360-02EN)
- 7 Setting the display color (7.1)
- 8 Locking the operation key and changing the password for operation lock (7.6)
- 9 Removing the USB storage medium (6.1 in this manual, 2.3 IM AQ6360-02EN)
 10 System information display (7.8)
 - System information display (7.8) 10-1 Displaying the serial number, Ethernet port MAC address, and other items (7.8) 10-2 Displaying, clearing, and saving the system log to USB memory (7.8)
- 11 Keyboard display setting (7.7)
- 12 Performs rms resolution calibration (2.2)
 - 12-1 Executes calibration (2.2)
 - 12-2 Clears the calibration value (2.2)
- 13 Initialize the settings (7.3)
- Displaying the version and updating the software (4.1 in IM AQ6360-02EN)14-1 Displaying the patch list
 - 14-2 Updating the firmware (via network) (4.1 in IM AQ6360-02EN)
 - 14-3 Updating the firmware (USB memory) (4.1 in IM AQ6360-02EN)
- 15 Service menu (7.7)
- 16 System shutdown (2.4 in IM AQ6360-02EN)

Index

Numerics	Page
0nm Sweep Time	5-47

Α	Page
ABSOLUTE	App-26
absolute level accuracy	5-53
active trace	3-33, 4-9
Active TraceABCDEFG	3-33
ADD	6-30
Advanced Marker	4-37
advanced markers	4-37
ALGO	5-38
algorithms for spectral width analysis	5-3
All Clear	
All Marker Clear	
ANALYSIS	App-59
analysis between line markers	5-48
analysis in the zoom area	
ASE ALGO	
ASE level measurement parameters	5-28
AUTO-CTR	App-24, App-33
AUTO-FIX	App-23, App-33
automatic offset	
automatic optical amp parameter setting	App-33
automatic WDM parameter setting	App-23
auto measurement	1-2, 3-1
auto search	4-56, 4-58
Auto Search ON/OFF	4-58
Average Times	3-31
average times, setting	
averaging	3-31

В	Page
bottom search	4-57
Bottom Search	4-57, 4-61
buzzer, setting	

C	Page
calculation mode	4-15
Cal Data Clear	
CENTER	App-51
center wavelength (center frequency), setting	3-16
Clear Marker Clear	4-57
CSV data format	6-9
curve fit target range	4-26
curve fitting	4-21, 4-24
curve fitting algorithm	4-26
custom grid table	5-44

D	Page
data format	6-31
device analysis	1-5
DFB-LD analysis	App-16
DISPLAY	App-54
display color, changing	
DISPLAY MASK	
Display Off	
display, turning off	
DISPLAY TYPE	
DRIFT(GRID)	App-29

DRIFT(MEAS)	App-28
DUAL TRACE	5-19, App-25

E	Page
EDFA-NF analysis parameters ENVELOPE (envelope curve) method extension	Арр-4

<u>F</u>	Page
FILE	App-60
file name	6-8, 6-24, 6-29
files, sorting	6-9, 6-24
filter bottom analysis	5-32, App-37
filter peak analysis	5-30, App-34
firewall	
Firewall	
FITTING ALGO	5-19, 5-28
FITTING AREA	5-28
Fix @	3-33, 4-8
fixed markers	4-30
fix mode	3-33, 4-9
FP-LD	5-11
FP-LD analysis	App-17
frequency	

G grid

G	Page
grid table	5-44, App-1

Н	Page
hold Hold HRZN	4-50

1	Page
interpolation algorithms	5-28
interval	3-28

L	Page
language	7-23
Language	7-23
LED	
LED analysis function	App-18
LEVEL	App-52
level accuracy	
level line markers	4-36
Level Shift ***.***dB	5-53
Linear Math	
linear scale	3-14
linear scale display, changing to	3-3
line markers	
Log Math	
log scale	3-14
log scale display, changing to	3-3

Index

M	Page
MARKER	App-57
markers	
MASK AREA	5-19, 5-28
maximum/minimum value, holding	4-10
MAX/MIN HOLD mode	4-10, 4-11
measurement sensitivity and effective ver	rtical scale range 3-6
Mode Diff	4-58, 5-18, 5-27, 5-40
moving markers	

Ν

N	Page
Next Level Search	4-57
Next Search Left	4-57
Next Search Right	
NOISE ALGO	
NOISE AREA	5-19
NOISE BW	5-19
noise mask	4-51
noise mask type	4-52
Normalize	4-19
normalized display	4-19
notch width measurement 1-	
NOTCH width measurement	App-9
number of displayed decimal places, setting	7-1
number of vertical scale divisions, setting	
numerical aperture and level errors 2-11	

0	Page
OFFSET	
one-action key	1-2
one-action keys	. 3-15, 3-19, 3-24
optical amplifier analysis	1-5, 5-22
optical fiber cable type	2-11
optical filter characteristics measurement	1-5, 5-30
OUTPUT SLOPE	5-21, App-25
OVER	6-30
overview	4-4

Ρ

<u>P</u>	Page
Parameter Clear	
Parameter & Data Clear	
peak curve fitting	4-23, 4-25
PEAK RMS method	App-8
peak search	4-57
Peak Search	4-57, 4-61, App-58
PIT	App-24
PMD analysis	App-15
PMD measurement	
POINT DISPLAY	5-21, 5-29
power analysis	App-14
power measurement between line markers	5-48
power measurement in the zoom area	5-49
power spectral density display	3-7
PROGRAM	App-63
pulse light measurement	3-36

R Page reference level, setting 3-12 Reference Wavelength 5-44 RELATIVE App-27 repeat sweep 1-2, 3-34 ripples 2-12, App-36 ripples in the 1350 to 1450 nm area..... 3-26 RMS method..... App-7 ROLL AVG mode 4-13

S	Page
sampling points	. 3-27, 3-28
screen, splitting	4-49
Search / Ana Marker L1-L2 OFF / ON	4-58
Search / Ana Zoom Area OFF / ON	4-58
second order diffraction light	2-12
sensitivity, setting	
Set Marker Set	
SETUP	App-53
single sweep	
SMSR	5-8
SMSR analysis	App-11
Sort by	
Spacing	5-44
SPAN	App-51
spectral width analysis	
Spec Width Thresh	
split display	
standard grid table	
sub scale, auto scaling	3-8
sub scale, displaying	
sub scale REF position, setting	
sweep	
SWEEP	App-51
sweeping between line markers	
Sweep Interval	
sweep span, setting	3-21
Sweep Speed	
SYSTEM	

Т

U

TEST BAND	
THRESH LEVEL	5-18, 5-27, 5-40
THRESH method	App-2
Threshold	4-61
trace	3-32
TRACE	App-55
traces, copying	4-53
trace-to-trace calculations	4-15
transparent display	7-1

Page "UNCAL", conditions that cause it to be displayed 3-26, 3-28 UNCAL mark, displaying 7-21 "UNCAL", what to do when displayed...... 3-25 USB storage device, removing 6-1

V Page vertical scale unit, setting 3-4 View @...DISP / BLANK 3-33

Page

۱۸/

W	Page
warning display	
waveform, zooming	4-1
wavelength in air	
wavelength in vacuum	3-2
wavelength line markers	4-34
Wavelength Shift **.**nm	5-53
WDM analysis	
WDM analysis parameters	
WDM filter analysis parameters	5-38
WDM filter bottom analysis	5-35, App-45
WDM filter peak analysis	5-33, App-39
Write @	3-33, 4-8
write mode	3-33, 4-9
_	_

<u>Z</u>	Page
zoom	
ZOOM	App-54

Index Index